GENERAL NOTES

- GN # 1 Driveway locations shall not interfere with the sidewalk handicap ramps, or curb injet sumps
- GN # 2 Sidewalks, curb ramps, ramps and accessible parking spaces shall be constructed in accordance with the current approved "American with Disabilities Act Accessibility Guidelines" (ADAAG) along with the required grades, construction materials, specifications and signage. If any conflict occurs between the above information and the plans, the ADAAG guidelines shall take precedence and the contractor prior to any construction shall notify the Project Engineer.
- GN # 3 Truncated domes for curb ramps located in public right of way shall meet ADA requirements and shall be constructed using red pre cast truncated domes per pavement details.
- GN # 4 Any proposed pavilions or playground areas will need a separate permit from the Building Division.
- GN # 5 The Contractor is responsible to call Missouri One Call and The City of O'Fallon for the location of utilities. Contact the City of O'Fallon (636) 379-3814 for the location of City maintained cable for street lights and traffic signals, all other utilities call Missouri One Call 1-800-DIG-RITE. 1-800-344-7483
- GN # 6 All proposed utilities and/or utility relocations shall be located underground.
- GN # 7 All proposed fencing requires a separate permit through the Planning and Development Division.
- GN # 8 All construction operations and work zone traffic control within the right of way will follow MoDOT or M.U.T.C.D. standards whichever is more stringent.
- GN # 9 All free standing signs shall be located a minimum of ten (10) feet away from any right of way line and/or property line and a minimum of three (3) feet from the back of curbing or sidewalk. All signs shall abide by the regulations for visibility at corners, including corners from driveways and the street it intersects per Section 400.260 of the O'Fallon Zoning Code.
- GN #10 All subdivision identification or directional sign(s) must have the locations and sizes approved and permitted separately through the Planning and Development Division.
- GN #11 Materials such as trees, organic debris, rubble, foundations, and other deleterious material shall be removed from the site and disposed of in compliance with all applicable laws and regulations. If the material listed previously are reused, a letter from a soil Engineer must clarify amount, location, depth. ect. and be approved with the construction plans. Landfill tickets for such disposal shall be maintained on file by the developer. Burning on site shall be allowed only by permit from the local fire district. If a burn pit is proposed the location and mitigation shall be shown on the grading plan and documented by the soils engineer.
- GN #12 Twenty-four (24) hours prior to starting any of the work covered by the above plans and after approval thereof, the developer shall make arrangements with the Construction Inspection Office to provide for inspection of the work, sufficient in the opinion of the City Engineer, to assure compliance with the plans and specifications as approved.
- GN #13 The City Engineer or their duly authorized representative shall make all necessary inspections of City infrastructure, escrow items or infrastructure located on the approved plans.

EROSION CONTROL NOTES

- EN # 1 The Permittee shall assume complete responsibility for controlling all siltation and erosion of the project area. The Permittee shall use whatever means necessary to control erosion and siltation including, but not limited to, staked straw bales and/or siltation fabric fences (possible methods of control are detailed in the plan). Control shall commence with the clearing operations and be maintained throughout the project until acceptance of the work by City of O'Fallon and as needed by MoDOT. The Permittee's responsibilities include all design and implementation as required to prevent erosion and the depositing of silt. The City of O'Fallon and as required by MoDOT may at their option direct the Permittee in his methods as deemed fit to protect property and improvements. Any depositing of silt or mud on new or existing pavement shall be removed immediately. Any depositing of silts or mud in new or existing storm sewers and/or swales shall be removed after each rain and affected areas cleaned to the satisfaction of the City of O'Fallon and as required by MoDOT."
- EN # 2 All erosion control systems are to be inspected and corrected weekly, especially within 48 hours of any rain storm resulting in one-half inch of rain or more. Any silt or debris leaving the site and affecting public right of way or storm water drainage facilities shall be cleaned up within 24 hours after the end of the storm.
- EN # 3 Erosion control devices (silt fence, sediment basin, etc.) shall be in accordance with St. Charles County Soil and Water Conservation District Erosion and Sediment Control guidelines.
- EN # 4 This development is required to provide long term post construction BMP's such as; low impact design, source control and treatment controls that protects water quality and controls run off to maximum extent practical in compliance with Phase II Illicit Storm Water Discharge Guidelines. (Ord. 5082, section 405.0245)
- EN #5 Graded areas shall be seeded and mulched (strawed) within 14 days of stopping land disturbance activities. Unless it can be shown to the City Engineer that weather conditions are not favorable, vegetative growth is to be established within 6 weeks of stopping grading work on the project. The vegetative growth established shall be sufficient to prevent erosion and the standard shall be as required by EPA and DNR. (70% coverage per square foot) Ord. 5242. Section 405.070

GRADING NOTES

- GRN #1 Developer must supply City construction inspectors with soil reports prior to and during site grading. The soil report will be required to contain the following information on soil test curves (Proctor reports) for projects within the City:
 - 1. Maximum dry density
 - 2. Optimum moisture content
 - 3. Maximum and minimum allowable moisture content
 - 4. Curve must be plotted to show density from a minimum of 90% Compaction and above as determined by the "Modified AASHTO T-180 Compaction Test" (A.S.T.M.-D-1157) or from a minimum of 95% as determined by the "Standard Proctor Test ASSHTO T-99, Method C" (A.S.T.M.-D-698). Proctor type must be designated on document.
 - 5. Curve must have at least 5 density points with moisture content and sample locations listed on document 6. Specific gravity
 - 7. Natural moisture content
 - 8. Liquid limit 9. Plastic limit
 - Be advised that if this information is not provided to the City's Construction Inspector the City will not allow grading or construction activities to proceed on any project site.
- GRN #2 All fill placed in areas other than proposed storm sewers, sanitary sewers, proposed roads, and paved areas shall be compacted from the bottom of the fill up in 8" lifts and compacted to 90% maximum density as determined by Modified AASHTO T-180 compaction test or 95% of maximum density as determined by the Standard Proctor Test AASHTO T-99. Ensure the moisture content of the soil in fill areas corresponds to the compactive effort as defined by the Standard or Modified Proctor Test. Optimum moisture content shall be determined using the same test that was used for compaction. Soil compaction curves shall be submitted to the City of O'Fallon prior to the placement of fill.
- GRN # 3 The surface of the fill shall be finished so it will not impound water. If at the end of a days work it would appear that there may be rain prior to the next working day, the surface shall be finished smooth. If the surface has been finished smooth for any reason, it shall be scarified before proceeding with the placement of succeeding lifts. Fill shall not be placed on frozen ground, nor shall filling operations continue when the temperature is such as to permit the layer under placement to freeze.
- GRN # 4 All sediment and detention basins are to be constructed during the initial phase of the grading operation or in accordance with the approved SWPPP.
- GRN # 5 When grading operations are complete or suspended for more than 14 days, permanent grass must be established at sufficient density to provide erosion control on site. Between permanent grass seeding periods, temporary cover shall be provided according to St. Charles Soil and Water Conservation District - Model Sediment and Erosion Control Regulations. All finished grades (areas not to be disturbed by improvements) in excess of 20% slopes (5:1) shall be mulched and tacked at a rate of 100 pounds per 1000 square feet when seeded.
- GRN # 6 No slopes shall exceed 3 (horizontal): 1 (vertical) unless otherwise approved by the soils report and specifically located on the plans and approved by the City Engineer.
- GRN # 7 All low places whether on site or off shall be graded to provide drainage with temporary ditches.
- GRN # 8 All existing wells on site shall be capped per DNR standards.



UNDERGROUND UTILITIES AND STRUCTURES HAVE BEEN PLOTTED FROM AVAILABLE INFORMATION AND THEREFORE, THEIR LOCATION MUST BE CONSIDERED APPROXIMATE ONLY, IT IS THE RESPONSIBILITY OF THE INDIVIDUAL CONTRACTORS TO NOTIFY THE UTILITY COMPANIES BEFORE ACTUAL CONSTRUCTION.

GRADING NOTES CONTINUED

GRN #10 All trench back fills under paved areas shall be granular back fill, and compacted mechanically. All other trench back fills may be earth material (free of large clods, or stones) and compacted using either mechanical or water jetting, Granular material and earth material associated with new construction outside of pavernents may be jetted, taking care to avoid damage to newly laid sewers. The jetting shall be performed with a probe route on not greater than 7.5 foot centers with the jetting probe centered over and parallel with the direction of the pipe. Trench widths greater than 10 feet will require multiple probes every 7.5 foot centers.

- a) Depth, Trench back fills less than 8 feet deep shall be probed to a depth extending half the depth of the trench back fill, but not less than 3 feet. Trench back fill greater than 8 feet in depth shall be probed to half the depth of the trench back fill but not greater than
- b) Equipment, The jetting probe shall be a metal pipe with an interior diameter of 1.5 to 2 inches.
- c) Method, Jetting shall be performed from the lowest surface topographic point and proceed toward the highest point, and from the bottom of the trench back fill toward the surface. The flooding of each jetting probe shall be started slowly allowing slow saturation of the soil. Water is not allowed to flow away from the trench without first saturating the trench.
- d) Surface Bridging, The contractor shall identify the locations of the surface bridging (the tendency for the upper surface to crust and arch over the trench rather than collapse and consolidate during the jetting process). The contractor shall break down the bridged areas using an appropriate method such as wheels or bucket of a backhoe. When surface crust is collapsed, the void shall be back filled with the same material used as trench back fill and rejetted. Compaction of the materials within the sunken/jetted area shall be compacted such that no further surface subsidence occurs.

- a. Within City right-of-way. Material is to be placed in eight (8) inch to twelve (12) inch loose lifts and compacted per the approved compaction requirements. One (1) compaction test will be performed every two hundred fifty (250) feet along the centerline for each lift.
- b. Outside of City right-of-way. Material is to be placed in eight (8) inch to twelve (12) inch loose lifts and compacted per the approved compaction requirements. One (1) compaction test will be performed at two (2) foot vertical intervals and approximately every one thousand (1,000) cubic yards.

SANITARY SEWER NOTES

SAN # 1 All-penitary sewer inetallation is to be in accordance with M.S.D. 2007 standards and specifications except as modified by the City of C'Fallon

-SAN # 2 Brick shall not be used in the construction of sanitary sewer structures. Pre cast concrete structures are to be used unless otherwise approved

by the City of C'Fallen. SAN # 3 Connections at all sanitary structures are to be made with A Lock joint or equal

-SAN # 4 All sanitary laterals shall be a minimum of 4" residential, 6" commercial diameter pipe.

SAN # 5 All sanitary mains shall be a minimum of 8" diameter pipe.

-SAN-# 6 All canitary cower line with a clope greater than 20% will require concrete cradle or concrete collar. Sanitary line with a clope greater than 50% will require a special approved design as shown on detail sheet.

SAN # 7 All manheles built within the 100 year flood plain must have leek type watertight manhele covers.

SAN # 8 All sanitary sewer mains must have a minimum of 42" cover. SAN # 9 When sanitary mains cross over storm line the sanitary main must be ductile iron pipe for 10 feet on each side of the crossing.

SAN #10 Encase with concrete both sunitary and storm sewer at crossing when storm sewer is within 18 inches above sunitary sewer. Add concrete cradle

to only RCP aterm sewer and energed HDPE storm sewer when it is more than 18 inches above canitary line. Show on profile cheet SAN #11 The sanitary sewers should run diagonally through the side yards to minimize any additional utility easements required.

SAN #12 All sanitary sewer structures shall be waterproofed on the exterior in accordance to Missouri DNR specifications 100SR 8.120 (7)(E). SAN #13 All sanitary sewer pipe shall be SDR35 or equal.

-SAN-#14 All canitary sower manheles and pipes will be tested to the following openifications. ASTM C1241. Standard testing method for Concrete Sower Manhole by Negative Air Pressure (Vacuum), Latest revision ASTM F1417, Standard teating method for Installation Acceptance of Plastic Gravity Sewer Lines Using Lew Pressure Air, Latest revision.

SAN #15 Add 1" minus rock back fill to all sanitary sewer and all other utilities that lie within the 1:1 shear plane of the road.

STORM SEWER NOTES

-STM # 1 All Storm Sewer installation is to be in accordance with M.S.D. 2007 standards and specifications except as modified by the City of O'Fallon

STM # 2 Brick shall not be used in the construction of storm sewer structures. Pro east concrete structures are to be used unless otherwise approved by the City of O'Fallon.

STM # 3 A 5/8" trash bar shall be installed horizontally in the center of the opening(s) in all ourb inlets and area inlets.

STM # 4 HDPE pipe is to be N 12WT or equal and to meet ASTM F1417 water tight field test. STM # 5 Encase with concrete both sanitary and storm sewer at crossing when storm sewer is within 18 inches above sanitary sewer. Add concrete cradie to only RCP storm sewer and encase HDPE storm sewer when it is more than 18 inches above sanitary line. Show on profile sheet.

-STM # 6 The storm sewers should run diagonally through the side yards to minimize any additional utility easoments required. STM # 7 All concrete pipes will be installed with 0 ring rubber type gaskets.

STM # 8 Connections at all storm structures are to be made with A lock joint or equal. STM # 9 Pre-cast concrete inlet covers are not to be used.

STM #10 The swale in the detention basins shall have a minimum 1% longitudinal slope and be lined with a permanent crosion control blanket that will allow infiltration of otorm water.

STM #11 All storm sewer shall be reinforced concrete pipe or H.D.P.E. pipe. All structures and flored end sections must be concrete. Manufacturing specifications must be followed and details provided for the installation of H.D.P.E. pipe. H.D.P.E. pipe will not be allowed for detention basin outflows, final pipe run to detention basins, creek discharge or other approved means.

STM #12 The discharge point of all flored end sections shall be protected by rip rap or other approved means. STM #13 Rip rap shown at flared and sections will be evaluated in the field by the Engineer, Contractor, and City Inspectors after installation for effectiveness and field modified, if necessary to reduce propien on and off site.

STM #14 Add 1" minus rock back fill to all storm sewer that lie within the 1:1 shear plane of the road.

WATER NOTES

- WN # 1 Fire hydrante shall be a maximum of 600' apart. Local fire district approval is required.
- -WN # 2 Coordinate with the water company on the leastion of water meters.
- WN # 3 All water main must have a minimum of 42" of cover. (City water mains)
- -WN # 4 Provide water valves to isolate the system.
- WN # 5 All water mains shall be class 200 SDR 21 or equal with locator/tracer wires -WN # 6 DISINFECTINO:

Disinfecting shall be accomplished by placing sufficient hypo chlorite granule (HTH) in each section of pipe to achieve a chlorine residual in the -pipeline, upon initial filling, of 50 mg/L (PPM). HT. tablete will-not be allowed. Following completion of the pipeline, it shall be clearly filled -with water and a cample will be taken immediately and the oblorine residual must be 50 mg/L or greater. The solution shall be allowed to stand for 24 hours and a sample shall then be taken. The chlorine residual after 24 hours shall be 30 mg/L or greater. If the piping shows insufficient -chlorine residuals in either test, the piping shall be re-chlorinated by the injection of hype-chlorite solution until satisfactory results are -achieved. All disinfecting shall be done by the centractor. Only the testing to determine the chlorine residual will be done by the City.

WN # 7 PRESSURE TESTING:

Immediately following disinffection, the piping chall be pumped to a procesure (at the lowest point in the project) of 150 poi or higher where the working proceure is higher than 150 PSI as determined by the City. In such cases, the proceure shall be as specified by the City and two proceure tests shall be conducted. The first test shall be with the first hydrant auxiliary valve open and be to 150 PSI. The escend test shall be with the fire hydrant auxiliary valve closed and be to the higher pressure as directed by the City. All pumping equipment and pressure gauges shall be previded by the contractor. After achieving the test pressure, the piping shall be left closed for a period of two (2) hours. At the end of this time the pressure drop shall not exceed 2 pair in addition, if the pressure appears, in judgment of the City's representative, to be continuing to drop, the test shall be continued for another two (2) hours and if any further drope secur, the test shall be considered a failure. If the pressure test faile, the contractor will be required to find and correct the course of the leakage. If this requires draining of the pipeline, when the lackage is corrected, the pipeline must be re-dicinfected and the procoure tooled again until actiofactory recult are gehioved. Any MDNR required dechlorination will be performed by the contractor.

WN # 8 All tops for valves, meters, and manholes are to be constructed to within 1 inch (0.08') of finish grade. Grading ground

atruoture tope on clopes need to be accounted for.

WATER NOTES

WN #10 DACTERIOLOGICAL TESTING:

After actisfactory dicinfection and precours testing, a cample shall be taken by the contractor in the precence of a City representative and submitted to a laboratory approved by the Missouri Department of Natural Resources and the City for bacteriological analysis. After 24 hours, a second cample shall be taken in a like manner and submitted for analysis. The two samples taken on consecutive days a minimum of 24 hours apart, must be found to be "oafe" by the testing laboratory, and espice of the test results must be supplied to the City. If the camples - are not found to be "safe" further flushing and/or disinfection as directed by the City shall be conducted by the contractor until "safe" samples "safe" the mains may be placed into service.

ROADWAY NOTES

City of O'Fallon ordinances. RN # 2 If the intersecting road does not have a curb, then the curb on the new entrance shall begin 10' from the edge of the existing road. RN # 3 Provide 6" of concrete over 4" of McDot type 1 or type 5 aggregate rock or asphalt equivalent for minor residential streets per City Code 405.370.

RN # 1 All paying (public and private) to be in accordance with 2006 St. Charles County Standards and Specifications except as modified by the

RN # 4 Multi-use trail (when required) Shall have a minimum of 3" Type "C" Asphalt ever 4" aggregate base per City requirements. RN # 5 Type C (BP 1) Compaction requirements shall be 98% minimum density according to \$t. Charles Go. Standard Specifications.

RN # 6 Provide pavement striping at any point where the multi-use trail crosses existing or proposed pavement RN # 7 All street stab-outs over 250' in length will require a temporary turnaround.

RN # 8 All sub-grade in cut or fill will need to conform to the City of O'Fallen Compaction requirements

- b. One (1) bulk density test per paying operation.

RN # 0 Material Testing And Frequency. Materials for construction shall be tested and inspected per the appropriate ASTM code or at the City Engineer's discretion. The developer's engineer shall perform the following quality control guidelines: - 1. Concrete.

a Cylinders/compressive strength. One (1) set of four (4) cylinders within the first fifty (50) cubic yards and one (1) set per one hundred (100) eubic yards thereafter. One (1) cylinder must be tested at seven (7) days, one (1) at fourteen (14) days and two (2) at twenty sight (28) days. If the first (1st) sylinder does not meet specifications at twenty eight (28) days, then the second (2nd) sylinder must be hold and tested b. Percent gir and temperature. First (1st) truck batch each day and two (2) thereafter until a consistency is ancountered. Once a consistency

is enseantered, then teets will be performed in conjunction with the concrete cylinders c. Slump. First (1st) truck batch each day and two (2) thereafter until a consistency is encountered. Once a consistency is encountered, then tests will be performed in conjunction with the concrete cylinders.

d. If concrete is batched from more than one (1) plant, then the aforementioned guidelines will be applicable to each pla

a. Proof roll as described in Section 405.210/P)

e. Cradation-test for sub-base material.

b. One (1) compaction test per two hundred fifty (250) feet of mainline paving, three (3) tests per intersection, five (5) tests within cul de seec and one (1) teet per reggir elab.

a. One (1) set of compaction tests per two hundred fifty (250) feet of mainline. One (1) set includes three (3) tests across the paved lane

RN #16 Utility Work Prior To Base Construction. No base course work may proceed on any street until all utility excavations (storm and sanitary sewers, water, gas, electric, etc.) have been properly back filled with granular material, crushed stone or gravel mechanically tamped in ten (10) inch

lifts. Utilities installed after sub grade preparation shall be bored. Compaction requirements shall follow St. Charles County standards (2006).

RN #17 Equipment adiibration. The developer's contractors and subcontractors must have their equipment adiibrated by the following minimum.

- b. Cylinder compression annually by independent calibration service.
- d. Nuclear testing devices—every six (6) months. e. Proeter equipment every six (6) menths.

RN #18 All permanent traffic control will be per M.U.T.E.D. or MoDet standards, S1 1 from the M.U.T.E.D. manual will be used at all processed ns accompanied with other w16-9p or w16-7p signs

RN #19 All traffic signals, street signs, sign post, backs and bracket arms shall be painted black using Carboline Rust Bond Penetrating Sealer SG and Carboline 133 HB paint (or equivalent as approved by City of O'Fallon and MoDOT).

FLOOD PLAIN INFORMATION

FP #1 A flood plan development application from the City is required for any work within the flood plan limits

RETAINING WALLS: TERRACED AND VERTICAL

-RW #1 A permit is required for all retaining walls that are 18 inches or taller in height, measured from the top of the feeting to the top of the wall or for - walls that support a surcharge load or that alters the channelized drainage of any lot or drainage area. RW #2 Retaining walls will not be allowed in public right of way without written approval from the City Engineer. RW #3 Any retaining wall more than thirty (30) inches tall which supports a walking surface that is within two (2) feet of the wall will require a quard

RW #4 Retaining walls that after the channeled drainage of any lot or drainage area shall not be constructed without prior approval and permitting from the City of O'Fallon Engineering Department regardless of the height of the wall.

-RW #5 Sec section 405.275 of the City code for additional design requirement

le a marking on the storm sewer inlets. The City will allow the following markers and adhesive procedures only as hown in the table below or an approved equal. Peel and stick, adhesive pads will not be allowed.

	Manufacturar	Sima	Adbasina	Style	Massage (Part #)	Wobsite	
	Trianaracear CI	SIEC	TRUMESTIC	Dey ke	MICOSUSC (I BITTH)	TO DOTE OF	
	A.CD International	2 7/9"	Unaver	Countral	No Demaine During	La contrata de la contrata del contrata de la contrata del contrata de la contrata del contrata de la contrata de la contrata de la contrata del contrata de la contrata del contrata de la contrata del contrat	<u> </u>
	TICI International	2.176	3. Poxy	Cijstai	140 Damping Diams	N. B. W. B. C. S. B. C.	
				Con	To Waterway		
				Cap	10 Hacel Ways		
	J		L		(CD W CC)		
					(SD W CC)		
	DAC Manufacturing Inc	A 22	Emparation	Ctandond	Na Damaina Dania	Marie Acare Societa Acatania a acare	
	Dito manufacturing, inc.		DOON	Diamaga	TW Dumping Diams	WWW.Companionerateronalist.	
				Style	To Stream (#SDS)	<u> </u>	
				1			

ALL EXISTING STORM SEWER INLETS SHALL INDICATE THAT NO WASTE IS TO BE DUMPED INTO THE EXISTING STORM

IF MATERIALS SUCH AS TREES, ORGANIC DEBRIS, RUBBLE, FOUNDATIONS AND OTHER DELETERIOUS MATERIAL ARE NOT TO BE REUSED, THEY SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN COMPLIANCE WITH ALL APPLICABLE LAWS AND REGULATIONS. IF THE MATERIALS LISTED PREVIOUSLY ARE RESUSED. A LETTER FROM A SOILS ENGINEER MUST CLARIFY AMOUNT, LOCATION, DEPTH, ETC AND BE APPROVED WITH THE CONSTRUCTION PLANS. LANDFILL TICKETS FOR SUCH DISPOSAL SHALL BE MAINTAINED ON FILE BY THE DEVELOPER. BURNING ON SITE SHALL BE ALLOWED ONLY BY PERMIT FROM THE LOCAL FIRE DISTRICT. IF A BURN PIT IS PROPOSED THE LOCATION AND MITIGATION SHALL BE SHOWN ON THE GRADING PLAN AND DOCUMENTED BY THE SOILS ENGINEER.

<u>Ш</u> г 8

O

 $\mathbf{v}_{\mathsf{S}} \approx \mathbf{v}_{\mathsf{S}}$

Z Z

ENGINEERS AUTHENTICATION is authenticated by the seal, signature, and d ill other engineering plans involved in this proje specifically excludes revisions after this ONAL

Notes

Commercial

allon

JSti) 201 E

P+Z No. 12-14 APPROVED 206.14 CITY No.

SHEET NUMBER:

PCE PROJECT NO. 137101