

GRADING NOTES

- 1. Siltation control will be provided as required to prevent
- 2. Siltation control shall be silt fence and/or straw bales placed end to end and anchored with no less than 3' long x 2"x1" wooden stakes. Upon completion of storm sewers, straw bales shall be placed on all sides of structures and shall remain
- 3. All straw bales must be countersunk a minimum of 3" and additional straw bales shall be placed at the direction
- 4. The contractor shall field investigate the entire site prior to his bid submittal noting the existing vegetation and trees and including the removal and disposal of same in his bid.
- 5. No area shall be cleared without permission of the
- 6. All grade shall be within 0.2 feet more or less of those shown on the grading plan.
- 7. No slope shall be greater than 3:1 and shall be either
- sodded or seeded or mulched. 8. The contractor shall restore offsite construction areas to an equal or better condition than existed prior to
- 9. Earth subgrade for paved areas must be compacted to a minimum 90% of maximum dry density as determined by the Modified AASHTO T-180 Compaction Test or 95% of maximum density as determined by the Standard Proctor Test AASHTO T-99. All filled places in proposed roads shall be compacted from the bottom of the fill up. All test shall be verified by a soils engineer concurrent with grading and backfilling operations and must be approved by a City Representative before paving may commence. Owner to provide a copy of the soils report to the grading contractor. Contractor shall be responsible for adhering to all recommendations outlined in the soils report.
- 10. Soil preparation and revegetation shall consist of Tall Fescue(TF) & Smooth Brome(SB) between March 1st. and June 1st. at a rate of TF=30lbs/AC & SB=20lsb/AC. See Appendix A of the Model Sediment and Erosion Control Regulations for Urban Development.
- 11. Proposed phasing of development (rough dates) including: AUG 04 - SEPT 04 a. Clearing (estimated duration of AUG 04 - DEC 04 b. Grading and construction (installation of temporary sediment control, storm drainage, paving). DEC 04 - c. Final Grading and Landscaping (vegetative cover).
- 12. Where natural vegetation is removed during grading, vegetation shall be re-established in such a density as to prevent erosion. Permanent type grasses shall be established as soon as possible or during the next seeding period after grading has been completed. Refer to Appendix A of St. Charles Soil and Water Conservation District - Model Sediment and Erosion Control Regulations.
- 13. When grading operations are completed or suspended for more than 14 days, permanent grass must be established at sufficient density to provide erosion control on the site. Between permanent grass seeding periods, temporary cover shall be provided according to the designated officials recommendation. Refer to Appendix A of St. Charles Soil and Water Conservation District — Model
- Sediment and Erosion Control Regulations. 14. Developer must supply City construction inspectors with soils reports prior to or during site soil testing.
- 15. Erosion control systems shall be inspected and necessary corrections made within 24 hours of any rainstorm resulting in one-half inch of rain or more.
- 16. Curb inlets are to be wrapped with filter fabric until paving is done.

EROSION AND SEDIMENT CONTROL NOTES:

- 1. EROSION AND SILTATION CONTROL SHALL BE INSTALLED PRIOR TO ANY GRADING AND BE MAINTAINED THROUGHOUT THE PROJECT UNTIL ACCEPTANCE OF THE WORK BY THE OWNER AND/OR CONTROLLING REGULATORY AGENCY AND ADEQUATE VEGETATIVE GROWTH INSURES NO FURTHER EROSION OF THE SOIL.
- 2. TEMPORARY SILTATION CONTROL MEASURES (STRUCTURAL) SHALL BE MAINTAINED UNTIL VEGETATIVE COVER IS ESTABLISHED AT A SUFFICIENT DENSITY TO PROVIDE EROSION CONTROL ON THE SITE.
- 3. ALL FINISHED GRADES (AREAS NOT TO BE DISTURBED BY FUTURE IMPROVEMENT) IN EXCESS OF 20% SLOPES (5:1) SHALL BE MULCHED AND TACKED AT THE RATE OF 100 POUNDS PER 1,000 SQUARE FEET WHEN SEEDED.
- 4. STORM WATER PIPES, OUTLETS AND CHANNELS SHALL BE PROTECTED BY SILT BARRIERS AND KEPT FREE OF WASTE AND SILT AT ALL TIMES PRIOR TO FINAL SURFACE STABILIZATION AND/OR PAVING.
- 5. SILTATION FENCES SHALL BE INSPECTED PERIODICALLY FOR DAMAGE AND FOR THE AMOUNT OF SEDIMENT WHICH HAS ACCUMULATED. REMOVAL OF SEDIMENT WILL BE REQUIRED WHEN IT REACHES 1/2 THE HEIGHT OF THE SILTATION FENCE.
- 6. SITE SHALL SHEET DRAIN DURING GRADING OPERATIONS SIMILAR TO EXISTING CONDITIONS. NO ADDITIONAL TEMPORARY DRAINAGE WAYS WILL BE NECESSARY TO ADEQUATELY HANDLE DRAINAGE DURING GRADING OPERATIONS.

SILVE

PICKET

PE

TASK # 1 FIELD BOOK

GRADING PLAN

C Copyright 2004 by Pickett, Ray & Silver Inc

FILE #9811.1

STAR,

ENGINEERS AUTHENTICATION The responsibility for professional engineering liability on this project is hereby limited to the set of plans authenticated by the seal, signature, and date hereunder attached. Responsibility is disclaimed for all other engineering plans involved in

this project and specifically excludes

revisions after this date unless reauthenticated. PICKETT, RAY & SILVER, INC

DRAWN DATE 08-12-04 CHECKED DATE D.L.S. 08-12-04 PROJECT # 01212.BRST.00C

CROSSINGS SPEC BLDG #2