

**SRWall (Version 4) Report****Project Identification**

Project ID :  
Project Name : **Biolife Plasma Center O'Fallon MO**  
Owner :  
Client : **WDS Construction**  
Prepared By : **DMF for JLT**  
Company : **Brucker Engineering Company**  
Address : **7266 Devonshire St Louis MO**  
Telephone : **314-781-0126**  
Section : **Wall #1 max gravity with 3 to 1 above silty**  
Project File : **Biolife max grav with 3 to 1 above with silty clay base.prj**  
Vendor Data File :  
Date and Time : **02/26/2016 17:42:52**

---

Type of Structure : **Gravity Wall**

---

**Wall Geometry**

Design Wall Height(ft) : **2.00**  
Embedment Wall Height(ft) : **0.50**  
Exposed Wall Design Height(ft) : **1.50**  
Number of Segmental Wall Units : **3**  
Wall Inclination(degrees) : **7.13**

---

**Grades**

Top Slope(degrees) : **18.30**

---

**Uniform Distributed Surcharge**

Live Load Surcharge(Psf) : **0.00**  
Dead Load Surcharge(Psf) : **0.00**

---