PERMIT) AND BECOME FAMILIAR WITH THEIR CONTENTS. CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES AS REQUIRED BY THE SWPPP. ADDITIONAL BEST MANAGEMENT PRACTICES

COST OF OWNER THROUGHOUT ALL PHASES OF CONSTRUCTION.

BEST MANAGEMENT PRACTICES (BMP'S) AND CONTROLS SHALL CONFORM TO FEDERAL, STATE, OR LOCAL REQUIREMENTS OR MANUAL OF PRACTICE, AS APPLICABLE CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY PERMITTING AGENCY OR OWNER.

SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL

- 4. SITE MAP MUST CLEARLY DELINEATE ALL STATE WATERS.
- CONTRACTOR SHALL MINIMIZE CLEARING TO THE MAXIMUM EXTENT PRACTICAL OR AS REQUIRED BY THE GENERAL PERMIT
- GENERAL CONTRACTOR SHALL DENOTE ON PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA, EMPLOYEE PARKING AREA, AND AREA FOR LOCATING PORTABLE FACILITIES, OFFICE TRAILERS,
- ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED OR
- . SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOATATION BOOMS SHALL BE MAINTAINED ON SITE OR READILY AVAILABLE TO CONTAIN AND CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- . DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
- O. RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS
- THE LOCAL AGENCY(IES) MUST BE NOTIFIED AT LEAST FORTY-EIGHT HOURS PRIOR TO THE COMMENCEMENT OF ANY GRADING OPERATIONS.
- 12. NO GRADED AREA IS TO REMAIN WITHOUT VEGETATIVE GROUND COVER FOR MORE THAN THIRTY (30) DAYS WITHOUT BEING SEEDED AND MULCHED OR SODDED.
- 13. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS STOPPED FOR AT LEAST 14 DAYS, SHALL BE TEMPORARILY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS.
- 4. IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE.
- 15. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED
- 6. CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER DRAINAGE SYSTEMS IN CONJUNCTION WITH THE STABILIZATION OF
- 7. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION.
- 18. DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURES (SILT FENCES) TO PREVENT EROSION.
- 19. ALL CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY. THIS INCLUDES BACKFILLING OF TRENCHES FOR UTILIT CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING.
- 20. THE CONTRACTOR SHALL FIELD INVESTIGATE THE ENTIRE SITE PRIOR TO HIS BID SUBMITTAL NOTING THE EXISTING VEGETATION AND TREES AND INCLUDING THE REMOVAL AND DISPOSAL IN HIS BID.
- 21. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. LOCATION, RELOCATION AND CONNECTION OF THE UTILITIES SHALL BE COORDINATED WITH THE UTILITY COMPANIES.
- 22. UNDERGROUND STRUCTURES, FACILITIES, AND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS. THEREFORE, THEIR LOCATIONS MUST BE CONSIDERED APPROXIMATE ONLY. THERE MAY BE OTHERS, THE EXISTENCE OF WHICH IS PRESENTLY NOT KNOWN.
- 23. FLOOD ZONE: THIS SITE FALLS WITHIN UNSHADED "ZONE X." AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN, PER FIRM; SHADED "ZONE X," AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN ONE 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD: "ZONE AE." SPECIAL FLOOD HAZARD AREAS SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD: BASE FLOOD ELEVATIONS DETERMINED; "FLOODWAY AREAS IN ZONE AE," THE FLOODWAY IS THE CHANNEL OF A STREAM PLUS ANY ADJACENT FLOODPLAIN AREAS THAT MUST BE KEPT FREE OF ENCROACHMENT SO THAT THE 1% ANNUAL CHANCE FLOOD CAN BE CARRIED WITHOUT SUBSTANTIAL INCREASES IN FLOOD HEIGHTS; PER FLOOD INSURANCE RATE MAP. FOR CITY OF O'FALLON, MISSOURI AND INCORPORATED AREAS, MAP NUMBER 29183C0451G, MAP REVISED ON JANUARY 20. 2016. FLOOD ZONES ARE DETERMINED BY SCALING.
- 24. THE BOUNDARY INFORMATION AND CONTOURS AS SHOWN IS FROM A TOPOGRAPHIC SURVEY PERFORMED BY COCHRAN.
- 25. TEMPORARY SILTATION CONTROL STRUCTURES SHALL BE MAINTAINED UNTIL A VEGETATIVE COVER OF AREA DISTURBED IS ESTABLISHED AT A SUFFICIENT DENSITY TO PROVIDE EROSION CONTROL ON THE SITE, AS DETERMINED BY THE CITY ENGINEER.
- 26. WHERE NATURAL VEGETATION IS REMOVED DURING GRADING, VEGETATION SHALL BE REESTABLISHED VEGETATIVE COVER OF AREA DISTURBED AS O PREVENT EROSION. PERMANENT TYPE GRASSES SHALL BE ESTABLISHED AS SOON AS POSSIBLE OR DURING THE NEXT SEEDING PERIOD AFTER GRADING HAS BEEN COMPLETED.
- 27. WHEN GRADING OPERATIONS ARE COMPLETED OR SUSPENDED FOR MORE THAN THIRTY (30) DAYS, PERMANENT GRASS MUST BE ESTABLISHED TO VEGETATIVE COVER TO PROVIDE EROSION CONTROL ON THE SITE. BETWEEN PERMANENT GRASS SEEDING PERIODS, TEMPORARY COVER SHALL BE PROVIDED ACCORDING TO THE CITY ENGINEER'S RECOMMENDATIONS. ALL FINISHED GRADES (AREAS NOT TO BE DISTURBED BY FUTURE IMPROVEMENTS) IN TWENTY (20) PERCENT SLOPES (5 HORIZONTAL TO 1 VERTICAL) SHALL BE MULCHED.
- 28. ALL EROSION AND SEDIMENT CONTROL FACILITIES SHALL BE INSPECTED FOLLOWING EACH RAINSTORM CAUSING SIGNIFICANT RUNOFF, OR BEING OF SUFFICIENT INTENSITY OR DURATION AS TO STOP CONSTRUCTION OR GRADING PROGRESS. THE SEDIMENT CONTROL FACILITIES SHALL BE CLEANED OF SEDIMENT, REPAIRED IF DAMAGED AND RESTORED TO SERVICEABLE CONDITIONS IF:
- 1. EROSION SEDIMENT HAS ACCUMULATED IN SILT DEVICES, SEDIMENT EROSION CONTROL DEVICES HAVE BEEN DAMAGED, 3. OBVIOUS GULLIES OR SEDIMENT DEPOSITS HAVE BEEN FORMED ON THE DOWNSTREAM SIDE OF CONTROL DEVICES, OR

4. SEDIMENT HAS BEEN CARRIED BEYOND THE WORKING SITE.

- GENERAL EROSION NOTES CONTINUED: 29. THE DEVELOPER MUST SUPPLY CITY CONSTRUCTION INSPECTORS WITH ALL COPIES OF INTERIM SOIL TESTING REPORTS.
- 30. ALL FILLED PLACES UNDER PROPOSED STORM AND SANITARY SEWER, PROPOSED ROADS. AND/OR PAVED OR FUTURE PAVED AREAS SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY AS DETERMINED BY THE STANDARD COMPACTION TEST. ALL FILL PLACED IN PROPOSED ROADS SHALL BE COMPACTED FROM THE BOTTOM OF THE FILL UP. ALL TESTS SHALL BE VERIFIED BY A SOILS ENGINEER CONCURRENT WITH GRADING
- 31. AREA SHALL BE TEMPORARILY RESEEDED AT A RATE OF 6-8 LBS. OF RYE GRASS PER 1000 SQ. FT. FERTILIZER SHALL BE APPLIED AT A RATE OF 50 LBS. PER 10,000 SQ. FT.

## CONTRACTOR SHALL ASSURE POSITIVE DRAINAGE FROM BUILDINGS FOR ALL NATURAL & PAVED AREAS.

- 2. ALL UNSURFACED AREAS ARE TO RECEIVE FOUR INCHES OF TOPSOIL. CONTRACTOR TO SEED, MULCH, AND FERTILIZE ALL AREAS OUTSIDE OF PAVED AREAS THAT WERE DISTURBED DURING CONSTRUCTION UNTIL AN ACCEPTABLE STAND OF GRASS IS
- 3. NO LAND CLEARING OR GRADING SHALL BEGIN UNTIL ALL EROSION CONTROL MEASURES HAVE BEEN INSTALLED.

SITE SHALL BE SEEDED AS SPECIFIED BY TEMPORARY SEEDING MIX.

- 4. SHOULD CONSTRUCTION STOP FOR LONGER THAN 15 DAYS, THE
- 5. MAINTAIN EROSION CONTROL MEASURES AFTER EACH RAIN AND AT LEAST ONCE A WEEK.
- 6. THIS PLAN SHALL NOT BE CONSIDERED ALL INCLUSIVE AS THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT SOIL SEDIMENT FROM LEAVING THE SITE.
- 7. CONTRACTOR SHALL COMPLY WITH ALL STATE AND LOCAL ORDINANCES THAT APPLY.
- 3. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON SITE INSPECTION.
- 9. LAND DISTURBING ACTIVITIES SHALL NOT COMMENCE UNTIL APPROVAL TO DO SO HAS BEEN RECEIVED BY GOVERNING
- 10. CONTRACTOR SHALL BE RESPONSIBLE TO TAKE WHATEVER MEANS NECESSARY TO ESTABLISH PERMANENT SOIL STABILIZATION.
- 11. ALL CUT OR FILL SLOPES SHALL BE 3:1 OR FLATTER UNLESS OTHERWISE NOTED.
- 12. EFFORTS WILL BE MADE TO DIRECT DRAINAGE TO EXISTING DISCHARGE POINTS.
- 13. ALL STORM WATER RUNOFF SHALL MEET LOCAL AGENCY(IES)
- 14. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO KEEP ALL MUD AND SILT ON SITE AND OFF OF STREETS.
- 15. THE CONTRACTOR IS RESPONSIBLE FOR KEEPING STORM WATER RUN-OFF AND SILTATION UNDER CONTROL DURING CONSTRUCTION
- 16. CONTRACTOR SHALL MAINTAIN THE SITE IN A WELL-DRAINED MANNER IN ORDER TO ASSUME THE SHORTEST POSSIBLE DRYING TIME AFTER EACH RAINFALL. THIS WILL MEAN THAT PUMPING OF STANDING WATER IN LOW AREAS ON THE SITE WILL MOST LIKELY BE REQUIRED DURING CONSTRUCTION.

### MAINTENANCE: ALL MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER A 0.5" RAINFALL EVENT, AND CLEANED AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING: 1. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED

- OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING, OR DETERIORATION. 2. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED.
- 3. SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF THE SILT 4. THE CONSTRUCTION ENTRANCES SHALL BE MAINTAINED IN A
- ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCES AS CONDITIONS 5. OUTLET STRUCTURES IN THE SEDIMENTATION BASINS SHALL BE MAINTAINED IN OPERATIONAL CONDITIONS AT ALL TIMES.

CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD

- SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY 6. ALL CURB AND AREA INLETS SHALL HAVE INLET PROTECTION
- SUFFICIENT TO PREVENT TRANSPORTED SOIL FROM BEING DEPOSITED IN THE FORM OF SILT IN THE STORM DRAINAGE SYSTEMS ON-SITE OR OFF-SITE. 7. ALL FINISHED GRADES THAT EXCEED 20% (5 HORIZONTAL TO 1 VERTICAL) SHALL BE MULCHED.

## SEQUENCE OF CONSTRUCTION

INSTALL EROSION CONTROL ITEMS.

- INSTALL TEMPORARY CONTROL MEASURES BEGIN DEMOLITION OF THE NOTED ITEMS ON THE PLANS. PERFORM GRADING ACTIVITIES.
- TEMPORARY SEED DENUDED AREAS.
- PAVE SITE. FINAL SEEDING/SOD.
- REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES (ONLY IF SITE IS STABILIZED).

# S.W.P.P.P. GENERAL NOTES AND DETAILS


1'MIN


FABRIC-

1% MAX SLOPE

WITHIN 3' OF


PERSPECTIVE





#### SOIL DISTURBANCE ACTIVITY OR CONDITION REQUIRED STABILIZATION TIME SOIL DISTURBANCE HAS CEASED IN AREAS GREATER THAN 2,000 SQUARE FEET AFTER CONSTRUCTION OF DIKES, BERMS, DIVERSIONS, 5 DAYS AND OTHER CONCENTRATED FLOW AREAS WHEN SLOPES ARE STEEPER THEN 3 HORIZONTAL TO 7 DAYS WHEN SLOPES ARE GREATER THAN 3% AND LONGER 14 DAYS THAN 150 FEET PERIMETER CONTROLS AROUND SOIL STOCKPILES END OF WORKDAY STABILIZATION OR COVERING OF INACTIVE STOCKPILES 30 DAYS WHEN LAND DISTURBANCE IS COMPLETED, PERMANENT 30 DAYS SOIL STABILIZATION MUST BE INSTALLED

TABLE 60-5 SOIL STABILIZATION SCHEDULE




OR 2x4 WOOD FRAME


MIN LENGTH 3'

MAX LENGTH 3½'

1.5' MAX

AREA INLET





Missouri State Certificate

of Authority Number: 2010000046

Registered Professional Engineer State of Missouri for Cochran Engineering & Surveying

Table 60-7 Temporary Fall Seeding

Plant Species	(lb/acre)	Seeding Times
de-Oats	65	8/16 - 9/30
inter Rye	50	8/01 - 10/15
inter Wheat	60	8/01 - 10/15
rchard Grass	120	8/01 - 10/15
rennial Ryegrass	80	8/01 - 10/15
all fescue, mooth Brome	80	8/01 - 10/15
-31 Fescue	120	9/01 - 11/15
idino Clover	2 2	8/15 - 9/15
rimson Clover	6 <sup>2</sup>	8/15 – 9/15
rchard Grass and ats or Rye	15 <sup>2</sup> 40 <sup>2</sup>	8/15 – 9/15

<sup>1</sup>If using aerial seeding or other broadcast method to apply seed without rolling or cultipacking, increase seeding rates by 50 percent.

<sup>2</sup>Pure live seed (PLS)

Plant Species	Rate <sup>1</sup> (lb/acre)	Seeding Dates
Winter Rye	50	3/15 - 5/31
Spring Oats	65	3/15 - 5/31
annual Ryegrass	4 2	3/15 - 6/15
Sudangrass	16 <sup>2</sup>	4/15 - 6/15
K-31 Fescue	30 <sup>2</sup>	3/15 - 5/31
ted Clover c Oats	2 <sup>2</sup> 30 <sup>2</sup>	3/15 – 5/31

<sup>1</sup>If using aerial seeding or other broadcast method to apply seed without rolling or cultipacking, increase seeding rates by 50 percent.

Soil Amendment Material		Application Rat (Lb per Acre)
Fertilizer	Nitrogen (N)	30 <sup>1</sup>
	Phosphate (P <sub>2</sub> O <sub>5</sub> )	90 <sup>1</sup>
	Potash (K <sub>2</sub> O)	90 <sup>1</sup>
Lime		1,000 2

DESIGN CRITERIA

1. MAXIMUM DRAINAGE AREA - 1 ACRE.

2. PEAK RUNOFF SHALL NOT EXCEED 2 CFS

BASED ON A 6-MONTH STORM EVENT.

. OTHER SEDIMENT PROTECTION PRODUCTS

MAY BE USED, SUCH AS FILTR FENCETM.

<sup>1</sup>Increase the rate by 25% for slopes steeper than 5:1. <sup>2</sup>Rate is in effective neutralizing material (ENM) units.

Material	Rate	Requirements	Installation/Uses
Straw	1.5-2.5 tons/ac (3-4 tons, if roller punched)	Dry, unchopped, unweathered; free of weed seeds & rot.	Spread by machine 1.5-2.5 inches deep; must be tacked or field down.
Compost Blanket	1" thick	Double the application rate for embankments	Follow manufacturer's application method.
Wood fiber, wood cellulose, paper	1-2 tons/ac	Double the application rate in critical areas	Use with power mulcher or hydroseeder; may be used to tack straw on steep slopes. Cannot be used in hot dry weather.

P+Z No. 22-002935

All OSHA rules & regulations established for the type of construction required by these plans shall be strictly followed (ie. Trenching, Blasting, etc.)

Page No.

City of O'Fallon Standard Notes and Details - July 2019

Not

City No.