CITY OF O'FALLON RESIDENTIAL

GENERAL NOTES:

- GN#1 Driveway locations shall not interfere with the sidewalk handicap ramps, or curb inlet sumps.
- GN#2 Sidewalks, curb ramps, ramps and accessible parking spaces shall be constructed in accordance with the current approved "American with Disabilities Act Accessibility Guidelines" (ADAAG) along with the required grades, construction materials, specifications and signage. If any conflict occurs between the above information and the plans, the ADAAG guidelines shall toke precedence and the contractor prior to any construction shall notify the Project Engineer.
- GN#3 Truncated domes for curb ramps located in public right of way shall meet ADA requirements and shall be
- constructed using red pre cast truncated domes per pavement details. • GN#4 Any proposed pavilions ar playground areas will need a separate permit from the Building Division.
- GN#5 The Contractor is responsible to call Missouri One Call and The City of O'Fallon for the location of utilities. Contact the City of O'Fallon (636) 379-3814 for the location of City maintained cable for street lights and traffic signals, all other utilities call Missouri One Call 1-800-DIG-RITE. 1-800-344-7483
- GN#6 All proposed utilities and/or utility relocations shall be lacated underground.
- GN#7 All proposed fencing requires a separate permit through the Building Division. • GN#8 All construction operations and work zone traffic control within the right of way will follow MoDOT or M.U.T.C.D.
- standards whichever is more stringent. • GN#9 All free standing signs shall be located a minimum of ten (10) feet away from any right of way line and/or property line and a minimum of three (3) feet from the back of curbing or sidewalk. All signs shall abide by the regulations for visibility at corners, including corners from drivewoys and the street it intersects per Section 400.260 of
- the O'Fallon Zoning Code. • GN#10 All subdivision identification or directional sign(s) must have the locations and sizes approved and permitted separately through the Planning and Development Division.
- GN#11 Materiols such as trees, organic debris, rubble, foundations, and other deleterious material shall be removed from the site and disposed of in compliance with all applicable laws and regulations. If the material listed previously are reused, a letter from a soil Engineer must clarify amount, location, depth. ect. and be approved with the construction plans. Landfill tickets for such disposal shall be maintoined on file by the developer. Burning on site shall be allowed only by permit from the local fire district. If a burn pit is proposed the location and mitigation shall be shown on the grading plan and documented by the soils engineer.
- GN#12 Twenty-four (24) hours prior to starting any of the work covered by the above plans and after approval thereof, the developer shall make arrongements with the Construction Inspection Office to provide for inspection of the work, sufficient in the opinion of the City Engineer, to assure compliance with the plans and specifications as approved.
- GN#13 The City Engineer or their duly authorized representative shall make all necessary inspections of City infrastructure, escrow items or infrastructure located on the approved plans.
- GN#14 All installations and construction shall conform to the approved engineering drawings. However, if the developer chooses to make minor modifications in design and/or specifications during construction, he/she shall moke such changes at his/her own risk, without any assurance that the City Engineer will approve the completed installation or approved drawings. The developer may be required to correct the installed improvements so as to conform to the engineering drawings. The developer may request a letter from the Construction Inspection Division regording any field changes approved by the City inspectors.
- GN#15 City approval of the construction site plans does not mean that any building can be constructed on the lots without meeting the building setbacks os required by the Zoning Code.

EROSION CONTROL NOTES:

- EN # 1 The Permittee shall assume complete responsibility for controlling all siltation and erosion of the project area. The Permittee shall use whatever means necessary to control erosion and siltation including, but not limited ta, staked straw bales and/or siltation fabric fences (possible methods of control are detailed in the plan). Control shall cammence with the clearing operations and be mointained throughout the project untilL acceptance of the wark by City of O'Fallon and as needed by MoDOT. The Permittee's respansibilities include all design and implementation as required to prevent erosion and the depositing of silt. The City of O'Fallon and as required by MoDOT may at their option direct the Permittee in his methods as deemed fit to protect property and improvements. Any depositing of silt ar mud an new or existing pavement shall be removed immediately. Any depositing af silts or mud in new or existing storm sewers and/or swales shall be removed after each rain and affected areas cleaned to the satisfaction of the City of O'Fallon and as required by MoDOT."
- EN # 2 All erosion cantral systems are to be inspected and corrected weekly, especially within 48 hours of any rain storm resulting in one—half inch of rain or more. Any silt or debris leaving the site and affecting public right of way or storm water drainage facilities shall be cleaned up within 24 hours after the end of the storm.
- EN # 3 Erosion control devices (silt fence, sediment basin, etc.) shall be in accordance with St. Charles County Soil and Water Conservation District Erosion and Sediment Control guidelines.
- EN # 4 This development is required to provide long term post construction BMP's such as; low impact design, source cantrol and treatment controls that protects water quality and controls run off to maximum extent practical in campliance with Phase II Illicit Storm Water Discharge Guidelines.(Ord. 5082, section 405.0245)
- EN #5 Graded areas shall be seeded and mulched (strawed) within 14 days of stopping land disturbance activities. Unless it can be shown to the City Engineer that weather conditions are not favorable, vegetative growth is to be established within 6 weeks of stopping grading work on the project. The vegetative growth established shall be sufficient to prevent erosion and the standard shall be as required by EPA and DNR. (70% coverage per square foot) Ord. 5242, Section 405.070

GRADING NOTES:

- GRN #1 Developer must supply City construction inspectors with soil reports prior to ond during site grading. The soil report will be required to contain the following information on soil test curves (Proctor reports) for projects within the
- 1. Maximum dry density 2. Optimum moisture content
- 3. Maximum and minimum allowable moisture content
- 4. Curve must be plotted to show density fram a minimum of 90% Compaction and above os determined by the
- "Modified AASHTO T-180 Compaction Test" (A.S.T.M.-D-1157) or from a minimum of 95% as determined by "Standard Proctor Test ASSHTO T-99, Method C" (A.S.T.M.-D-698). Practor type must be designoted on
- document. 5. Curve must have at least 5 density paints with moisture content and sample locations listed on document
- 6. Specific gravity
- 7. Natural moisture cantent
- 8. Liquid limit
- 9. Plastic limit Be advised that if this information is not provided to the City's Construction Inspector the City will not allow grading or construction activities to proceed on any project site.
- GRN #2 All fill placed in areas other than proposed storm sewers, sanitary sewers, proposed roads, and paved oreas shall be compacted from the bottom of the fill up in 8" lifts and compacted to 90% maximum density as determined by Modified AASHTO T-180 compaction test or 95% of maximum density as determined by the Standard Proctor Test AASHTO T-99. Ensure the moisture content of the soil in fill areas corresponds to the compactive effort as defined by the Standard or Modified Proctor Test. Optimum moisture content shall be determined using the same test that wos used for compaction. Soil compaction curves shall be submitted to the City of O'Fallon prior to the placement of fill.
- GRN # 3 The surface of the fill shall be finished so it will not impound water. If at the end of a days work it would appear that there may be rain prior to the next working day, the surface shall be finished smooth. If the surface has been finished smooth for any reason, it shall be scarified before proceeding with the placement of succeeding lifts. Fill shall not be placed on frozen ground, nor shall filling operations continue when the temperature is such as to permit the layer under placement to freeze.
- GRN # 4 All sediment and detention basins are ta be constructed during the initial phase of the grading operation or in accordance with the approved SWPPP.
- GRN # 5 When grading operations are complete or suspended for more than 14 days, permanent grass must be established at sufficient density to provide erosion control on site. Between permanent grass seeding periods, temporary cover shall be provided according to St. Charles Soil and Water Conservation District — Model Sediment and Erosian Control Regulations. All finished grades (areas not to be disturbed by improvements) in excess of 20% slopes (5:1) shall be mulched and tacked at a rate of 100 pounds per 1000 square feet when seeded.
- GRN # 6 No slopes shall exceed 3 (horizontal): 1 (vertical) unless otherwise approved by the soils report and specifically located on the plans and appraved by the City Engineer.
- GRN # 7 All low places whether on site or off shall be graded to provide drainage with temporary ditches.
- GRN # 8 All existing wells on site shall be capped per DNR standards.

GRADING NOTES (CONT'D):

- GRN #10 All trench back fills under paved areas shall be gronular back fill, and compacted mechanically. All other trench back fills may be earth material (free of large clods, or stones) and compacted using either mechanical or woter jetting, Granular moterial and earth material associated with new construction autside of pavements may be jetted, taking care to avoid damage to newly laid sewers. The jetting shall be performed with a probe route on not greater than 7.5 foot centers with the jetting probe centered over and parollel with the direction of the pipe. Trench widths greater than 10 feet will require multiple probes every 7.5 foot centers.
 - a) Depth, Trench back fills less than 8 feet deep shall be probed to a depth extending half the depth of the trench back fill, but not less than 3 feet. Trench back fill greater than 8 feet in depth shall be probed to holf the depth of the trench back fill but not greater than 8 feet. b) Equipment, The jetting probe shall be a metal pipe with an interior diameter of 1.5 to 2 inches.
 - c) Methad, Jetting shall be performed from the lowest surface topographic point and proceed toward the highest point, and from the bottom of the trench back fill toward the surface. The flooding of each jetting probe shall be started slowly allowing slow saturation of the sail. Water is not allowed to flow away fram the trench without first saturating the trench.
 - d) Surface Bridging, The cantractor shall identify the locations of the surface bridging (the tendency for the upper surface to crust and h over the trench rather than collapse and consolidate during the jetting process). The contractor shall break down the bridged areas Using an appropriate method such as wheels or bucket of a backhoe. When surface crust is collapsed, the void shall be back filled with the same material used as trench back fill and rejetted. Compaction of the materials within the sunken/jetted area shall be compacted such that no further surface subsidence occurs.
- GRN #11 Site grading. a) Within City right—of—way. Material is to be placed in eight (8) inch to twelve (12) inch loose lifts and compacted per the approved compaction requirements. One (1) compaction test will be performed every two hundred fifty (250) feet along the centerline for each lift.
- b) Outside of City right-of-way. Materiol is to be placed in eight (8) inch to twelve (12) inch loose lifts and compacted per the approved compaction requirements. One (1) compaction test will be performed at two (2) foot vertical intervals and approximately every one thousand (1,000) cubic yords.

SANITARY SEWER NOTES:

- SAN # 1 All sanitary sewer installation is to be in accordance with M.S.D. 2007 standards and specifications except as modified by the City of O'Fallon Ordinances.
- SAN # 2 Brick shall not be used in the construction of sanitary sewer structures. Pre cast concrete structures ore to be used unless otherwise approved by the City of O'Fallon.
- SAN # 3 Connections of all sanitary structures are to be made with A-Lock joint or equal.
- SAN # 4 All sanitary laterals shall be a minimum of 4" residential, 6" commercial diameter pipe.
- SAN # 5 All sanitary mains shall be a minimum of 8" diameter pipe.
- SAN # 6 All sanitory sewer line with a slope greater than 20% will require concrete crodle or concrete collor. Sanitary line with a slope greater than 50% will require a special approved design as shown on detail sheet.
- SAN # 7 All manholes built within the 100 year flood plain must have lock type watertight manhole covers. SAN # 8 All sanitary sewer mains must have a minimum of 42" cover.
- SAN # 9 When sanitary mains cross aver storm line the sanitary main must be ductile iron pipe for 10 feet on each
- side of the crossing. • SAN #10 Encase with concrete both sanitary and storm sewer at crossing when storm sewer is within 18 inches above
- sanitary sewer. Add concrete cradie to only RCP storm sewer and encase HDPE storm sewer when it is more than 18 inches above sanitary line. Show on profile sheet. • SAN #11 The sanitary sewers should run diagonally through the side yards to minimize any additional utility easements
- reauired.
- SAN #12 All sanitary sewer structures shall be waterpraofed on the exterior in accordance to Missouri DNR specifications 10CSR-8.120 (7)(E).
- SAN #13 All sanitary sewer pipe shall be SDR35 or equal. • SAN #14 All sonitary sewer manholes and pipes will be tested to the following specifications. ASTM C1244, Standard testing method for Concrete Sewer Manhole by Negative Air Pressure (Vacuum), Lotest revision ASTM F1417, Standard testing method for Installation Acceptonce of Plastic Gravity Sewer Lines Using Low Pressure Air, Latest revisian.
- SAN #15 Add 1" minus rock back fill to all sanitary sewer and all other utilities that lie within the 1:1 shear plone of the road.

STORM SEWER NOTES:

- STM # 1 All Storm Sewer installation is to be in accordance with M.S.D. 2007 standards and specifications except as modified by the City of O'Fallon ordinances.
- STM # 2 Brick shall not be used in the construction of storm sewer structures. Pre cast concrete structures are to be used unless otherwise approved by the City af O'Fallon. • STM # 3 A 5/8" trash bar shall be installed horizontally in the center of the opening(s) in all curb inlets and area
- STM # 4 HDPE pipe is to be N-12WT or equal and to meet ASTM F1417 water tight field test.
- STM # 5 Encose with concrete both sanitary and storm sewer at crossing when storm sewer is within 18 inches above sanitary sewer. Add concrete cradle to anly RCP storm sewer and encase HDPE storm sewer when it is more than 18 inches above sanitary line. Show on profile sheet.
- STM # 6 The storm sewers should run diagonally through the side yards to minimize any additional utility easements
- STM # 7 All cancrete pipes will be installed with O-ring rubber type gaskets.
- STM # 8 Connections at all storm structures are to be made with A-lock joint or equal.
- STM # 9 Pre cast concrete inlet covers are not to be used.
- STM #10 The swale in the detention basins shall have a minimum 1% longitudinal slope and be lined with a permanent erosion control blanket that will allow infiltration of storm woter.
- STM #11 All starm sewer shall be reinforced concrete pipe or H.D.P.E. pipe. All structures and flared end sections must be concrete. Manufocturing specifications must be followed and details provided for the installation of H.D.P.E. pipe. H.D.P.E. pipe will not be allowed for detention basin outflows, final pipe run to detention basins, creek discharge or other approved means. STM #12 The discharge point of all flared end sections shall be protected by rip rap or other approved means.
- STM #13 Rip rap shown at flared end sections will be evaluated in the field by the Engineer, Contractor, and City Inspectors after installation for effectiveness and field modified, if necessary to reduce erosion an and off site.
- STM #14 Add 1" minus rock back fill to all storm sewer that lie within the 1:1 shear plane of the road.

WATER NOTES:

- WN # 1 Fire hydrants shall be a maximum of 600' apart. Local fire district approval is required.
- WN # 2 Coordinate with the water company on the location of water meters.
- WN # 3 All water main must have a minimum af 42" of cover. (City water mains)

Grading around structure tops on slopes need to be accounted for.

- WN # 4 Provide water valves ta isolate the system.
- WN # 5 All water moins shall be class 200 SDR 21 or equal with locator/tracer wires
- WN # 6 DISINFECTING: Disinfecting shall be accomplished by placing sufficient hypo chlorite granule (HTH) in each section of pipe to achieve a chlorine residual in the pipeline, upon initial filling, of 50 mg/L (PPM). HT. tablets will not be allowed. Following completion of the pipeline, it shall be slowly filled
- with water and a sample will be taken immediately and the chlorine residual must be 50 mg/L or greater. The solution shall be allowed to stand for 24 hours and a sample shall then be taken. The chlorine residual after 24 hours shall be 30 mg/L or greater. If the piping shows insufficient chlorine residuals in either test, the piping shall be re-chlorinated by the injection of hypo chlorite solution until satisfactory results are achieved. All disinfecting shall be done by the contractor. Only the testing to determine the chlorine residual will be done by the City. WN # 7 PRESSURE TESTING:
- Immediately following disinffection, the piping shall be pumped to a pressure (at the lowest point in the project) of 150 psi or higher where the working pressure is higher than 150 PSI as determined by the City. In such cases, the pressure shall be as specified by the City and two pressure tests shall be conducted. The first test shall be with the fire hydrant auxiliary valve open and be to 150 PSI. The second test shall be with the fire hydrant auxiliary valve closed and be to the higher pressure as directed by the City. All pumping equipment and pressure gauges shall be provided by the contractor. After achieving the test pressure, the piping shall be left closed for a period of two (2) hours. At the end of this
- time the pressure drop shall not exceed 2 psi. In addition, if the pressure appears, in judgment of the City's representative, to be continuing to drop, the test shall be continued for another two (2) hours and if any further drops occur, the test shall be considered a failure. If the pressure test fails, the contractor will be required to find and correct the source of the leakage. If this requires droining of the pipeline, when the leakage is corrected, the pipeline must be re-disinfected and the pressure tested ogain until satisfactory result are achieved. Any MDNR required dechlorination will be perfarmed by the contractor. • WN # 8 All tops for valves, meters, and manholes are to be constructed to within 1 inch (0.08') of finish grade.

WATER NOTES (CONT'D):

 WN #10 BACTERIOLOGICAL TESTING: After satisfactory disinfection and pressure testing, a sample shall be taken by the contractor in the presence of a City representative and submitted to a laboratory approved by the Missouri Department of Notural Resources and the City for bacteriological analysis. After 24 hours, a second sample shall be token in a like manner and submitted for analysis. The two samples taken on consecutive days ,a minimum of 24 hours aport, must be found to be "safe" by the testing laboratory, and copies of the test results must be supplied to the City. If the samples are not found to be "safe" further flushing and/or disinfection as directed by the City shall be conducted by the contractor until "safe" samples on two consecutive test days are achieved. Following successful bacteriological testing and a determination by the City that the samples ore "safe", the mains may be placed into service.

ROADWAY NOTES:

- RN # 1 All poving (public and private) to be in accordance with 2006 St. Charles County Standards and Specifications except as modified by the City of O'Fallon ordinances.
- RN # 2 If the intersecting road does not have a curb, then the curb on the new entrance shall begin 10' from the edge of the existing road.
- RN # 3 Provide 6" of concrete over 4" of MoDot type 1 or type 5 aggregate rock or asphalt equivalent for minor residential streets per City Code 405.370.
- RN # 4 Multi-use trail (when required) Shall have a minimum of 3" Type "C" Asphalt over 4" aggregate base per City requirements.
- RN # 5 Type C (BP-1) Compoction requirements shall be 98% minimum density according to St. Charles Co. Standard Specifications.
- RN # 6 Provide pavement striping at any point where the multi-use trail crosses existing or proposed pavement. RN # 7 All street stub—outs over 250' in length will require a temporary turnaround.
- RN # 8 All sub grade in cut or fill will need to conform to the City of O'Fallon Compaction requirements
- RN # 9 Material Testing And Frequency. Materiols for construction shall be tested and inspected per the appropriate ASTM code or at the City Engineer's discretion. The developer's engineer shall perform the following quality control guidelines:
 - 1. Concrete. a. Cylinders/compressive strength. One (1) set of four (4) cylinders within the first fifty (50) cubic yards and one (1) set per one hundred (100) cubic yards thereofter. One (1) cylinder must be tested at seven (7) doys, one (1) at fourteen (14) days and two (2) at twenty-eight (28) days. If the first (1st) cylinder does not meet specifications at twenty-eight (28) days, then the second (2nd) cylinder must be held and tested at day fifty—six (56).
 - b. Percent oir and temperature. First (1st) truck batch each day ond two (2) thereafter until a consistency is encountered. Once a consistency is encountered, then tests will be performed in conjunction with the
 - c. Slump. First (1st) truck batch each day and two (2) thereafter until a consistency is encountered. Once a consistency is encountered, then tests will be performed in conjunction with the concrete cylinders. d. If concrete is batched from more than one (1) plant, then the aforementioned guidelines will be applicable to each plant.
- 2. Sub grade and bose. a. Proof roll as described in Section 405.210(B).
- b. One (1) compaction test per two hundred fifty (250) feet of mainline paving, three (3) tests per intersection, five (5) tests within cul-de-sacs and one (1) test per repair slab. c. Gradation test for sub base material.
- 3. Asphalt. a. One (1) set of campaction tests per two hundred fifty (250) feet of mainline. One (1) set includes three (3) tests across the paved lane at the same station.
- b. One (1) bulk density test per paving operation. • RN #10 Approval Of Sub grade And Base (Sub base). The City Engineer or representative shall approve the sub grade befare any base is placed thereon and shall approve the base before concrete or surface caurse is placed. The sub
- grade and base shall be so constructed that it will be uniform in density throughout. • RN #11 In all fill areas in the roadways, soil tests shall be submitted and approved by the City Engineer for each foot
- of fill ond at least one (1) test and an average of one (1) test within every two hundred fifty (250) feet. • RN #12 No traffic will be allowed on new concrete pavement until it has cured for seven (7) doys and it reaches three thausand five hundred (3,500) psi within 28 days. Concrete pavements shall not be approved unless it reaches a strength of four thousand (4,000) psi.Cylinders/compressive strength. One (1) set of four (4) cylinders within the first fifty (50) cubic yards and one (1) set per one hundred (100) cubic yards thereafter. One (1) cylinder must be tested at seven (7) doys, one (1) at fourteen (14) days and two (2) at twenty-eight (28) days. If the first (1st) cylinder does not meet specifications at twenty—eight (28) days, then the second (2nd) cylinder must be held and tested at day
- RN #13 Prior to placement of aggregate base material on sub grade and prior to placement of pavement on base material, the sub grade and base must be proof-rolled with a fully loaded (ten (10) ton load) tandem truck or equivalent tire vehicle with one (1) pass down each driving lone no faster than three (3) miles per hour. If soft spots are detected, or pumping, rutting or heaving occurs greater than one (1) inch ot the sub grade, the roadbed shall be considered unsatisfactory and the soil in these areas shall be remediated to the depth indicated by the controctor's testing firm and approved by a representative of the City Engineer.
- RN #14 Sub grade and base beneath pavements shall be compacted to St. Charles County Highway Department specifications. The moisture range shall be determined by the Standard or Modified Proctor Density Method AASHTO
- T-99 and within -2/+4 percentage points of the optimum moisture content. • RN #15 The entire width and length will conform to line, grade and cross section shown on the plans or as established by the engineer. If any settling or washing accurs, or where hauling results in ruts or other objectionable irregularities, the contractor shall improve the sub grade or base to the satisfaction of the City before the pavement is placed. Additional rolling or methods to verify compaction shall be at the discretian of the City Engineer. Toleronce allowed on
- all lines, grades and cross sections shall be plus or minus four-hundredths (+0.04) feet. • RN #16 Utility Work Prior To Base Construction. No base course work may proceed on any street until all utility excavations (storm and sanitary sewers, water, gas, electric, etc.) have been properly back filled with granular material, crushed stone or gravel mechanically tamped in ten (10) inch lifts. Utilities installed after sub grade preparation shall
- be bored. Compaction requirements shall follow St. Charles County standards (2006). • RN #17 Equipment calibration. The developer's controctors and subcontractors must have their equipment calibrated by the following minimum standards. a. Air meter--weekly.
- b. Cylinder compression—annually by independent calibration service.
- c. Batch scales——monthly. d. Nuclear testing devices—every six (6) months.
- e. Proctor equipment—every six (6) manths.
- f. Slump cone--monthly. • RN #18 All permanent traffic cantrol will be per M.U.T.C.D. or MoDot standards. S1-1 from the M.U.T.C.D. manual will be used at all crosswalk locations accompanied with ether w16-9p or w16-7p signs
- RN #19 All traffic signals, street signs, sign post, backs and bracket arms shall be painted black using Carboline Rust Bond Penetroting Sealer SG ond Carboline 133 HB paint (or equivalent as approved by City of O'Fallon and MoDOT).

FLOOD PLAIN INFORMATION:

- FP #1 A flood plain development application from the City is required for any work within the flood plain limits.
- FP #2 This property lies within Zone AE (FLOODPLAIN ELEVATIONS DETERMINED) per the Flood Insurance Rate Maps, Community Panel No. 29183C210 F and No. 29183C0220 F, effective date March 17, 2003.
- All lots with the basement floor below the 100 year flood plain elevation will require backflow preventers to be installed on the sanitary lateral. "*" after the lot number indicated basement floor below flood plain elevation.

TE OF MISO ---KARL ANTHONY SCHOENIKE NUMBER PE-2003015039 🗧 , **---**ELECTRONIC SEAL KARL A. SCHOENIKE, P.E. PROFESSIONAL ENGINEER LICENSE 2003015039 थ्र ह uio:

m

 \mathbf{Z}

SILVER

RAY

P R R

HODRE #000325

ENGINEERS AUTHENTICATION

PICKETT, RAY & SILVER, INC. MO

THE RESPONSIBILITY FOR PROFESSIONAL ENGINEERING LIABILITY ON THIS PROJECT IS HEREBY LIMITED TO TO

SET OF PLANS AUTHENTICATED BY THE BEAL, SIGNATUR

AND DATE HEREIMOER ATTACHED, RESPONSIBILITY IS DISCLATMED FOR ALL OTHER ENGINEERING PLANS INVOLVED IN THIS PROJECT AND SPECIFICALLY EXCLUDES REVISIONS AFTER THIS DATE UNLESS REAUTHENTICATED.

P+Z No. 2603.04

City No. 14-156-SP

Page No.

NOTES

City of O'Fallon Standard Subdivision Notes and Details — June 2010