

TABULATIONS OF QUANTITIES

MOBILIZATION = 1 LUMP SUM

CONTRACTOR FURNISHED SURVEYING AND STAKING = 1 LUMP SUM

ADJUST TO GRADE

SHEET	STATION	ROUTE	LOCATION	ADJUSTING MANHOLE (EA)	GAS VALVE (EA)	REMARKS
BRYAN ROAD						
PN-01	109+69	BRYAN	35.4', RT	1		MH 1-3, COVERT EXIST DOUBLE CURB INLET TO MANHOLE
PN-02	113+79	BRYAN	35.6' RT	1		MH 2-14, COVERT EXIST DOUBLE CURB INLET TO MANHOLE
FEISE ROAD						
PN-04	299+70	SIDE	6.2', RT		1	
PN-05	51+50	FEISE	24.5', LT	1		MH 2-11, COVERT EXIST CURB INLET TO MANHOLE
PN-05	51+98	FEISE	24.7', LT	1		MH 2-10, COVERT EXIST CURB INLET TO MANHOLE
PAY TOTAL				4	1	

CONCRETE CURB & GUTTER / MEDIAN STRIP


SHEET	STATION	STATION	ROUTE	LOCATION	6" INTEGRAL CURB (LF)	6 IN. CONCRETE MEDIAN STRIP (SY)	REMARKS
CITY OF O'FALLON							
PN-01	107+76	113+00	BRYAN	RT	684.4	80.2	QUANTITIES INCLUDE CURB ALONG CORA MARIE
PN-02	113+00	118+00	BRYAN	RT	517.5	68.8	
PN-03	118+00	118+64	BRYAN	RT	95.9		
PN-05	50+18	52+96	FEISE	LT	321.8	21.8	QUANTITIES INCLUDE CURB ALONG MIA ROSE
SUBTOTAL					1619.6		
PAY TOTAL					1620	170.7	
CITY OF DARDENNE PRAIRIE							
PN-04	45+27	48+00	FEISE	LT	278.0		QUANTITIES INCLUDE CURB ALONG CORA MARIE
PN-05	48+00	50+18	FEISE	LT	218.4		
SUBTOTAL					496.4		
PAY TOTAL					497	0.0	

PAVEMENT ITEMS / LINEAR GRADING

SHEET	STATION	STATION	ROUTE	LOCATION	5" TYPE 5 AGGR. BASE (SY)	CONC PAVEMENT 9 IN. (NON- REINF.) (SY)	LINEAR GRADING (LF)	PAVEMENT EDGE TREATMENT (LF)	REMARKS
CITY OF O'FALLON									
PN-01	107+76	113+00	BRYAN	RT	1853.6	1777.3	524.0	524.0	WIDTH OF LINEAR GRADING VARIES; QUANTITIES INCLUDE CORA MARIE
PN-02	113+00	118+00	BRYAN	RT	891.1	832.8	500.0	500.0	WIDTH OF LINEAR GRADING VARIES; QUANTITIES INCLUDE RIGHT-IN/RIGHT-OUT
PN-03	118+00	118+64	BRYAN	RT	75.1	68.0	63.6	63.6	WIDTH OF LINEAR GRADING VARIES; QUANTITIES INCLUDE RIGHT-IN/RIGHT-OUT
PN-05	50+18	52+96	FEISE	LT	743.8	707.9	277.4	277.4	WIDTH OF LINEAR GRADING VARIES; QUANTITIES INCLUDE MIA ROSE WAY
SUBTOTAL					3563.6		1365.0	1366	
PAY TOTAL					3564	3386.1	1366		
CITY OF DARDENNE PRAIRIE									
PN-04	45+27	48+00	FEISE	LT	562.3	531.5	272.7	272.7	WIDTH OF LINEAR GRADING VARIES; QUANTITIES INCLUDE WEST ENTRANCE
PN-05	48+00	50+18	FEISE	LT	353.0	328.8	218.2	218.2	WIDTH OF LINEAR GRADING VARIES
SUBTOTAL					915.3		490.9	491	
PAY TOTAL					916	860.4	491		

CONCRETE SIDEWALK

SHEET	STATION	STATION	ROUTE	LOCATION	SIDEWALK AREA (SF)	4" TYPE 5 AGGR. BASE (SY)	CONCRETE SIDEWALK, IN. 4 (SY)	REMARKS
CITY OF O'FALLON								
PN-01	107+76	26+74.58	BRYAN/CORA	RT	2763.1	307.0	307.0	
PN-01	26+74.58	113+00	CORA/BRYAN	RT	876.9	97.4	97.4	
PN-02	113+00.00	118+00.00	BRYAN	RT	2527.3	280.8	280.8	
PN-03	118+00.00	118+63.63	BRYAN	RT	278.6	31.0	31.0	
PN-05	50+18	52+96	FEISE	LT	1193.1	132.6	132.6	
SUBTOTAL						848.8		
PAY TOTAL						849	848.8	
CITY OF DARDENNE PRAIRIE								
PN-03	45+27	48+00	FEISE	LT	1147.2	127.5	127.5	
PN-04	48+00	50+18	FEISE	LT	1089.6	121.1	121.1	
SUBTOTAL						248.5		
PAY TOTAL						249	248.5	



DATE PREPARED 02/05/2024	
ROUTE .	STATE MO
DISTRICT STL	SHEET NO. 3
COUNTY ST. CHARLES	
JOB NO. .	
CONTRACT ID. .	
PROJECT NO. 1201400	
BRIDGE NO. .	

DESCRIPTION	DATE
.	.
.	.
.	.
.	.
.	.
.	.
.	.
.	.
.	.

KALECO, LLC
7 BAXTER LANE
CHESTERFIELD, MO 63017
(217-370-7623)

Volkert
CERTIFICATE OF AUTHORITY
NO. F00391502
401 S. 18TH STREET
SUITE 250
ST. LOUIS, MO 63103

BYRAN ROAD & FEISE
ROAD IMPROVEMENTS

SUMMARY OF
QUANTITIES (QU)
(3 OF 5)