

TABULATIONS OF QUANTITIES

CONCRETE CURB RAMP / LINEAR GRADING, SIDEWALK

SHEET	STATION	ROUTE	LOCATION	RAMP/LANDING AREA (SF)	CONCRETE CURB RAMP (SY)	4" TYPE 5 AGGR. BASE (SY)	TRUNCATED DOMES (SF)	REMARKS
CITY OF O'FALLON								
PN-01	111+67.31	BRYAN	74.2' RT	124	13.8	13.8	10.0	CURB RAMP 1
PN-01	111+85.66	BRYAN	41.0' RT				10.5	CURB RAMP 2 (SEE NOTE 1)
PN-01	111+84.77	BRYAN	55.0' RT				14.5	CURB RAMP 3 (SEE NOTE 1)
PN-01	112+00.19	BRYAN	49.5' RT				10.5	CURB RAMP 4 (SEE NOTE 1)
PN-01	111+85.66	BRYAN	33.2' LT	189	20.9	20.9	16.0	CURB RAMP 5
PN-01	112+07.83	BRYAN	41.8' LT	161	17.8	17.8	23.0	CURB RAMP 6
PN-01	112+72.75	BRYAN	51.0' RT	129	14.3	14.3	11.0	CURB RAMP 7
PN-01	112+68.35	BRYAN	38.7' LT	223	24.8	24.8	37.8	CURB RAMP 8
PN-02	117+10.02	BRYAN	57.8' RT	132	14.7	14.7	10.0	CURB RAMP 9
PN-02	117+26.07	BRYAN	45.0' RT				17.2	CURB RAMP 10 (SEE NOTE 1)
PN-02	117+48.63	BRYAN	45.0' RT				17.2	CURB RAMP 11 (SEE NOTE 1)
PN-02	117+64.70	BRYAN	57.8' RT	132	14.7	14.7	10.0	CURB RAMP 12
PN-05	50+82.41	FEISE	53.0' LT	131	14.6	14.6	10.0	CURB RAMP 15
PN-05	50+97.89	FEISE	39.6' LT				14.2	CURB RAMP 16 (SEE NOTE 1)
PN-05	51+09.70	FEISE	39.0' LT				10.4	CURB RAMP 17 (SEE NOTE 1)
PN-05	51+49.26	FEISE	38.9' LT	71	7.9	7.9	16.3	CURB RAMP 18
				SUBTOTAL		143.5	238.6	
				PAY TOTAL	143.5	144	239	

RDENNE PRAIRIE								
PN-03	45+60.33	FEISE	38.5' LT	95	10.6	10.6	13.8	CURB RAMP 13
PN-03	46+13.02	FEISE	38.8' LT	61	6.8	6.8	12.6	CURB RAMP 14
				SUBTOTAL		17.4	26.4	
				PAY TOTAL	17.4	18	27	

STORMWATER FACILITIES


SHEET	STATION	STATION	ROUTE	LOCATION	CONVERT INLET TO MANHOLE (EA)	12" CLASS III RCP STORM SEWER (LF)	PIPE COLLAR, TYPE A (EA)	TYPE T PRECAST DROP INLET 5' X 3' (LF)	CLASS 3 EXCAVATION (CY)	GRANULAR BACKFILL (CY)	REMARKS
CITY OF O'FALLON											
PN-01	109+68	109+68	BRYAN	RT		7.2	1		5.4	5.2	PIPE COLLAR 1-3 TO DCI 1-4
PN-01	109+68	NA	BRYAN	RT				5.7	5.9	4.8	DCI 1-4
PN-02	113+79	113+79	BRYAN	RT		8.3	1		4.9	4.6	PIPE COLLAR 2-14 TO DCI 2-15
PN-02	113+79	NA	BRYAN	RT				5.3	5.3	4.4	DCI 2-15
PN-05	50+98	50+98	FEISE	LT		9.8	1		2.9	2.7	2-10 TO 2-18
PN-05	50+95	NA	FEISE	LT				5.2	5.2	4.3	DCI 2-18
PN-05	51+49.55	NA	FEISE	LT	1			5.2	5.2	4.3	DCI 2-18
					TOTAL	25.3		21.3	35.0	31.0	
					PAY TOTAL	0	26	3	35	31	

EROSION CONTROL

SHEET	STATION	STATION	ROUTE	LOCATION	8' STRAW WATTLE (LF)	INLET CHECK (EA)	REMARKS
CITY OF O'FALLON							
PN-01	109+68	NA	BRYAN	RT		1	
PN-01	107+76	110+84	BRYAN	RT	308.4		
PN-02	113+79	NA	BRYAN	RT		1	
PN-02	112+88	118+00	BRYAN	RT	501.3		
PN-03	119+03	NA	BRYAN	RT		1	
PN-03	118+00	119+61	BRYAN	RT	161.0		
PN-05	50+96	NA	FEISE	LT		1	
PN-05	50+18	52+96	FEISE	LT	142.4		
					SUBTOTAL	1113.1	
					PAY TOTAL	1114	4
CITY OF DARDENNE PRAIRIE							
PN-04	45+27	48+00	FEISE	LT	272.7		
PN-05	48+00	50+18	FEISE	LT	218.2		
					SUBTOTAL	490.9	
					PAY TOTAL	491	0

SODDING

SHEET	STATION	STATION	ROUTE	LOCATION	KENTUCKY BLUEGRASS SODDING (SY)	REMARKS
CITY OF O'FALLON						
PN-01	107+76	113+00	BRYAN	RT	136.6	TREELAWN ONLY
PN-02	113+00	118+00	BRYAN	RT	220.9	TREELAWN ONLY
PN-03	118+00	118+64	BRYAN	RT	43.8	TREELAWN ONLY
PN-05	50+18	52+96	FEISE	LT	86.5	TREELAWN ONLY
					SUBTOTAL	487.7
					PAY TOTAL	488
CITY OF DARDENNE PRAIRIE						
PN-04	45+27	48+00	FEISE	LT	79.5	TREELAWN ONLY
PN-05	48+00	50+18	FEISE	LT	96.9	TREELAWN ONLY
					SUBTOTAL	176.3
					PAY TOTAL	177



DATE PREPARED
02/05/2024

ROUTE
STATE
MO

DISTRICT
SHEET NO.
STL 3

COUNTY
ST. CHARLES

JOB NO.
.

CONTRACT ID.
.

PROJECT NO.
1201400

BRIDGE NO.
.

DATE	DESCRIPTION
.	.
.	.
.	.
.	.
.	.
.	.
.	.

KALECO, LLC
7 BAXTER LANE
CHESTERFIELD, MO 63017
(217-370-7623)

Volkert
CERTIFICATE OF AUTHORITY
NO. F00391502
401 S. 18TH STREET
SUITE 250
ST. LOUIS, MO 63103

BYRAN ROAD & FEISE
ROAD IMPROVEMENTS

SUMMARY OF
QUANTITIES (QU)
(4 OF 5)