

EROSION CONTROL							
EROSION CONTROL SHEET NO.	ROADWAY	STATION BEGIN	STATION END	SIDE	806-70.00 SILT FENCE (L.F.)	806-45.08 INLET PROTECTION DEVICE, SINGLE UNIT - FILTER SOCK/ROLL (EA.)	806-10.05 ROCK DITCH CHECK (L.F.)
1	BRYAN	101+15.20	-	RT	-	1.0	-
1	BRYAN	101+14.91	-	LT	-	2.0	-
1	BRYAN	101+96.00	104+56.91	RT	263.0	1.0	-
1	BRYAN	104+30.83	-	RT	-	-	20.0
1	BRYAN	104+50.16	-	RT	-	-	25.0
1	BRYAN	104+70.55	-	RT	-	-	25.0
1	BRYAN	105+13.77	-	RT	-	-	20.0
1	BRYAN	105+33.64	106+14.49	LT	105.0	-	-
1	BRYAN	106+31.74	-	LT	-	-	20.0
1	BRYAN	106+59.73	-	LT	-	-	20.0
1	BRYAN	106+86.38	-	LT	-	-	20.0
1	BRYAN	106+57.01	107+44.30	LT	94.0	-	-
PROJECT TOTAL					462.0	4.0	150.0

\* TEMPORARY SEEDING IS INCIDENTAL TO BID ITEM EROSION CONTROL AND MULCH.

UTILITY ADJUSTMENTS						
PLAN SHEET NO.	ROADWAY	STATION	OFFSET	603-10.35 ADJUST WATER SERVICE VALVE BOX TO GRADE (EA.)	604-20.10 ADJUST MANHOLE TO GRADE (EA.)	
1	BRYAN	103+03.85	36.5' LT	1.0	-	
1	BRYAN	103+77.60	46.65' LT	-	1.0	
2	BRYAN	105+86.16	43.87' LT	-	1.0	
PROJECT TOTAL				1.0	2.0	

ROCK DITCH LINER						
PLAN SHEET NO.	ROADWAY	STATION BEGIN	STATION END	LOCATION	609-60.20 FURNISHING TYPE 2 ROCK DITCH LINER (C.Y.)	609-60.42 PLACING TYPE 2 ROCK DITCH LINER (C.Y.)
2	BRYAN	101+05.24	102+15.66	RT	156.0	156.0
2	BRYAN	106+13.42	107+03.69	LT	134.0	134.0
PROJECT TOTAL					290.0	290.0

SODDING					
PLAN SHEET NO.	ROADWAY	STATION BEGIN	STATION END	SIDE	803-10.00 SODDING (SY)
1	BRYAN	100+36.70	104+75.05	LT	894.2
1	BRYAN	101+96.00	105+82.28	RT	323.9
1	BRYAN	105+23.35	107+44.30	LT	160.9
PROJECT TOTAL					1,378.9

CLEARING AND GRUBBING (201-30.00)	
1 LUMP SUM	

EARTHWORK					
PLAN SHEET NO.	ROADWAY	STATION BEGIN	STATION END	203-10.00 CLASS "A" EXCAVATION (C.Y.)	203-60.00 COMPACTING EMBANKMENT (C.Y.)
1-2	BRYAN	100+50.00	107+50.00	1080.0	61.0
PROJECT TOTAL				1080.0	61.0

\* VMF = 0.85

FILE: G:\13326\Micro\Highways\13326R0402.dgn  
 PLOTTED ON 4/20/2016 11:01:22 AM  
 DRAWN BY \$USER\$NAME\$\$

REVISION

PER CITY COMMENTS 03/10/16

PER CITY COMMENTS 04/19/16

PROJECT NUMBER

GBA PROJECT NUMBER  
13226.00

DATE

4/20/2016

DESIGNED:  
DSB

DRAWN:  
MLG

REVIEWED

SHEET TITLE

**SUMMARY OF  
QUANTITIES  
SHEET 2 OF 2**

SHEET NUMBER

4