





TYPICAL PLAN VIEW OF VALVE PIT TOP




PUMP STATION BASE REINFORCING



VALVE PIT REINFORCING



VALVE PIT DRAIN BACK FLOW PREVENTER



TYPICAL SECTION OF PUMP STATION & VALVE PIT TOP REINFORCING

- Strain relief shall be provided in the wet well for all motor and control wires.
- Motors shall have ground-fault-interrupting circuit breakers.
- Pumps shall have internal moisture and heat sensors that will not allow the pump to restart without manual resetting at the control panels.
- Stations shall utilize either the floating mercury switch or the TRANS-LOCK type control.
- The valve box shall be designed and built to prevent ground or rain water flooding.

PUMP STATION DATA	
AVERAGE DAILY FLOW	= 78,810 G.P.D.
PEAK FLOW	= 205,945 G.P.D.
T.D.H.	= 16.1 FT.
FLOW VELOCITY	= 2.62 F.P.S.
PUMP CYCLE TIME	= 23.7 MIN.
24 HOUR RETENTION	= 11,012 C.F.
SHUT OFF HEAD - FT.	= 220

- Force mains shall be installed with #2-AWG solid bare copper wire beneath the pipe. Add valve boxes and points of termination shall have an access to this wire. All splices shall be performed with approved split-bolt wire connectors.
- Access points to the tracer wire shall be provided at intervals not greater than 400 feet and shall be plainly marked on the plans. The access points may be of the meter box or lampbox type.
- Forced mains that terminate at manholes or lift stations at a point higher than 2 feet must be made into an outside drop. The drop must have a threaded screw plug or cap at the top clean-out and the bottom inlet shall be at the flow line or floor.
- Where controls are located above ground, the controls shall be of the floating mercury or flow matcher type.
- In wet-well/dry-well stations, control shall be of the bubbler or flow matcher type.
  - The final bubbler tube or canister shall be mounted to provide for easy removal and cleaning.
  - There shall be a platform easily accessible from the ladder to provide easy removal of the final bubbler tube or canister.

- Control wires that enter the wet-well (except moisture sensor wires) shall be either ground fault protected or less than 25 volts to ground.
- Control voltages must be provided for stations of two or more pumps in one of the following ways:
  - Separate, plainly marked fuse or circuit breakers.
  - If the control voltage is taken from the fuse/circuit breaker that supplies power for any other device (e.g., a pump), a method must be provided to switch to an alternate fuse/circuit breaker in the event that breaker or fuse opens.
- All control panels shall contain a GFI duplex receptacle that can provide 20 amperes at 115 volts and shall have a locking cover.
- Each station shall have an audio visual alarm with self contained power source. The alarm shall activate on power outage and/or high water. The high water alarm float shall not be used for any other purpose. Telemetry may be required by the District.
- All pump flange and carrier shall be compatible with the ABS SLIDE RAIL system.
- There shall be an airtight moisture seal between the control panel and the connection box.

- H.M.P. STATION GENERAL NOTES
- Use 3/8 bolts on all connections.
  - Use 5/8 chain (lifting chain).
  - CONNECTION BOX OF MANUAL (RATED NEMA 3B OR NEMA 4B) SHALL BE PROVIDED TO FACILITATE PLUG AND/OR CONTROL WIRE REMOVAL WITHOUT DISRUPTING THE MOISTURE SEAL.
  - Slope valve pit bottom to 3" drain pipe.
  - 15" clearance between check valve arms and valve pit wall.
  - Strain relief fittings to be used on junction box. Strain reliefs shall be plastic and rubber grommet, water resistant box connectors.
  - Fresh water to be provided in valve pit with frost free tap.
  - Contractor to install 3/4" potable water supply in accordance with applicable plumbing codes.
  - All locking hardware will be "best locking hardware" per PWS/D #2 specifications.
  - Power line to enter valve pit through 1" PVC conduit.
  - The 12 foot wide access road and the area within the fence shall be paved with 2" of type "C" asphaltic concrete laid over 6" of type "X" asphaltic concrete. All subgrade shall consist of 6" of well compacted crushed limestone.
  - Power line and level switch cables shall enter valve pit through a 3" PVC conduit connected to the junction box.
  - RACO VERBATIM ALARM DIALER shall be provided per PWS/D #2 specifications.
 

ALARM DIALER TO BE INSTALLED IN IDEAL LOCATION CONTROL PANEL ENCLOSURE. PROVIDE REQUIRED SPACE INSIDE OF PANEL TO ADD ADDITIONAL DEVICES, CIRCUIT BREAKERS AND BATTERIES. THE DIALER SHALL BE INSTALLED WITHIN THE WET WELL SHALL BE PROVIDED WITH A 3" DIA. INVERT TOWARDS THE DRAIN PIPE. USE 2" INCH CONCRETE FILLER.
  - LIFT STATION SHALL BE ENCLOSED BY A 6" FT. CHAIN LINK OR WIRE MESH FENCE WITH 3 STRANDS OF BARB WIRE. AT THE TOP A GATE SHALL BE PROVIDED WITH TWO LOCKS. THE VALVE PIT FLOOR SHALL BE SLOPED WITH A THREE INCH INVERT TOWARDS THE DRAIN PIPE. USE 2" INCH CONCRETE FILLER.
  - Pump slide rails shall be supported with brackets every 15 feet. Concrete supports placed underneath the valves and tees inside the valve pit shall be placed as:
    - The supports are solidly secured in the valve pit floor.
    - They allow for a minimum of 10" clearance under the valve bodies.
    - Not to interfere with flange bolt removal.
  - All sewage pipes running through the valve pit and wet well walls shall be passed through an A-lock type compression fittings.
  - The wet well and valve pit shall be provided with Bilco, Type O or K aluminum sidewalk type access doors with padlock type lugs.
  - All pump power and control leads, level control, and float wires shall be hung from the switch bracket supplied by the pump manufacturer. The switch bracket shall be attached to the wet well access door frame. Pump shall be wired so that they alternate, except where the influent rate exceeds the capacity of one pump and activates the second pump.
  - Shop drawings shall be submitted to PWS/D #2 for review in accordance with the general conditions and shall include mechanical and electrical details of equipment as well as schematics and interconnection drawings. A minimum of three (3) sets of drawings shall be furnished. The following shop drawings are required:
    - Main Circuit Breaker
    - Wiring Diagrams
    - Motor Starters and Control Devices
    - Alarm and Transmitting Equipment
    - Pump Control Panel
  - All force main station piping shall be D.I.P. OR APPROVED EQUAL. SPECIFICALLY ALL OF THE PIPES CONNECTED TO THE VALVES AND LIFTINGS WITHIN THE VALVE VAULT SHALL BE D.I.P. OR APPROVED EQUAL. THE DRAIN PIPE FROM THE VALVE VAULT TO THE WET WELL SHALL BE SCH-40 AS SHOWN.
  - ALL WET WELL STEPS SHALL BE P.V.C. COATED.
  - The pump station manufacturer shall be present and responsible for the initial start up of the station. The manufacturer will further be responsible to check for proper installation of the unit and will make all necessary adjustments to insure proper operation, fully meeting the performance specifications.
  - Float requirements are as follows:
    - Off float - The pump shall have water covering a minimum of 1/2 the pump rotor at the off level.
    - First Trip - Is less than 1/2" above top of pump rotor.
    - Second Trip - Is less than 2" above top of pump rotor.
    - High Level - Is less than 1/2" above the top of pump rotor and Alarm is more than 1 in. below the 24 hr. retention line.
    - ADD FLOAT SWITCH FOR FUTURE PUMP.
  - Run #12 AWG stranded conductor with insulation for direct burial over the force main. Splice only with split bolt type of wire connectors. Provide access to wire at valve pit and receiving manhole.
  - Protect wet well and valve pit manufactured by "Kleiner Bros." may be used in lieu of cast in place reinforced concrete structures.
  - Permanent sign that reads "WARNING, KEEP OFF" shall be placed on the wet well cover so that the sign will be visible to anyone who is not supposed to be there.