



DOORS TALL  
= FLOOR  
SECTION

EXISTING TELEPHONE SERVICE  
TO SMPB, PROTECT AND RETAIN  
SERVICE FOR DURATION OF PROJECT.

**SOUTH WING AND CENTRAL UTILITY SPACE**  
SCALE: 1/8" = 1'-0"



- DEMO KEY NOTES**
- Ⓛ REMOVE PARTITION, OR WALL, AND ALL ELECTRICAL CONDUIT AND WIRING BACK TO PANEL -- AS SHOWN AS DASHED LINES ON PLAN. (PROTECT ALL EXISTING TERRAZZO FLOORING TO REMAIN IN PLACE).
  - Ⓜ REMOVE DOOR AND FRAME.
  - Ⓨ REMOVE DOOR AND FRAME AND SAVE FOR REUSE.
  - Ⓩ REMOVE LAV, COLD WATER, HOT WATER, SANITARY PIPES AND ALL PIPING BELOW FLOOR.
  - ⓐ REMOVE WINDOW FRAME, CAULK AND SILL.
  - ⓑ REMOVE CASEWORK - CAP ALL PLUMBING CONNECTION WHERE APPLICABLE.
  - ⓓ NOT USED
  - ⓔ REMOVE WOOD WORK / CASE WORK AND SAVE FOR RE-INSTALLATION.
  - ⓕ EXISTING DOORS TO REMAIN.
  - ⓖ REMOVE COUNTERTOP.
  - ⓗ NOT USED
  - ⓓ NOT USED
  - ⓓ NOT USED
  - ⓓ REMOVE TOILET STALL PARTITIONS.
  - ⓓ NOT USED
  - ⓓ NOT USED
  - ⓓ REMOVE WATER CLOSET, COLD WATER, AND SANITARY, AND PIPING BELOW FLOOR -- IF MARBLE TOILET PARTITIONS EXIST, REMOVE (INCLUDING DOORS) & SAVE FOR REUSE.
  - ⓓ REMOVE CARPET AND TACK STRIP CLEAN.
  - ⓓ NOT USED
  - ⓓ REMOVE CAST IRON RADIATOR (OR UNIT VENTILATOR) AND ALL ASSOCIATED PIPING.
  - ⓓ NOT USED
  - ⓓ NOT USED
  - ⓓ NOT USED
  - ⓓ NOT USED
  - ⓓ NOT USED
  - ⓓ NOT USED
  - ⓓ NOT USED
  - ⓓ REMOVE STACK.
  - ⓓ REMOVE PORTION OF EXISTING WALL FOR INSTALLATION OF NEW DOOR.
  - ⓓ REMOVE EXISTING MARBLE CHASE WALL.
  - ⓓ REMOVE EXISTING DOORS & FRAME ARCH -- CLERESTORY TO REMAIN.
  - ⓓ REMOVE DRAPEY ROD.
  - ⓓ REMOVE HAND RAIL(S).
  - ⓓ REMOVE EXISTING A.C. UNIT, PATCH AND FILL OPENING TO MATCH ADJOINING SURFACES. REUSE SALVAGE BRICKS OR APPROVED EQUAL. TOOTH IN ALL MASONRY.



Revisions

CONSTRUCTION ISSUE	DECEMBER 5, 1997
--------------------	------------------

Project No.	96036
Date	SEPT. 4, 1997
Designed	
Drawn	MAG3
Drawing No.	D-8