



**UTILITY SPACE PLUMBING PLAN - WEST WING**  
 SCALE: 1/8" = 1'-0"

**KEYED NOTES:**

- ① SANITARY WASTE DOWN APPROXIMATELY 18" AT THIS POINT FROM ELEVATED SANITARY LINE IN BASEMENT. VERIFY FINAL ELEVATIONS FROM FARTHEST POINT IN BASEMENT PRIOR TO ESTABLISHING TIE-IN.
- ② CORE DRILL FOUNDATION WALL AS REQUIRED TO ACCEPT NEW 6" SANITARY MAIN.
- ③ BASE BID: CONNECT NEW 6" WATER SERVICE WITH BACKFLOW PREVENTER IN MECH/ELECTRICAL ROOM. SEE SHEET P-8 AND FIRE PROTECTION PLANS.  
ALTERNATE BID: CONTRACTOR TO PROVIDE ALTERNATE COST TO REMOVE AND REPLACE EXISTING WATER MAIN WITH NEW 6" MAIN (APPROXIMATELY 440 LIN. FT.), FURNISH NEW BUILDING SHUTOFFS (O'FALLON AND ST. MARY'S FACILITIES) BACKFLOW PREVENTER AND WATER METERS.
- ④ HUB DRAIN FOR MECHANICAL UNIT CONDENSATE.

Revisions  
 CONSTRUCTION ISSUE  
 DECEMBER 5, 1997  
 CHANGE ORDER NO. 1  
 JANUARY 27, 1998

Project No.	96036
Date	SEPT. 4, 1997
Designed	
Drawn	
Drawing No.	