



GENERAL NOTES:

1. PROVIDE A WET PIPE AUTOMATIC SPRINKLER SYSTEM INSTALLED IN COMPLIANCE WITH THE LATEST APPLICABLE EDITION OF NFPA 13.
2. FINAL SPRINKLER HEAD SELECTION AND LOCATION IS THE RESPONSIBILITY OF THE SPRINKLER CONTRACTOR AND SHALL BE IN ACCORDANCE WITH NFPA 13 AND THE MANUFACTURERS LISTING.
3. COORDINATE FINAL LOCATION OF SPRINKLER HEADS WITH LIGHTS, DIFFUSERS, GRILLE, ETC.
4. PROVIDE A WET STANDPIPE SYSTEM IN EACH STAIRWELL INSTALLED IN ACCORDANCE WITH THE LATEST EDITION OF NFPA 14 AND THE 1996 BOCA NATIONAL BUILDING CODE.

KEYED NOTES

- 1 AUTOMATIC SPRINKLER PIPING FOR WEST LOBBY SHALL BE RUN IN 25 FT. LEVEL SOFFIT. PROVIDE PENDENT SPRINKLERS AS INDICATED.
- 2 STANDPIPE RISER. PROVIDE OUTLETS AS REQUIRED BY CODES AND LOCAL FIRE DISTRICT.
- 3 FEED MAIN FOR SECOND FLOOR. PROVIDE INDICATING CONTROL VALVE AND TAMPER SWITCH AT CONNECTION TO RISER.



SECOND FLOOR FIRE PROTECTION PLAN - WEST WING AND CENTRAL LOBBY

SCALE: 1/8" = 1'-0"



Revisions

CONSTRUCTION ISSUE	DECEMBER 5, 1997
CHANGE ORDER NO. 1	JANUARY 27, 1998

Project No.	96036
Date	SEPT. 4, 1997
Designed	
Drawn	
Drawing No.	FP-3