

THREE PHASE PANEL SCHEDULE

PANEL NAME: ERP2-2
 VOLTS: 120/208
 PHASE: 3

MAIN BKR: 150A
 BUS SIZE: 200A
 MOUNTING: SURFACE

T.C.L. = 17500 VA

Ø	DIRECTORY	LOAD	WIRE	AMP	POLE	POLE	AMP	WIRE	LOAD	DIRECTORY	Ø
A	B-1 (BOILER CONTROL)	720	12	15	1	1	15	12	1080	RECEPTACLE	A
B	B-1 (BOILER CONTROL)	720	12	15	1	3	15	12	1080	RECEPTACLE	B
C	JUNCTION BOX	1080	12	15	1	5	15	12	1080	RECEPTACLE	C
A	JUNCTION BOX	1080	12	15	1	7	15	12	1080	RECEPTACLE	A
B	JUNCTION BOX	1080	12	15	1	9	15	12	1080	RECEPTACLE	B
C	JUNCTION BOX	1080	12	15	1	11	15	12	1080	RECEPTACLE	C
A	JUNCTION BOX (W.C.)	1000	12	20	1	13	20	12	1080	RECEPTACLE	A
B						15		12	1260	RECEPTACLE	B
C						17		12	1440	RECEPTACLE	C
A						19					A
B						21					B
C						23					C
A						25					A
B						27					B
C						29					C
A						31					A
B						33					B
C						35					C
A						37					A
B						39					B
C						41					C

NOTES: 1. ALL CONDUCTORS SHALL BE IN 3/4" CONDUIT.
 2. PROVIDE ADDITIONAL ISOLATED GROUND BUS.

CONSTRUCTION DOCUMENTS

Project No. 96036
 Date SEPT. 4, 1997
 Designed
 Drawn
 Drawing No.

Revisions
 CONSTRUCTION ISSUE
 DECEMBER 5, 1997

CONSTRUCTION DOCUMENTS

 **City of O'Fallon**
 138 South Main Street
 O'Fallon, Missouri 63366

NEW CITY HALL COMPLEX



 **CRD Campbell, Inc.**
 Engineers Architects Planners

One Campbell Plaza 5th & Arsenal St. Louis, MO 63139 314/781-2004