



retaining wall manufacturer's construction recommendations and/or as noted herein.  
**Materials**  
The Leveling Pad shall be constructed 1" minus or clean compacted by at least 4 passes with a vibratory compactor with minimum dimensions of 6" thick and 24" wide.  
Retaining Wall Units shall be Rockwood Classic or equal. Units must be 12" deep. Concrete wall units shall meet the requirements of ASTM C90-90 and compressive strength shall be a minimum of 3000 psi. The maximum water absorption shall be limited to 8.0 percent.  
The block unit fill material shall be 1" clean crushed limestone.  
The reinforced wall backfill material shall be crushed limestone 1"-2" minus or screenings, placed in 8" max lifts & compacted to at least 95% standard proctor.  
Geogrid shall be Geostar HP200 as indicated on the plan, or approved equivalent.  
Filter Fabric shall be Mirafi 140N or approved equivalent.  
Drain Tile shall be 4" HDPE, perforated.  
The Soil Cap shall consist of compacted low plastic impervious soil above the granular backfill in areas not to be paved.  
**Wall Foundation Excavation**  
Foundation soil shall be excavated as required for the leveling pads and the reinforcing zone. Any soils that are soft, plastic (LL > 50%), frozen, or wet and untested soils shall be removed and replaced to 90% modified Proctor under the direction of the geotechnical engineer.  
**Wall Construction**  
The wall shall consist of units on the leveling pad. Install the next course in a running bond stack. Adjust for setback per course. Backfill, install reinforcement as required, backfill, and place geogrid. The geogrid shall be placed horizontally and laid flat on the reinforcing fill material. The geogrid shall be placed in one continuous piece across the entire width of the wall. The geogrid shall be between the blocks and the backfill.  
**Wall Backfill**  
Backfill material shall be crushed limestone 1"-2" minus or screenings, placed in 8" max lifts and compacted. Backfill shall be placed, spread and compacted in such a manner that minimizes wrinkles and movement. Hand held tamper shall be used for placement only hand operated equipment shall be used in the 4' zone directly behind the wall. The front of the wall shall be backfilled with crushed limestone 1"-2" minus or screenings.  
**Protection of Work Areas**  
The surfaces surrounding the wall shall be graded daily at the end of each day to provide positive drainage away from the wall. Grading shall include proper contouring of fills in adjacent areas to prevent surface water from flowing toward the wall. Finishing grade should be completed in accordance with the approved site development plan.  
**Miscellaneous**  
If a fence or guardrail is to be installed adjacent to the wall under a separate plan. We recommend that PVC or sonotube sleeves be placed ss the wall is being backfilled to prevent a need to excavate and protect all utilities. The contractor shall notify Engineering Solutions, P.C. of any utility conflict affecting this work.  
**General Notes**  
Existing utilities are not shown. The contractor shall locate and protect all utilities. The contractor shall notify Engineering Solutions, P.C. of any utility conflict affecting this work.  
Unless otherwise noted all temporary sheeting and shoring shall be the responsibility of the contractor under a separate design.  
All job site worker and public safety is strictly the responsibility of the contractor. The contractor shall comply with all OSHA regulations & requirements.  
Engineering Solutions, P.C. is available upon request to inspect the work in progress to ensure construction compliance with this plan. Please notify Engineering Solutions, P.C. in advance of the work if field inspection is requested.  
**The Owner or Owner's Representative is responsible for ensuring that construction by others adjacent to the wall does not disturb the wall or place heavy loads, including loads such as water pressure, temporary grades, or equipment loading, on the wall. Heavy paving or grading equipment shall not be allowed to travel within 10 feet behind the back of the wall face. Equipment with wheel loads in excess of 150 psf shall not be allowed to travel within 10 feet behind the back of the wall face. Owner or Owner's Representative to coordinate traffic flow and ensure traffic is directed away from the wall structure until final grading and surface drainage collection systems are completed.**  
Global stability and settlement are the responsibility of the designer. Global stability and settlement are the responsibility of the designer.




Date: 4/17/17  
Revisions

#	Description	Date



Sheet:  
RW 1 of 1



**SEE REVISED APPROVED 10/13/2017**