


Drawing name: V:\2008\327 Highway N Assembly\Drawings\Engineering\Improvements\9327 IMP FOR PRINTING.dwg Printed on: Feb 11, 2025 - 10:28am Plotted by: jankenhous




Plan View / Sheet Index

## Drawing Index

1.1	COVER SHEET
1.2	GENERAL NOTES
1.3	CONDITIONS OF APPROVAL
1.6-1.8	LOT INFORMATION
2.9-2.14	GRADING PLAN
3.9-3.14	SITE PLAN
4.9-4.14	UTILITY PLAN
5.10, 5.12-5.16	STREET PROFILES
6.1-6.8	SANITARY PROFILES
7.10-7.18	STORM PROFILES
7.27-7.28, 7.30	STORM HYDRAULICS
8.9-8.14	DRAINAGE AREA MAP
8.23	DRAINAGE AREA MAP INFORMATION
9.1, 9.8-9.13	DETENTION / WATER QUALITY DETAILS
9.19-9.21	DOWNSTREAM DEFENDER DETAILS
11.3-11.4	TRAFFIC CONTROL PLAN
12.1, 12.4, 12.5	ZONE OF INFLUENCE SECTIONS
13.3, 13.9-13.12	ENTRANCE DETAILS / WARPINGS
3.16-13.17	TRAFFIC CALMING DETAILS
13.22-13.23	AMENITY PLAN
13.24	LANDSCAPE PLAN
L-1-L-2	EROSION CONTROL DETAILS
DTL-1 - DTL-2	DUCKETT CREEK SANITARY DETAILS
DTL-3 - DTL-6A	STORM SEWER DETAILS
DTL-7	PWSD#2 WATER DETAILS
DTL-8	PAVEMENT DETAILS
DTL-9 - DTL-11.1	EMERGENCY RELIEF PATH DETAILS
DTL-12	CONSTRUCTION DETAILS
DTL-14	

City of O'Fallon Construction work hours per City Ordinance 3429 as shown in Section 500.420 of the Municipal Code of the City of O'Fallon are as follows:

October 1 through May 31	
7:00 A.M. To 7:00 P.M.	Monday Through Sunday
June 1 Through September 30	
6:00 A.M. To 8:00 P.M.	Monday Through Friday
7:00 A.M. to 8:00 P.M.	Saturday and Sunday



LOCATION MAP  
N.T.S.

## Benchmarks

PROJECT BENCHMARK:  
NGS CONTINUOUSLY OPERATING REFERENCE STATION (CORS) ID MOOF  
ELEVATION = 496.90' (NAVD 88 OBSERVED).

SITE BENCHMARK #1: ELEVATION = 659.60' (NAVD 88)

"ALUMINUM DISK" LABELED AS CONTROL POINT FOUND AT THE NORTH SIDE OF HIGHWAY N, 21 FEET EAST OF THE CENTERLINE OF GRAVEL FOR WEST ENTRANCE TO 1065 EAST HIGHWAY N, 19 FEET NORTH OF NORTH EDGE OF ASPHALT, 53 FEET NORTH OF A MAILBOX FOR 910 EAST HIGHWAY N AND 79 FEET NORTHWEST OF A UTILITY POLE.

SITE BENCHMARK #2: ELEVATION = 594.08' (NAVD 88)

"SPIKE" IN UTILITY POLE AT THE WEST SIDE OF HOPEWELL ROAD, 173 FEET NORTH OF THE NORTHERNMOST OF TRIPLE CULVERT FOR CREEK CROSSING UNDER HOPEWELL ROAD, 8 FEET WEST OF WEST EDGE OF ASPHALT, 41 FEET SOUTHWEST OF A UTILITY POLE ON THE EAST SIDE OF HOPEWELL ROAD AND 188 FEET SOUTH OF MAILBOX FOR 2512 HOPEWELL ROAD (LOCATION SHOWN HEREON).

SITE BENCHMARK #3: ELEVATION = 556.27' (NAVD 88)

"PK" NAIL AT EDGE OF ASPHALT AT THE WEST EDGE OF HOPEWELL ROAD, JUST NORTH OF ENTRANCE DRIVE TO 3037 HOPEWELL ROAD, 11 FEET EAST OF SOUTHEAST CORNER OF VINYL FENCE, 39 FEET SOUTHWEST OF MAILBOX FOR 3136 HOPEWELL ROAD AND 56 FEET NORTH OF A UTILITY POLE (LOCATION SHOWN HEREON).

## Estimated Earthwork

740,000 CUBIC YARDS CUT

NOTE:  
QUANTITIES ARE ESTIMATES AND WILL CHANGE BASED ON THE ACTUAL SIZE OF SEWERS AND FOUNDATIONS CONSTRUCTED AND THE TYPE OF MATERIAL EXCAVATED. ANY EXCESS MATERIALS SHALL BE DISPLACED ON THE PROJECT SITE.

THE ESTIMATED EARTHWORK QUANTITIES ARE CALCULATED FOR PERMIT AND INSPECTION PURPOSES ONLY. THESE QUANTITIES ARE NOT TO BE USED FOR BIDDING. CONTRACTOR TO VERIFY ALL YARDAGE QUANTITIES.

## Zoning and Density Notes

1. GROSS AREA OF SITE:	261.50 ACRES
2. CURRENT ZONING:	R-1 SINGLE FAMILY RESIDENTIAL W/ P.U.D. (CITY OF O'FALLON)
3. CURRENT OWNER:	HARVEST HOPEWELL, LLC 5091 NEW BAUMGARTNER ROAD ST. LOUIS, MO 63129
4. DWELLING UNITS PROPOSED:	896 UNITS
5. OVERALL PARKING: REQUIRED: (2.0 SPACES/UNIT)X 734 UNITS=1468 SPACES (2.5 SPACES/UNIT)X 162 UNITS=405 SPACES	
TOTAL SPACES PROVIDED:	1630 GARAGE SPACES 1630 DRIVEWAY SPACES 87 GUEST SPACES 3347 SPACES PROVIDED
6. VILLAGE 'A' PARKING LOTS 1A-98A: PARKING REQUIRED: (2.0 SPACES/UNIT)X 98 UNITS=196 SPACES GUEST PARKING REQUIRED: (0.5 SPACES/UNIT)X 98 UNITS=49 SPACES	
TOTAL SPACES PROVIDED:	98 GARAGE SPACES 98 DRIVEWAY SPACES 49 GUEST SPACES 7 MAIL PARKING SPACES 252 SPACES PROVIDED
7. VILLAGE 'A' PARKING LOTS 99A-162A: PARKING REQUIRED: (2.0 SPACES/UNIT)X 64 UNITS=128 SPACES GUEST PARKING REQUIRED: (0.5 SPACES/UNIT)X 64 UNITS=32 SPACES	
TOTAL SPACES PROVIDED:	64 GARAGE SPACES 64 DRIVEWAY SPACES 32 GUEST SPACES 4 MAIL PARKING SPACES 170 SPACES PROVIDED

# A SET OF CONSTRUCTION PLANS FOR HARVEST AT HOPEWELL CITY OF O'FALLON PHASE 2

## Legal Description

A TRACT OF LAND LOCATED IN FRACTIONAL SECTION 17 AND IN U.S. SURVEYS 61 AND 418, TOWNSHIP 26 NORTH, RANGE 2 EAST OF THE FIFTH PRINCIPAL MERIDIAN, ST. CHARLES COUNTY, MISSOURI AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT AN OLD STONE AT THE COMMON CORNER OF SECTIONS 7, 8, 17 AND 18 OF ABOVE-SAID TOWNSHIP AND RANGE; THENCE ALONG THE NORTH LINE OF ABOVE-SAID FRACTIONAL SECTION 17, SOUTH 89°00'42" EAST, 1258.78 FEET TO A POINT ON THE WEST LINE OF ABOVE-SAID U.S. SURVEY 61; THENCE LEAVING SAID NORTH LINE AND ALONG SAID WEST LINE, NORTH 06°43'19" EAST, 3261.30 FEET TO AN OLD STONE AT THE NORTHWEST CORNER OF SAID U.S. SURVEY 61; THENCE LEAVING SAID WEST LINE AND ALONG THE NORTH LINE OF SAID U.S. SURVEY 61, SOUTH 81°58'43" EAST, 1136.94 FEET; THENCE LEAVING LAST SAID NORTH LINE, SOUTH 36°07'10" WEST, 251.16 FEET, TO THE BEGINNING OF A 125.00 FOOT RADIUS NON-TANGENT CURVE, WHICH RADIUS POINT BEARS SOUTH 45°03'30" WEST; THENCE SOUTHEASTERLY ALONG SAID CURVE HAVING A CENTRAL ANGLE OF 07°50'12", AN ARC DISTANCE OF 17.10 FEET TO A POINT OF TANGENCY; THENCE SOUTH 37°06'18" EAST, 127.71 FEET, TO THE BEGINNING OF A 125.00 FOOT RADIUS TANGENT CURVE TO THE RIGHT; THENCE SOUTHEASTERLY ALONG SAID CURVE HAVING A CENTRAL ANGLE OF 19°06'42", AN ARC DISTANCE OF 41.69 FEET TO A POINT OF NON-TANGENCY; THENCE SOUTH 83°07'49" EAST, 231.29 FEET TO A POINT ON THE WEST RIGHT-OF-WAY LINE OF HOPEWELL ROAD, WIDTH VARIES, SAID POINT BEING 20 FEET PERPENDICULAR DISTANCE WEST OF THE ORIGINAL CENTERLINE OF SAID HOPEWELL ROAD, TO THE BEGINNING OF A 555.00 FOOT RADIUS NON-TANGENT CURVE, WHICH RADIUS POINT BEARS SOUTH 73°13'21" EAST; THENCE SOUTHERLY ALONG SAID CURVE HAVING A CENTRAL ANGLE OF 09°54'28", AN ARC DISTANCE OF 97.70 FEET TO A POINT OF TANGENCY; SOUTH 06°52'11" WEST, 132.26 FEET; SOUTH 83°07'49" EAST, 10.00 FEET; SOUTH 06°52'11" WEST, 1509.94 FEET; NORTH 83°28'44" WEST, 23.42 FEET; SOUTH 06°52'11" WEST, 298.75 FEET; SOUTH 83°07'49" EAST, 23.42 FEET; AND SOUTH 06°52'11" WEST, 345.15 FEET TO THE NORTHEAST CORNER OF A TRACT OF LAND CONVEYED TO CENTRAL ELECTRIC POWER COOPERATIVE (CEPC) BY DOCUMENT RECORDED IN DEED BOOK 1886 PAGE 1372 OF THE ST. CHARLES COUNTY, MISSOURI RECORDS; THENCE LEAVING SAID WEST RIGHT-OF-WAY LINE AND ALONG THE NORTH, WEST AND SOUTH LINES OF SAID CEPC TRACT THE FOLLOWING COURSES AND DISTANCES: NORTH 82°57'48" WEST, 325.00 FEET TO AN OLD IRON ROD; NORTH 07°02'12" EAST, 125.13 FEET; SOUTH 70°14'48" WEST, 308.07 FEET; SOUTH 07°02'03" WEST, 251.14 FEET TO AN OLD IRON ROD; AND SOUTH 82°57'48" EAST, 600.77 FEET TO THE SOUTHEAST CORNER OF SAID CEPC TRACT, SAID CORNER BEING ON SAID WEST RIGHT-OF-WAY LINE OF HOPEWELL ROAD, BEING 20 FEET PERPENDICULAR DISTANCE WEST OF SAID CENTERLINE OF HOPEWELL ROAD; THENCE LEAVING SAID SOUTH LINE OF CEPC TRACT AND ALONG SAID WEST RIGHT-OF-WAY LINE, SOUTH 06°52'11" WEST, 896.62 FEET TO A POINT ON THE SOUTH LINE OF SAID U.S. SURVEY 61, SAID LINE ALSO BEING THE NORTH LINE OF A TRACT OF LAND CONVEYED TO DAVID D. KRANZ AND AMY E. KRANZ, HUSBAND AND WIFE, BY DOCUMENT RECORDED IN DEED BOOK 4481 PAGE 523 OF SAID RECORDS; THENCE LEAVING SAID WEST RIGHT-OF-WAY LINE AND ALONG SAID SOUTH LINE OF U.S. SURVEY 61, NORTH 82°10'53" WEST, 485.98 FEET; THENCE LEAVING LAST SAID SOUTH LINE, SOUTH 07°18'29" WEST, 196.45 FEET TO A POINT ON THE NORTH LINE OF LOT B OF HOPEWELL FARM SUBDIVISION, NORTH 51°53'32" EAST, 1050.48 FEET; AND NORTH 48°19'28" WEST, 1196.22 FEET TO THE WESTERNMOST CORNER OF SAID LOT B, SAID CORNER ALSO BEING THE WEST LINES OF SAID LOT B THE FOLLOWING COURSES AND DISTANCES: SOUTH 31°11'12" WEST, 915.79 FEET; SOUTH 38°27'37" WEST, 733.00 FEET TO AN OLD IRON PIPE; SOUTH 36°26'38" EAST, 730.15 FEET; SOUTH 37°02'32" EAST, 483.42 FEET; AND SOUTH 31°11'07" EAST, 238.98 FEET TO AN OLD IRON ROD AT THE SOUTHEAST CORNER OF SAID LOT B; THENCE LEAVING SAID WEST RIGHT-OF-WAY LINE AND ALONG THE SOUTH AND WEST LINES OF SAID LOT B THE FOLLOWING COURSES AND DISTANCES: SOUTH 49°48'57" WEST, 1077.80 FEET TO AN OLD IRON ROD; NORTH 37°16'53" WEST, 523.96 FEET TO AN OLD STONE; SOUTH 53°17'36" WEST, 233.68 FEET TO AN OLD IRON PIPE; NORTH 44°22'18" WEST, 905.75 FEET TO AN OLD IRON PIPE ON THE NORTH LINE OF ABOVE-SAID U.S. SURVEY 418; ALONG THE NORTHWEST LINE OF U.S. SURVEY 418, SOUTH 52°47'20" WEST, 84.19 FEET TO THE EASTERNMOST CORNER OF U.S. SURVEY 891; ALONG THE NORTHEAST LINE OF SAID U.S. SURVEY 891, NORTH 37°39'48" WEST, 182.99 FEET TO THE SOUTHERNMOST CORNER OF LOT A OF SAID HOPEWELL FARM SUBDIVISION; NORTH 51°53'32" EAST, 1050.48 FEET; AND NORTH 48°19'28" WEST, 1196.22 FEET TO THE WESTERNMOST CORNER OF SAID LOT B, SAID CORNER ALSO BEING THE NORTHEAST CORNER OF SAID LOT A; THENCE LEAVING SAID WEST LINE AND ALONG THE NORTH LINE OF SAID LOT A, NORTH 88°45'45" WEST, 134.64 FEET TO THE NORTHWEST CORNER OF SAID LOT A, SAID CORNER BEING ON THE WEST LINE OF SAID FRACTIONAL SECTION 17; THENCE LEAVING LAST SAID NORTH LINE AND ALONG SAID WEST LINE OF FRACTIONAL SECTION 17, NORTH 00°33'36" EAST, 1829.52 FEET TO THE POINT OF BEGINNING AND CONTAINS 11,390.877 SQUARE FEET, OR 261.499 ACRES, MORE OR LESS ACCORDING TO SURVEY PERFORMED BY THE STERLING COMPANY DURING THE MONTH OF MARCH, 2021 UNDER ORDER NUMBER 20-09-327

## Legend

EXISTING		PROPOSED
--- 542 ---	CONTOURS	--- (542) ---
X 536	SPOT ELEVATIONS	XXX.X
--- X --- X ---	CENTER LINE	---
---	BUILDINGS, ETC.	---
---	TREE LINE	---
---	FENCE	--- X --- X ---
---	SILTATION CONTROL FENCE	--- X --- X --- X ---
---	STORM SEWERS	---
---	SANITARY SEWERS	---
---	CATCH BASIN	---
---	AREA INLET	---
---	GRATED INLET	---
---	DOUBLE CURB INLET	---
---	STORM MANHOLE	---
---	SANITARY MANHOLE	---
---	FLARED END SECTION	---
---	CLEANOUT	---
---	LATERAL CONNECTION	---
---	UTILITY OR POWER POLE	---
---	FIRE HYDRANT	---
---	TEST HOLE	---
---	PAVEMENT	---
---	GAS MAIN & SIZE	---
---	WATER MAIN & SIZE	---
---	TELEPHONE	---
---	ELECTRIC (U) UNDERGROUND	---
---	ELECTRIC (O) OVERHEAD	---
---	FLOW LINE	---
---	TO BE REMOVED	---
---	TO BE REMOVED & RELOCATED/REPLACED	---
---	TOP OF CURB	---
---	SWALE	---
---	LIGHT STANDARD	---
---	STREET SIGN	---
---	PARKING STALLS	---
---	YARD LIGHT	---
---	JURISDICTIONAL STREAM	---
---	H.R. ~ DENOTES PROPOSED HANDICAP RAMP W/ TRUNCATED DOME	---
---	TF ~ TOP OF FOUNDATION ELEVATION	---
---	BF ~ BASEMENT FLOOR ELEVATION	---
---	LS ~ LATERAL STATION FROM DOWNSTREAM MANHOLE	---
---	NOTE: AN "A" WITH THE LOT NUMBER INDICATES A LOT WHICH IS MORE SUSCEPTIBLE TO STREET MOVEMENT.	---

## Conditions of Approval From Planning and Zoning

SEE SHEET 1.3 NOTES FOR A LIST OF THE CONDITIONS OF APPROVAL FROM PLANNING AND ZONING

## Project Data

1. TOTAL SITE AREA:	261.5 ACRES
2. TOTAL PHASE 2 AREA:	86.1 ACRES
3. TOTAL PHASE 2 LOTS:	252 LOTS
4. TOTAL DISTURBED AREA:	228.3 ACRES

5. FLOOD NOTE FOR TOTAL DEVELOPMENT:  
ACCORDING TO THE FLOOD INSURANCE RATE MAP OF THE COUNTY OF ST. CHARLES, MISSOURI, UNINCORPORATED AREAS (COMMUNITY PANEL NUMBERS 29183C02156 & 29183C04050 DATED JANUARY 20, 2016), THIS PROPERTY LIES PARTIALLY WITHIN ZONE 'X' (UNSHADED), ZONE 'X' (SHADED), ZONE 'AE' AND ZONE 'AE' (FLOODWAY).

THE PHASE 2 PORTION OF THIS DEVELOPMENT LIES WITHIN ZONE 'X' (UNSHADED).

DURING PHASE 1A AND PHASE 1B OF THE OVERALL DEVELOPMENT THE FOLLOWING LOTS HAVE BEEN REMOVED FROM THE FLOODPLAIN WITH LOMR CASE NO. 23-07-0866A DATED NOV. 03, 2023: 3180-3280, 3460-3510

DURING PHASE 3 OF THE OVERALL DEVELOPMENT THE FOLLOWING LOTS WILL BE REMOVED FROM THE FLOODPLAIN DURING THE LOMR PROCESS AFTER THEY ARE BROUGHT UP TO GRADE: 6160-6170

NO LOTS WILL REMAIN IN THE FLOODPLAIN AFTER GRADING IS COMPLETE.

HOMES BUILT ON THE LOTS LISTED ABOVE WILL REQUIRE AN ELEVATION CERTIFICATE PRIOR TO OCCUPANCY SHOWING THAT THEY MEET THE CITY'S CODE FOR THE LOWEST FLOOR BEING 2 FEET ABOVE THE BASE FLOOD ELEVATION.


## Tree Ordinance

EXISTING TREES	59.5 AC.
TREES REMOVED	47.6 AC.
TREES SAVED	11.9 AC.
TREES REQUIRED TO BE SAVED	20.0% (11.9 AC)
PERCENTAGE OF TREES SAVED	20.0%

NO PLANTING MITIGATION REQUIRED  
COMPLIED WITH CHAPTER 402, SECTION 402.040

## EMERGENCY CONTACT

ELITE DEVELOPMENT SERVICES, LLC  
17415 NORTH OUTER FORTY ROAD  
CHESTERFIELD, MISSOURI 63005  
TONY WAYHART  
PH. 314-742-1670

CITY OF O'FALLON  
ENGINEERING DEPARTMENT  
ACCEPTED FOR CONSTRUCTION  
BY:  DATE **FEBRUARY 12, 2025**  
PROFESSIONAL ENGINEER'S SEAL  
INDICATES RESPONSIBILITY FOR DESIGN

PROPOSED AMENITY AREAS IS NOT PART  
OF THIS APPROVAL. TO BE DESIGNED BY  
OTHERS

City of O'Fallon Standard Notes and Details - July 2019

ISSUE	REMARKS/DATE
1	2024-08-13, INITIAL SUBMITTAL CITY PH.2
2	2024-11-08, REVISED PER CITY COMMENTS
3	2025-01-03, REVISED PER CITY COMMENTS
4	2025-01-16, REVISED PER ST. CHARLES CO
5	2025-02-11, REVISED PER CITY COMMENTS

## Utility Contacts

### Sanitary Sewers

City of O'Fallon  
100 N. Main St.  
O'Fallon, MO 63366  
Contact: 636-240-2000

Duckett Creek Sanitary District  
3550 Highway K  
O'Fallon, MO 63368  
636-441-1244

### Water

City of O'Fallon  
100 N. Main St.  
O'Fallon, MO 63366  
Contact: 636-240-2000  
Missouri American Water Co.  
727 Craig Rd.  
St. Louis, MO 63141  
1-866-430-0820

Public Water Supply District No. 2  
P.O. Box 967  
O'Fallon, MO 63366  
636-561-3737

### Storm Sewer

City of O'Fallon  
100 N. Main St.  
O'Fallon, MO 63366  
636-240-2000

### Electric

Curve River Electric Co.  
P.O. Box 160  
Troy, MO 63379-0160  
1-800-392-3709

Central Electric Power Cooperative  
2106 Jefferson Street  
Jefferson City, MO 65102  
573-761-2860

Ameren Missouri  
200 Calhoun Road  
Wentzville, MO 63385  
636-639-8312

### Gas

Spire Gas  
6400 Graham Road  
St. Louis, MO 63134  
314-522-2297

### Telephone

CenturyLink  
1151 Century Tel Dr.  
Wentzville, MO 63385  
636-332-7261

Charter Communications  
941 Charter Commons  
Town & Country, MO 63017  
888-438-2427

### Fire District

O'Fallon Fire Protection District  
111 Laura K Dr.  
O'Fallon, MO 63366  
636-272-3493

Wentzville Fire Protection District  
502 Luetkenhaus Blvd.  
Wentzville, MO 63385  
636-327-6239

Cottleville Fire Protection District  
1385 Motherhead Rd.  
St. Charles, MO 63304  
636-447-6655

New Melle Fire Protection District  
3705 Mill St.  
New Melle, MO 63365  
636-828-5528

PROJECT TITLE


HARVEST  
AT HOPEWELL

O'Fallon, Missouri

O'FALLON PHASE 2

THE  
**STERLING**  
CO.  
ENGINEERS & SURVEYORS

6055 New Baumgartner Road  
St. Louis, Missouri 63129  
Ph 314-487-0440 Fax 314-487-8944  
www.sterling-eng-survey.com  
Corporate Certificate of Authority #001348



Date: 02-11-2025  
Michael G. Boerding  
License No. MO E-28643  
Professional Engineer

HARVEST HOPEWELL, LLC  
5091 New Baumgartner Road  
St. Louis, Missouri 63129

COVER SHEET

P+Z No. 21-004994  
City No. 21-011444  
Date: 02-11-2025  
Job No. 20-09-327

Page No.

1.1

IMP