



NOTES:
 1. To prevent damage to the walls during site development, all surface drainage should be directed away from the walls. Excess water during heavy rain events, if not drained properly can cause washouts at wall ends and 'blowouts' of interior sections. These precautions should be taken during wall construction, and after, until the final site drainage, landscaping and paving are complete.
 2. The design of safety fencing at the top of the wall is not included in the design of this retaining wall. The responsibility for this design of safety fence is the project designers.

**NOT TO SCALE
 DRAWING IS FOR ORIENTATION USE ONLY**


Shively Geotechnical, Inc.
 8460 North Linbergh Avenue, Suite 10
 St. Louis, Missouri 63031
 314-770-1001; Fax: 314-770-1046

Wall 1
 Orientation View
Copyright 2005

Hyland Green Village
 O'Fallon, Missouri

| | | | |
|-------------------------------|------------------------|-----------------|-------------------|
| Project Number S21-3419 | Issue Date 09/20/05 | Drawn By JES | Checked By JES |
| Sheet Number 1 of 4 | | | |