

PRINCIPLES & STANDARDS:

1. All excavations, grading, or filling shall have a finished grade not to exceed a 3:1 slope (33 %). Steeper grades may be approved by the designated official if the excavation is through rock or the excavation or the fill is adequately protected (a designed head wall or toe wall may be required). Retaining walls that exceed a height of four (4) feet shall require the construction of safety guards as identified in the appropriate section(s) of the adopted BOCA Codes and must be approved by the Building Department. Permanent safety guards will be constructed in accordance with the appropriate section(s) of the adopted BOCA Codes.

2. Sediment and erosion control plans for sites that exceed 20,000 square feet of grading shall provide for sediment or debris basins, silt traps or filters, staked straw bales or other approved measures to remove sediment from run—off waters. The design to be approved by the Designated Official. Temporary siltation control measures (structural) shall be maintained until vegetative cover is established at a sufficient density to provide erosion control on the site.

3. Where natural vegetation is removed during grading, vegetation shall be reestablished in such a density as to prevent erosion. Permanent type grasses shall be established as soon as possible during the next seeding period after grading has been completed.

4. When grading operations are completed or suspended for more than 14 days permanent grass must be established at sufficient density to provide erosion control on the site. Between permanent grass seeding periods, temporary cover shall be provided according to the City Engineer's recommendations. All finished grades (areas not to be disturbed by future improvement) in excess of 20% slopes (5:1) shall be mulched and tacked at the rate of 100 pounds per 1,000 square feet when seeded.

5. Provisions shall be made to accommodate the increased runoff caused by changed soils and surface conditions during and after grading. Unvegetated open channels shall be designed so that gradients result in velocities of 2 fps (feet per second) or less. Open channels with velocities more than 2 fps and less that 5 fps shall be established in permanent vegetation by use of commercial erosion control blankets or lined with rock rip rap or concrete or other suitable materials as approved by the City Engineer. Detention basins, diversions, or other appropriate structures shall be constructed to prevent velocities above 5 fps.

6. The adjoining ground to development sites (lots) shall be provided with protection from accelerated and increased surface water, silt from erosion, and any other consequence of erosion. Run-off water from developed areas (parking lots, paved sites and buildings) above the area to be developed shall be directed to diversions, detention basins, concrete gutters and/or underground outlet systems. Sufficiently anchored straw bales may be temporarily substituted with the approval of the City Engineer.

7. Development along natural watercourses shall have residential lot lines, commercial or industrial improvements, parking areas or driveways set back a minimum of 25 feet from the top of the existing stream bank. The watercourse shall be maintained and made the responsibility of the subdivision trustees or in the case of a site plan by the property owner. Permanent vegetation should be left intact. Variances will include designed stream bank erosion control measures and shall be approved by the City Engineer. FEMA and U.S. Army Corps of Engineers guidelines shall be followed where applicable regarding site development areas designated as flood plains and wetlands.

8. All lots shall be seeded and mulched at the minimum rates defined in Appendix A or sodded before an occupancy permit shall be issued except that a temporary occupancy permit may be issued by the Building Department in cases of undue hardship because of unfavorable ground conditions.

> VEGETATIVE ESTABLISHMENT For Urban Development Sites

APPENDIX A

Seeding Rates:

Tall Fescue — 30 lbs./ac. Smooth Brome - 20 lbs./ac. Combined Fescue @ 15 lbs./ac. and Brome @ 10 lbs./ac.

Wheat or Rye - 150 lbs./ac. (3.5 lbs. per square foot) - 120 lbs./ac. (2.75 lbs. per square foot)

Fescue or Brome - March 1 to June 1 August 1 to October 1 Wheat or Rye - March 15 to November 1 March 15 to September 15

100 lbs. per 1,000 sq. feet (4,356 lbs. per acre)

Fertilizer Rates Nitrogen 30 lbs./ac Phosphate Potassium

30 lbs./ac. 600 lbs./ac. ENM* * ENM = effective neutralizing material as per State evaluation of quarried rock.

LANDSCAPE LEGEND

QTY. (20) ~

INDICATES PROPOSED EVERGREEN OR ORNAMENTAL SHRUB mugho pines, yews, junipers, hollies, boxwoods)



(spireas, forsythia, barberries, privets, lilacs) INDICATES PROPOSED DECIDUOUS SHADE TREE ashes, oaks, maples, birches, sweet gum)

(minimum 2 1/2" caliper) LANDSCAPING AS DEPICTED IS SUBJECT TO FINAL DESIGN BY A QUALIFIED LANDSCAPE DESIGNER

LANDSCAPING AS DEPICTED IS SUBJECT TO FINAL DESIGN BY A QUALIFIED LANDSCAPE DESIGNER

. ALL LANDSCAPED AREAS SHALL BE IRRIGATED. HOSE BIBS SHALL BE USED FOR IRRIGATION PURPOSES.

A SET OF CONSTRUCTION PLANS FOR IMO'S PIZZA AND RETAIL CENTER

THE RESUBDIVISION OF LOT 6 OF WINGHAVEN CENTRE A TRACT OF LAND BEING PART OF SECTION 1, TOWNSHIP 46 NORTH, RANGE 2 EAST OF THE FIFTH PRINCIPAL MERIDIAN. CITY OF O'FALLON, ST. CHARLES COUNTY, MISSOURI

GENERAL NOTES:

1. Underground utilities have been plotted from available information and therefore their locations shall be considered approximate only. The verification of the location of all underground utilities, either shown or not shown on these plans shall be the responsibility of the contractor, and shall be located prior to any grading or construction of the

2. All filled places under proposed storm and sanitary sewer, proposed roads, and/or paved areas shall be compacted to 90% of the maximum density as determined by the "Modified AASHTO T-180 Compaction Test. or 95% of maximum density as determined by the standard Proctor Test AASHTO T-99. All tests shall be verified by a soils engineer concurrent with grading and backfilling operations. All filled places in proposed roads shall be compacted from the bottom up. All test shall be verified by a soil engineer concurrent with grading and backfilling operations. Ensure the moisture content of the soil in the fill areas is to correspond to the compactive effort as defined by the Standard or Modified Proctor Test. Optimum moisture content shall be determined using the same test that was used for compaction. Soil compaction curves shall be submitted to The City of O'Fallon prior to the placement of fill. Proof rolling may be required to verify soil stability at the descretion of The City of O'Fallon.

- 3. No area shall be cleared without the permission of the Project Engineer.
- 4. The City of O'Fallon shall be notified 48 hours prior to construction for coordination and inspection.
- 5. All existing site improvements disturbed, damaged or destroyed shall be repaired or replaced to closely match pre-construction conditions.
- 6. All construction and materials shall conform to the current construction standards of the City of O'Fallon.
- 7. Any permits, licenses, easements, or approvals required to work on public or private properties or roadways are the responsibility of the developer.
- 8. No slopes shall exceed 3(Horizontal): 1(Verticle).

9. The Contractor shall assume complete responsibility for controlling all siltation and erosion of the project area. The Contractor shall use whatever means necessary to control erosion and siltation including, but not limited to, staked straw bales and/or siltation fabric fences (possible methods of control are detailed in the plan). Control shall commence with grading and be maintained throughout the project until acceptance of the work by the Owner and/or the City of O'Fallon and/or MODOT. The Contractor's responsibilities include all design and implementation as required to prevent erosion and the depositing of silt. The Owner and/or the City of O'Fallon and/or MODOT may at their option direct the Contractor in his methods as deemed fit to protect property and improvements. Any depositing of silts or mud on new or existing pavement or in new or existing storm sewers or swales shall be removed after each rain and affected areas cleaned to the satisfaction of the Owner and/or the City of O'Fallon and/or MODOT.

10. Erosion control systems shall not be limited to what is shown on the plan. Whatever means necessary shall be taken to prevent siltation and erosion from entering natural streams and adjacent roadways, properties and ditches.

- 11. All building mounted lights shall be pointed downward and fully screened to prevent light from spilling over onto adjacent properties.
- 12. All ground and roof hvac mechanical units to be screened from view.
- 13. The Developer must supply City Construction Inspectors with soil reports prior to or during
- 14. All paving to be in accordance with St. Charles County standards and specifications except as modified by the City of O'Fallon ordinances.

15. All sidewalks, curb ramps, ramps and accessible parking spaces shall be constructed in accordance with the current approved "Americans with Disabilities Act Accessibility Guidelines" (ADAAG) along with the required grades, construction materials, specifications and signage. If any conflict accurs between the above information and the plans, the ADAAG guidelines shall take precedence and the contractor prior to any construction shall notify the Project Engineer. Ensure at least one 8' wide handicap access aisle is provided and curb ramps do not project into handicap access aisles.

- 16. Brick shall not be used in the construction of storm or sanitary sewer structures.
- 17. The Contractor shall ensure all storm and sanitary sewer joint shall be gasketed 0-Ring
- 18. Lighting values will be reviewed on the site prior to the final occupancy inspection. Corrections will need to be made if not in compliance with City standards.
- 19. All proposed fencing requires a separate permit through the Planning Division.
- 20. All sign locations and sizes must be approved separately through the Planning Division.
- 21. All sign post and backs and bracket arms shall be painted black using Carboline Rustbond Penetrating Sealer SG and Carboline 133 HB paint (or equivalent as approved by the City of O'Fallon and MoDOT). Sign designating street names shall be on the opposite side of the street from traffic control signs.
- 22. All new utility line shall be located underground.
- 23. All erosion control systems shall be inspected and necessary corrections shall be made within 24 hours of any rainstorm resulting in one-half inch of rain or more.
- 24. All graded areas that are to remain bare for over 2 weeks shall be seeded and mulched per
- 25. Rip—rap shown at flared ends will be evaluated in the field after installation for effectiveness and field modificied if necessary to reduce erosion on and off-site.
- 26. Marking to be provided on storm sewer inlets. The City will allow the following markers and adhesive procedures only as shown in the table below. "Peel and Stick" adhesive pads will not be

Manufacturer	Size	Adhesive	Style	Message (Part #)	Website
ACP International	3 7/8"	Ероху	Crystal Cap	No Dumping Drains To Waterways (SD-W-CC)	www.acpinternational.com
DAS Manufacturing, Inc.	4"	Ероху	Standard	No Dumping Drains To Stream (#SDS)	www.dasmanufacturing.com

27. Developer must supply City Construction inspectors with soil reports prior to or during site soil testing. The soil report will be required to contain the following information on soil test curves (Proctor reports) for projects within the City:

- Maximum dry density 2. Optimum moisture content
- 3. Maximum and minimum allowable moisture content
- 4. Curve must be plotted to show density from a minimum of 90% Compaction and above as determined by the "Modified AASHTO T-180 Compaction Test" (A.S.T.M.-D-1157) or from a minimum of 95% as determined by the "Standard Proctor Test ASSHTO T-99, Method C" (A.S.T.M.-D-698). Proctor type must be designated on document.
- 5. Curve must have at least 5 density points with moisture content and sample locations listed on document.
- Specific gravity.
- Natural moisture content. 8. Liquid limit.
- 9. Plastic limit.
- Be advised that if this information is not provided to the City's Construction Inspector the City will not allow grading or construction activities to proceed on any project site.

GRADING NOTES:

disposed of off-site.

1. A Geotechnical Engineer shall be employed by the owner and be on site during grading operations. All soils tests shall be verified by the Geotechnical Engineer concurrent with the grading and back filling operations.

2. The grading contractor shall perform a complete grading and compaction operation as shown on the plans, stated in these notes, or reasonably implied there from, all in accordance with the plans and notes as interpreted by the

3. The Contractor shall notify the Soils Engineer at least two days in advance of the start of the grading operation.

4. All areas shall be allowed to drain. All low points shall be provided with temporary 5. A sediment control plan that includes monitored and maintained sediment control basins and/or straw bales should be implemented as soon as possible. No graded

and silting up existing downstream storm drainage system. 6. Any existing trash and debris currently on this property must be removed and

mulched. Care should be exercised to prevent soil from damaging adjacent property

area is to be allowed to remain bare over the winter without being seeded and

7. Soft soil in the bottom and banks of any existing or former pond sites or tributaries should be removed, spread out and permitted to dry sufficiently to be used as fill. None of this material should be placed in proposed right-of-way locations or on storm sewer locations.

8. Site preparation includes the clearance of all stumps, trees, bushes, shrubs, and weeds; the grubbing and removal of roots and other surface obstructions from the site; and the demolition and removal of any man-made structures. The unsuitable material shall be properly disposed of off-site. Topsoil and grass in the fill areas shall be thoroughly disced prior to the placement of any fill. The Soils Engineer shall approve the discing operation.

9. Compaction equipment shall consist of tamping rollers, pneumatic—tired rollers, vibratory roller, or high speed impact type drum rollers acceptable to the Soils Engineer. The roller shall be designed so as to avoid the creation of a layered fill without proper blending of successive fill layers.

10. The Soils Engineer shall observe and test the placement of the fill to verify that specifications are met. A series of fill density tests will be determined on each lift of fill. Interim reports showing fill quality will be made to the Owner at regular

11. The Soils Engineer shall notify the Contractor of rejection of a lift of fill or portion thereof. The Contractor shall rework the rejected portion of fill and obtain notification from the Soils Engineer of its acceptance prior to the placement of

12. All areas to receive fill shall be scarified to a depth of not less than 6 inches and then compacted in accordance with the specifications given below. Natural slopes steeper than 1 vertical to 5 horizontal to receive fill shall have horizontal benches, cut into the slopes before the placement of any fill. The width and height to be determined by the Soils Engineer. The fill shall be loosely placed in horizontal layers not exceeding 8 inches in thickness and compacted in accordance with the specifications given below. The Soils Engineer shall be responsible for determining the acceptability of soils placed. Any unacceptable soils placed shall be removed at the Contractor's expense.

13. The sequence of operation in the fill areas will be fill, compact, verify acceptable soil density, and repetition of the sequence. The acceptable moisture contents during the filling operation are those at which satisfactory dry densities can be obtained.

14. The surface of the fill shall be finished so that it will not impound water. If at the end of a days work it would appear that there may be rain prior to the next working day, the surface shall be finished smooth. If the surface has been finished smooth for any reason, it shall be scarified before proceeding with the placement of succeeding lifts. Fill shall not be placed on frozen ground, nor shall filling operations continue when the temperature is such as to permit the layer under placement to freeze.

15. All siltation control devices shall be inspected by the contractor after any rain of 1/2" or more with any appreciable accumulation of mud to be removed and siltation measures repaired where necessary.

- 16. No slope shall be steeper than 3(Horizontal):1(Vertical). All slopes shall be sodded
- 17. Any contaminated soil encountered during excavation shall be hauled and placed as directed by the owners environmental engineering representative.

USGS REFERENCE BENCHMARK

REFERENCE BENCHMARK ELEV 667.66 STANDARD DISK STAMPED "ORF 1931" SET IN A 12" SQUARE CONCRETE MONUMENT. LOCATE ABOUT 3 MILES SOUTHWEST OF THE TOWN OF O'FALLON; 2 MILES SOUTHEAST OF THE DAM FOR LAKE SAINT LOUIS AND 0.8 MILE NORTHEAST OF THE IMMACULIATE CONCEPTION CATHOLIC CHURCH. 107' NORTHWEST OF THE NORTHWEST CORNER OF A SHED ADDITION TO AN OLDER BARN; 25' SOUTHWEST OF A SMALL POND; 39' NORTHEAST OF A LONE PEAR TREE; AND 24.9' NORTHEAST OF A METAL WITNESS POST.

SITE BENCHMARK ELEV 618.76 OLD IRON PIPE ON EAST LINE OF SUBJECT PROPERTY

CALL BEFORE YOU DIG! -800-DIG-RITE GRADING QUANTITIES: 426 C.Y. CUT (INCLUDES SUBGRADE) 1,289 C.Y. FILL (INCLUDES 15% SHRINKAGE)

863 SHORT

THE ABOVE GRADING QUANTITY IS APPROXIMATE ONLY, NOT FOR BIDDING PURPOSES. CONTRACTOR SHALL VERIFY QUANTITIES PRIOR TO CONSTRUCTION.

TREE OR BUSH	\bigcirc
LIGHT POLE	\$
SANITARY SEWER & MANHOLE	
STORM SEWER & INLET	====
MAILBOX	⊡
ELECTRIC LINE	—— E ——
GAS LINE	—— G——
WATER LINE	W
TELEPHONE LINE	— T—
CABLE TV LINE	CATV
OVERHEAD WIRE	OHW
UTILITY POLE	O
UTILITY POLE W/ DOWN GUY	$\stackrel{\bullet}{\longrightarrow}$
FIRE HYDRANT	25
WATER VALVE	₩V ⊠
WATER METER	⊗ ^{WM}
GAS VALVE	Sv ⋈
ROAD SIGN	
TELEPHONE PEDESTAL	☐ TEL. PED.
FENCE	x

STANDARD SYMBOLS

DEVELOPMENT NOTES:

1. Area of tract:

Proposed Use:

Lot 6B = 247.603.66 sq.ft. = 5.6841 Acres

Lot 6A = 27,347.06 sq.ft. = 0.6278 Acres

2. Current Zoning:

Restaurant/Retail

3,900 sq.ft.

(City of O'Fallon)

4. Area of Building:

5. Required building & parking setbacks: Front yard.... 25 feet

Side yard.... 10 feet Rear yard.... 10 feet Parking.... 10 feet along lot perimeter

6. Parking Requirements & Provisions: 5.5 spaces per 1,000sq.ft. of floor area

1,300 sq.ft. / 1,000 x 5.5 = 7.15 spaces required (Imo's)=1 space per employee + 1 space per 250 sq.ft. usable space

1,400 sq.ft. 1,200 sq.ft. usable space 1,200/250 = 4.8 spaces required 8 employees max = 8 spaces required

1,200 sq.ft. / 100 = 12 spaces required

(Future Restaurant: 1 space per 100 sq.ft.

Spaces required: $7.15 + 4.8 + 8 + 12 = 31.95 \sim 32$ spaces provided space per 15 parking spaces or 4 spaces minimum per building 32 spaces / 15 = 2.13 \sim 3 spaces required

Bicycle spaces provided: 4 spaces minimum Landscape requirement:

Parking and/or loading area internal landscaping: Not less than 6% of interior parking lot shall be

landscaped plus 1 tree per 3,000sq.ft. of landscaped open space. 32 spaces x 270 = 8,640 sq.ft. of interior landscaping required

4,007.14 sq.ft. interior landscaping provided 8. This property is served by the following utilities: Electric - AmerenUE Electric Company 636-639-8312 Telephone - Century Telephone Co. 636-332-7318 Water - Public Water Supply District No. 2 636-561-3737 Sewer - Duckett Creek Sanitary Sewer District 636-441-1244 Gas - Laclede Gas Company 314-658-5417 Wentzville Fire Protection District 636-327-6239

Wentzville School District 636-327-3800

Per F.I.R.M. floor insurance rate map of St. Charles County (Unincorporated Areas), Missouri, Community panel number 290315 0240 E Dated August 2, 1996). This Property is within zone 'X'. Zone 'X' is defined as an area outside the 500 year flood plain limits.

Owner/Developer of property: Winghaven and Associates L.L.C. 2500 Old Hwy 94 S. Suite 200 St. Charles, MO 63303

11. All HVAC mechanical equipment will be rooftop units and screened by a parapet wall per City standards on all four sides of the building.

12. All signs shall require a separate permit by the City of O'Fallon.

13. Lot 6A site calculation: Building = 3,900 sq.ft. = 14%Pavement = 19,440 sq.ft. = 71% Landscape = 4,007 sq.ft. = 15%

14. Detention for this site provided by the original Winghaven Centre development

15. Covenants, Codes and Restriction for Lot 6A and 6B will be provided with the Record Plat. 16. No trees are proposed to be removed with this development, therefore no trees to be replaced as required

by the Tree Preservation Requirement. 17. All new utilities to be located underground. Any utilities under city streets shall be bored. No open cuts

18. Existing irrigation system for greenspace areas within Winghaven Centre which will be disturbed for the construction of this facility will be modified and repaired as required to maintain its intended purpose. All landscape areas shall be irrigated with an automatic irrigation system.

19. Existing electric lines and conduits to existing light standards may need to be relocated due to the proposed construction depending on the exact location of these lines.

20. All HVAC and mechanical units on site shall be properly screened as required by City Code. Rooftop units shall be screened by a parapet wall that extends around the entire perimeter of the building. The parapet shall have a minimum height that is at least as tall as the tallest unit mounted on the roof. Ground mounted HVAC and mechanical units shall be screened by fencing, vegetation, or some other means (approved by the Planning and Zoning Commissions) that has a minimum height that is at least as tall as the tallest unit being screened.

21. No light standards are to be removed or added with this development. Therefore no Photometric plan

has been submitted. 22. All new easements will be provided on record plat.

23. Depending on construction activities and building or parking lot location, light standards my need to be removed and replaced in the same location during construction.

24. Estimated Sanitary flow is 1,000 gallons per day.

COVER SHEET SHEET 2 DEMOLITION PLAN SITE PLAN SHEET 3 SHEET 4 GRADING PLAN DRAINAGE AREA MAP SHEET 5

SHEET INDEX:


PLANNING AND ZONING FILE #9831.37.07

SHEET 6 CONSTRUCTION DETAILS


OM ≥ 0 PROPERTI PERUQUE TZVILLE, N -332-652 0 < o ≥ o

DISCLAIMER OF RESPONSIBILITY I hereby specify that the documents intended to be authenticated by my seal are limited to this sheet, and I hereby disclaim any respon sibility for all other Drawings, Specifications, Estimates, Reports or other documents or instruments relating to or intended to be used for any part or parts of the architectural or engineering project or survey.

0



Bax Engineering Company, Inc. All Rights Reserved 08-10-05 Duckett Comments D8-16-05 PWSD#2 Comments 09-14-05 Per City Comments 10-06-05 Footprint/Walls



ENGINEERING SURVEYING

221 Point West Blvd. St. Charles, MO 63301 636-928-5552 FAX 928-1718

05-13233 PROJECT NUMBER

FILE NAME DRB/KLW

DESIGNED CHECKED