PLANTING LIST					
BOTANICAL NAME	COMMON NAME	SIZE	SPACING	QUANTITY	REMARKS
Acerrubrum	Sugar Maple	2" Cal	As Shown		B & B
Ginkgo Biloba	Ginkgo	2" Cal	As Shown		B & B
Liquidambar Styraciflua	Sweet Gum	2" Cal	As Shown		B & B
Quercus Macrocarpa	Bur Oak	2" Cal	As Shown		B & B
Castanea Mollisima	Chinese Chestnut	2" Cal	As Shown		B & B
Fraxinus Americana	European Ash	2" Cal	As Shown		B & B
Cerus	Red Bud	5'-0" + Ht.	As Shown		B & B
Crataegus	Hawthorn	5'-0" + Ht.	As Shown		B & B
Rhus Cotinus	Purple Fringe	5'-0" + Ht.	As Shown		B & B
Pyrus Callervanna	Bradford Pear	5'-0" + Ht.	As Shown		B & B
Cornus 'Cloud Nine'	White Dogwood	5'-0" + Ht.	As Shown		B & B
Pseudotsuga Menziesii	Douglas Fir	5'-6" Ht.	As Shown		B & B
Picea Ables	Norway Spruce	5'-6" Ht.	As Shown		B & B
S. Japonica Shirobana	Japanese Spired	12"-18" Ht.			Container
Euonymus Alatus Compactus'	Burning Bush	12'-18" Ht.			Container
Juniperus 'Bar Harbor'	Bar Harbor Juniper	1 Gal. Cont			Container
Juniperus Witconi	Blue Rug Juniper	12" Spread 1 Gal. Cont			Container
Forsythia Intermedia Lynwood Gold	Forsythia	24" Ht.			Container
Pieris Japonica	Japanese Andromeda	12"-18" Ht. 1 Gal. Cont			Container
Coroneastee-Apiculata	Cranberry Cotton Easter	24" Ht. 1 Gal. Cont			Container
Juniperus Virginiana	Canaerti Juniper	5' Ht.			B & B
Rhamnus Frangula Columnaris	Tall Hedge	18"-24" Ht.			Container

LEGEND

EXISTING		PROPOSED
●	PROPERTY LINE / PROPERTY CORNER	●
	CENTER LINE	
135	CONTOUR LINE	135
	CURB & GUTTER	
S/W	SIDEWALK	S/W
6"W	WATER LINE	6"W
G"G	GAS LINE	G"G
15"ST	STORM SEWER	15"ST
8"SS	SANITARY SEWER	8"SS
U.E./T.	UNDERGROUND ELECTRIC AND OR TELEPHONE	U.E./T.
O.E./T.	OVERHEAD ELECTRIC AND OR TELEPHONE	O.E./T.
	UTILITY POLE	
	FIRE HYDRANT	
	STREET LIGHT	
	GAS VALVE	
	WATER VALVE	
G	GAS METER	
W	WATER METER	
	MANHOLE	
	CURB INLET	
	STORM SEWER INLET	
	BUSHES	
	TREE	
	CHAIN LINK FENCE	
	FLOW	
70x15	BORING LOCATION / SPOT ELEVATION TO BE REMOVED	B1 / x70.15
	GRASS	

N 89^ 28' 37" E 592.67'

S 00^ 37' 41" W 208.43'

S 00^ 12' 34" W 257.75'

N 07^ 44' 56" W 453.74'

N 38^ 11' 54.28" W

R=293.84'
L=127.03'

S 89^ 29' 00" W 371.83'

328.50'

53'

CHURCH STREET

MATCH EXISTING CURB (TYP.)

USPS
POST OFFICE
FACILITY
26,530 S.F. +/-

RETAINING WALL

R50'

CALLERY MAPLE

CONDENSORS

RAMP

DUMPSTER

CANOPY

DOCK

TRANSFORMER PAD

GINKGO

CURB

EXTERIOR LIGHTS
25' METAL POLE
400W HP SODIUM
VAPOR LUMINAIRES (TYP.)

SWEET GUM

RED BUD

NORWAY SPRUCE

SCREEN WALL

FENCE

(14) BLUE RUG JUNIPER

GATE

SCREEN WALL

DOUGLAS FIR

FORSYTHIA

WHITE DOGWOOD

JAPANESE SPIREA

PIERIS JAPONICA

BURNING BUSH

BOLLARD (TYP.)

SIDEWALK

BRADFORD PEAR

SUGAR MAPLE

BUR OAK

CUSTOMER PARKING

CURB

DROP BOXES

SNORKEL LANE

CHINESE CHESTNUT

EUROPEAN ASH

HAWTHORN

PURPLE FRINGE

RED BUD

SWEET GUM

HAWTHORN

CRANBERRY COTTONEASTER

BOAR HARBOR JUNIPER

4' GATE

(12) BLUE RUG JUNIPER

SCREEN WALL

(6) BLUE RUG JUNIPER

CURB

RED BUD

NORWAY SPRUCE

CANAERTI JUNIPER

BRADFORD PEAR

SCREEN WALL

GINKGO

SUGAR MAPLE

HAWTHORN

BLUE OAK

RURAL CARRIER PARKING

CANOPY (TYP.)

"TALL HEDGE" RHAMNUS FRANGULA COLUMNARIS) 30" O.C.

CARRIER PARKING

CARRIER PARKING

EMPLOYEE PARKING

R60'

R20'

NOTES

1) BUILDINGS TO SET PARALLEL AND PERPENDICULAR TO S 89^ 29' 00" W
2) PARKING:
   PROPOSED — 48 CUSTOMER
   — 2 HANDICAP CUSTOMER
   — 21 EMPLOYEE
   — 3 HANDICAP EMPLOYEE
   — 4 OFFICIAL CARS
   — 44 POSTAL VEHICLES
   124 TOTAL

SITE PLAN

SCALE: 1"=20'-0"

NORTH

11/21 SUBMITTAL

MARTELL & ASSOCIATES, P.A.
Engineers — Architects — Planners
1333 Meadowlark Lane, Suite 100
Kansas City, Kansas 66102
913-287-1771

THE HOLLIS + MILLER GROUP
Architects & Engineers
309 S.W. Market Street
Lee's Summit, Missouri 64063
816-525-5600

United States Postal Service
Facilities Department
Kit of Parts

Facilities Service Center
6800 West 64th Street
Overland Park, KS 66202-4171

O'FALLON, MISSOURI 63366

UNITED STATES POST OFFICE

Revisions:

Date: 11/28/89

Number: 8959

USPS File Number: