

Presell Board

Everbrite
Illumination: 03 F00T12 CW/HO
Electrical: 1,822 amps @ 120V 50 Hz
Ballast: Fulham Workhorse 7
Ship Weight:
Other:

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Everbrite

REVISIONS:
A INITIAL RELEASE 07 JUN07
B CHANGED ANCHOR BOLTS FROM 40 TO 47 07 JUN07
C UPDATED S&T TO L&P, ADDED TO L&P 08 JUL08
D CHANGED S&T TO SHOW WIND ROSTER 08 JUL08
E WIND ROSTER 14 SEP08
F WIND ROSTER 24 SEP08
G WIND ROSTER 24 SEP08
H WIND ROSTER 24 SEP08
I WIND ROSTER 24 SEP08

INSTALLATION INSTRUCTIONS:
1. PREPARE THE AREA AND CONFORM WITH LOCAL REQUIREMENTS FOR PERMITS AND INSURANCE.
2. EXCAVATE AND INSURE FOUNDATION.
3. POUR CONCRETE AND BRACE TO PREVENT MOVEMENT.
4. ALLOW CONCRETE TO CURE FOR 7 DAYS.
5. EXCAVATE FOUNDATION AND POSITION (4) ANCHOR BOLTS AND BRACE TO PREVENT MOVEMENT THEN POUR CONCRETE. ALLOW CONCRETE TO CURE FOR 7 DAYS.
6. LIFT VERTICAL COLUMN ASSEMBLY INTO PLACE ON ANCHOR BOLTS AND ADJUST FOR LEVEL AND PLUMB. TIGHTEN NUTS. REMOVE LIFTING ANGLE.
7. PULL WIRES FOR ORDER CONFORMATION UNIT (INSTALLED BY OTHERS) AND PULL WIRE FOR CANOPY LIGHT FIXTURE UP THRU COLUMN.
8. INSTALL "ORDER HERE" BAR. SLIDE TUBE OVER ANGLE AND BOLT TOGETHER (SEE DETAIL).
9. LIFT CANOPY ASSEMBLY INTO PLACE AND SECURE WITH SUPPLIED BOLTS. WIRE CANOPY LIGHT FIXTURE WHILE LOWERING CANOPY. REMOVE LIFTING ANGLES.
10. USE NON-SHRINK GROUT TO FILL IN GAP AT LEVELING NUTS.
11. CLEAN SIGN AND DISCARD INSTALLATION DEBRIS ACCORDINGLY. TOUCH UP SCRATCHES WITH SUPPLIED PAINT.

LANDSCAPE NOTE:
ANCHOR BOLTS TO BE INSTALLED IN ACCORDANCE WITH LOCAL REQUIREMENTS FOR PERMITS AND INSURANCE. LOCAL REQUIREMENTS MAY EXCEED THIS DESIGN. THE CONTRACTOR IS RESPONSIBLE TO VERIFY THIS PLAN.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Flag Poles

Everbrite

Available Heights: 20' (7.62 m), 30' (9.14 m), 40' (12.19 m), 50' (15.24 m)
Construction: Spun aluminum
Includes: Hardware, rope and cord
Max. allowable sq. ft. of flag (Flag not included):
20' - 40 sq. ft. (4' x 8' Flag)
30' - 60 sq. ft. (6' x 8' Flag)
40' - 80 sq. ft. (8' x 8' Flag)
50' - 100 sq. ft. (10' x 10' Flag)
Other:
• 20', 30' and 40' flag poles available with single pole.
• 50' flag pole available with single pole.
• Anchor bolt mount.
• Storm or Road fixed light available.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Anchor Bolt Pattern

EVERBRITE
25' & 30' FLAG POLE FOUNDATIONS

ANCHOR BOLT PATTERN (SCALE 2")

EVERBRITE, INC. 315 MARIAN AVE. SOUTH MILWAUKEE, WI 53172 P: 888-867-4078 F: 877-430-7363 WWW.EVERBRITE.COM

FP-43 Modular Outdoor Menu Board

Everbrite

Illumination: 4 F00T12 CW/HO
Electrical: 4.6 Amps @ 1.6 Amps (600watts) 120V 50 Hz
Ballast: Advance #ND-1563 TP Power Lighting #PV304L-13 Fluor Lighting #PV12.4-12 18T lbs.
Ship Weight:
Other:
• Modular design for increased flexibility.
• Adjustable shelves for easy menu modification.
• Optional kit to accept Customer Order Display and/or speaker.
• Flipchart panel can rotate 180 degrees to display live signage.
• Plastic call Floortex Plaster for signs and galle.
• Topper only allowed with column static board. Cannot have flip chart and topper.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Everbrite

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Directional Sign w/o Arch

Everbrite

Illumination: 1- F00T12 CW/HO
Electrical: 50 amps 120V 60 Hz
Ballast: 1 Fulham Workhorse 50
Ship Weight: 30 lbs.
Other:
• Shows with available toppers
• 4' or 6' pole available.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

ENTER/EXIT SIGNS

Everbrite

ENTER/EXIT SIGNS
1. PREPARE THE AREA AND CONFORM WITH LOCAL REQUIREMENTS FOR PERMITS AND INSURANCE.
2. EXCAVATE AND INSURE FOUNDATION.
3. POUR CONCRETE AND BRACE TO PREVENT MOVEMENT.
4. ALLOW CONCRETE TO CURE FOR 7 DAYS.
5. EXCAVATE FOUNDATION AND POSITION (4) ANCHOR BOLTS AND BRACE TO PREVENT MOVEMENT THEN POUR CONCRETE. ALLOW CONCRETE TO CURE FOR 7 DAYS.
6. LIFT VERTICAL COLUMN ASSEMBLY INTO PLACE ON ANCHOR BOLTS AND ADJUST FOR LEVEL AND PLUMB. TIGHTEN NUTS. REMOVE LIFTING ANGLE.
7. PULL WIRES FOR ORDER CONFORMATION UNIT (INSTALLED BY OTHERS) AND PULL WIRE FOR CANOPY LIGHT FIXTURE UP THRU COLUMN.
8. INSTALL "ORDER HERE" BAR. SLIDE TUBE OVER ANGLE AND BOLT TOGETHER (SEE DETAIL).
9. LIFT CANOPY ASSEMBLY INTO PLACE AND SECURE WITH SUPPLIED BOLTS. WIRE CANOPY LIGHT FIXTURE WHILE LOWERING CANOPY. REMOVE LIFTING ANGLES.
10. USE NON-SHRINK GROUT TO FILL IN GAP AT LEVELING NUTS.
11. CLEAN SIGN AND DISCARD INSTALLATION DEBRIS ACCORDINGLY. TOUCH UP SCRATCHES WITH SUPPLIED PAINT.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Drive-Thru Canopy

Everbrite

Illumination: 4 F00T12 CW/HO
Electrical: 10 Amp 120 Volt
Ballast: Fulham Workhorse 7
Ship Weight: 1300 lbs.
Other:
• Available with LED or LCD COO.
• Spring loading allows easy 90° rotation.
• Illuminated signage provides a customer with environmental all-weather protection from inclement weather.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Everbrite

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Welcome Point Gateway

Everbrite

Illumination: N/A
Ship Weight: 26 lbs.
Other:
• Non-shrinkable concrete (grout with 1/2" mesh) to be used in all applications.
• Adjustable hanging bar.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Everbrite

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

CUSTOMER ORDER DISPLAY (C.O.D.) GENERAL NOTES

ITEMS SUPPLIED BY AUDIO VENDOR:
1. SPEAKER & MICROPHONE.
2. TROUBLE SHOOTING GUIDE.
TORX HEAD DRIVER REQUIRED FOR INTERNAL ACCESS SIGN (NOT SUPPLIED).
INSTALLER TO INSURE SIGN IS PROPERLY INSTALLED, CONNECTED AND GROUNDED PER ALL LOCAL CODES.
DESIGN SPECIFICATIONS:
1. 3,000 PSI CONCRETE, 0.5 CUBIC YARDS REQUIRED.
2. SIGN, POLE, AND CONCRETE BASE ARE DESIGNED TO WITHSTAND A WIND OF 30 PSF.
3. CONCRETE BASE DESIGNED USING SOIL BEARING PRESSURE OF 1,000 PSF VERTICAL. IF THESE SOIL CONDITIONS DO NOT EXIST, IT IS THE ERECTOR'S RESPONSIBILITY TO HAVE A NEW BASE DESIGNED FOR THE EXISTING SOIL CONDITIONS BY A LICENSED STRUCTURAL ENGINEER.

C.O.D. ITEMS SUPPLIED BY EVERBRITE:
1. C.O.D. WITH ANCHOR BOLT SHROUD.
2. FULL MATRIX ELECTRONIC DISPLAY UNIT IN OEM CONFIGURATION.
3. (1) RS422 DATA CABLE, 250' LONG.
4. (1) RS232-RS485 CONVERTER & 2" DATA CABLE WITH DB9 & RJ11 CONNECTORS.
5. DATA CABLE CONNECTION BOX LOCATED IN SIGN SHROUD FOR QUICK CONNECTION.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

INSTALLATION INSTRUCTIONS:

- UNCRATE AND INSPECT SIGN. NOTIFY IMAGEPOINT OF ANY DAMAGE.
- USE SITE PLAN TO ESTABLISH POSITION OF SIGN (IF AVAILABLE).
- EXCAVATE FOUNDATION AND POSITION (4) ANCHOR BOLTS AND BRACE TO PREVENT MOVEMENT THEN POUR CONCRETE. ALLOW CONCRETE TO CURE FOR 7 DAYS.
- LIFT VERTICAL COLUMN ASSEMBLY INTO PLACE ON ANCHOR BOLTS AND ADJUST FOR LEVEL AND PLUMB. TIGHTEN NUTS. REMOVE LIFTING ANGLE.
- PULL WIRES FOR ORDER CONFORMATION UNIT (INSTALLED BY OTHERS) AND PULL WIRE FOR CANOPY LIGHT FIXTURE UP THRU COLUMN.
- INSTALL "ORDER HERE" BAR. SLIDE TUBE OVER ANGLE AND BOLT TOGETHER (SEE DETAIL).
- LIFT CANOPY ASSEMBLY INTO PLACE AND SECURE WITH SUPPLIED BOLTS. WIRE CANOPY LIGHT FIXTURE WHILE LOWERING CANOPY. REMOVE LIFTING ANGLES.
- USE NON-SHRINK GROUT TO FILL IN GAP AT LEVELING NUTS
- CLEAN SIGN AND DISCARD INSTALLATION DEBRIS ACCORDINGLY. TOUCH UP SCRATCHES WITH SUPPLIED PAINT

SPEAKER INSTALLATION INSTRUCTIONS:

- OPEN BOTTOM ACM PANEL TO ACCESS LOWER SPEAKER SHELF.
- REMOVE ACM PANEL AT TOP SPEAKER LOCATION TO ACCESS SHELF.
- INSTALL SPEAKERS PER SPEAKER MANUFACTURES RECOMMENDATIONS.

NOTE:
1. THIS IS A SUGGESTED INSTALL PROCEDURE. LOCAL REQUIREMENTS MAY EXCEED THIS DESIGN. THE CONTRACTOR IS RESPONSIBLE TO VERIFY THIS PLAN.
2. LEAVE SIDES OF EXCAVATION ROUGH TO KEY FOUNDATION TO EXCAVATION. REMOVE ALL LOOSE DIRT AND DEBRIS.
3. THE SOIL BEARING CAPACITY AT THE ERECTION SITE MUST BE CONSIDERED WHEN DESIGNING THE FOUNDATION. THE SIGN MANUFACTURER IS NOT ABLE TO PRE-DETERMINE THE SPECIFIC NEEDS OF EACH LOCATION. CONSULT A LOCAL ENGINEER FOR DESIGN SPECIFICATIONS.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

BOLLARD SIGN

Everbrite

Illumination: N/A
Ship Weight: 26 lbs.
Other:
• PMS 109 yellow reflective message disk with black decal graphics.
• Two mounting systems available (direct mount or anchor bolt).
• Additional copy available upon request.

BOLLARD SIGN NOTES:
1. FOOTINGS SHALL BE SIMILAR TO STANDARD BOLLARD. SEE BOLLARD DETAIL. VERIFY ALL FOUNDATIONS AND FOOTINGS WITH McDONALD'S PROJECT SIDE ELEVATION.

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

Everbrite

Everbrite, LLC, 315 Marian Ave., South Milwaukee, WI, 53172 P: 888-867-4078 F: 877-430-7363 www.everbrite.com

STATE OF MISSOURI
ROBERT E. POLK
REGISTERED PROFESSIONAL ENGINEER
DATE 10-26-11

McDonald's CORPORATION SITE DETAILS

THIS DRAWING AND SPECIFICATIONS ARE THE PROPERTY OF McDONALD'S CORPORATION AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THEIR WRITTEN PERMISSION.

| NO. | REV. | DATE | DESCRIPTION | UNITS OF MEASURE |
|-----|------|------|-------------|------------------|
| 1 | | | | |
| 2 | | | | |
| 3 | | | | |
| 4 | | | | |

SCALE: NONE

McDonald's CORPORATION SITE DETAILS

MENU BOARDS & DRIVE THRU DETAILS

CHECKED BY: DATE CHECKED: DATE APPROVED: DATE ISSUED:

DRAWN BY: M.P. DATE DRAWN: 13AUG09 DRAWING D: 1-1

D:\WORK\BUILDINGS\SD SHEETS PLOT: 1-1

SHEET NO. SD3