


METAL FENCE WITH BLOCK WALL

11x17 SCALE: N.T.S.
24x36 SCALE: N.T.S.


1
S-3



SITE COMPOUND SUBGRADE

11x17 SCALE: N.T.S.
24x36 SCALE: N.T.S.

2
S-3




GENERAL NOTES:

1. STEEL POSTS WHICH SUPPORT THE SILT FENCE SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF ONE FOOT.
2. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CAN NOT BE TRENCHED IN (E.G. PAVEMENT) WEIGHT FABRIC FLAP WITH WASHED GRAVEL ON UPHILL SIDE TO PREVENT FLOW UNDER FENCE.
3. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.
4. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST.
5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
6. SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.
7. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 6 INCHES. THE SILT SHALL BE DISPOSED OF IN AN APPROVED SITE AND IN SUCH A MANNER AS TO NOT CONTRIBUTE TO ADDITIONAL SILTATION.

SILT FENCE

11x17 SCALE: N.T.S.
24x36 SCALE: N.T.S.


3
S-3



SIGN DETAIL

11x17 SCALE: N.T.S.
24x36 SCALE: N.T.S.

4
S-3



ACCESS ROAD PROFILE

11x17 SCALE: N.T.S.
24x36 SCALE: N.T.S.

5
S-3



DATE SIGNED: 09-14-00

OMNIPOINT COMMUNICATIONS INC.
2004 WESTPORT CENTER DRIVE
ST. LOUIS, MO 63146
OFFICE: (314) 812-3600
FAX: (314) 812-3692

MIDWEST WIRELESS
690 CANTON STREET
WESTWOOD, MA 02090
OFFICE: (718) 461-6840
FAX: (718) 461-6841

SDS STRATA DESIGN SERVICES
10190 Old Katy Road, Suite 340
Houston, Texas, U.S.A.
Phone: 713 . 463 . 6099
Fax: 713 . 463 . 8731
Email: drawings@stratagroup.net
SDS Job No: D290

APPROVALS

OMNIPOINT _____

LANDLORD _____

LEASING _____

R.F. _____

ZONING _____

CONSTRUCTION _____

A & E _____

PROJECT NO: MO-05-212 D

DRAWN BY: KH

CHECKED BY: R. PACHECO

SUBMITTALS

DATE	DESCRIPTION	REV
05-02-00	ZONING REVIEW	A
05-05-00	GENERAL REVISION	B
06-28-00	FINAL ZONING	C
06-30-00	CONSTRUCTION REVIEW	0
08-18-00	ISSUE FOR CONSTRUCTION	1

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO OMNIPOINT COMMUNICATIONS INC. IS STRICTLY PROHIBITED.

SITE NAME
MO-05-212 D
NORTH ST. PETERS

SHEET TITLE
FENCE & SUBGRADE DETAILS

SHEET NUMBER
S-3
SHEET 15 of 16 SHEETS