

Austin  
Corvallis  
Denver  
New York  
St. Louis: 319 North 4th Street  
Suite 1000  
St. Louis, MO 63102  
Phone 314-241-5700  
Fax 314-241-5700

Project Team:  
General Contractor: PARC  
4208 Rider Trail North  
Earth City, MO 63045  
Phone 314-241-5700  
Fax 314-241-5700  
Civil Engineer: Pickett Ray & Silver, Inc.  
233 Mid Rivers Mall Drive  
St. Peters, MO 63376  
Phone 314-241-5700  
Fax 314-241-5700  
Structural Engineer: ABS Consulting  
1844 Lockland Hill Pike  
St. Louis, MO 63146  
Phone 314-241-5700  
Fax 314-241-5700  
Mechanical Designer: Jarrall Mechanical  
3630 South Broadway  
St. Louis, MO 63118  
Phone 314-241-5700  
Fax 314-241-5700  
Plumbing Designer: Kyrn Plumbing  
13160 Taussig Avenue  
Briggsdale, MO 63044  
Phone 314-241-5700  
Fax 314-241-5700  
Electrical Designer/Contractor: Crown Electrical  
3630 South Broadway  
St. Louis, MO 63118  
Phone 314-241-5700  
Fax 314-241-5700



Project Title:

O'Fallon, Missouri 63366

**Park Place**  
Independent and Assisted Living Apartments  
Phoenix Parkway (Village M)

PROJECT: BUILDING PERMIT SET  
Sheet Title: DCSC DETAILS 1

No. Revision Description Date

1 CITY OF O'FALLON, DCSD 1-07-00

BUILDING PERMIT SET

Sheet Title: DCSC DETAILS 1

Project Number: 04188  
Drawn By: G.V.C.  
Issue Date: NOV. 15, 2004  
Sheet Number: C11

ROUND PIPE				HORIZONTAL ELLIPTICAL PIPE			
INSIDE DIAMETER OF PIPE (INCHES)	"W" PAYLINE WIDTH OF TRENCH (INCHES)	"W" PAYLINE WIDTH OF TRENCH (FEET)	PAY-VOLUMES CU. FT. PER FT. CONCRETE ENGAGEMENT	INSIDE DIAMETER OF PIPE (INCHES)	"W" PAYLINE WIDTH OF TRENCH (INCHES)	"W" PAYLINE WIDTH OF TRENCH (FEET)	PAY-VOLUMES CU. FT. PER FT. CONCRETE ENGAGEMENT
4	30	2.50	3.28				
6	30	2.50	3.59				
8	30	2.50	3.87				
10	30	2.50	4.09				
12	30	2.50	4.25				
15	36	3.00	5.55				
18	36	3.00	5.77	14 x 23	41	3.42	5.94
21	39	3.25	6.61				
24	42	3.50	7.39	19 x 30	49	4.08	7.68
27	45	3.75	8.18	22 x 34	53	4.42	8.61
30	49	4.08	9.30	24 x 38	58	4.83	9.70
33	53	4.42	10.53	27 x 42	62	5.17	10.71
36	56	4.67	11.43	29 x 45	66	5.50	11.72
39	DISCONTINUED			32 x 49	71	5.92	13.14
42	63	5.25	13.38	34 x 53	75	6.25	14.05
48	70	5.83	15.67	38 x 60	83	6.92	16.18
54	77	6.42	18.15	43 x 68	92	7.67	18.81
60	84	7.00	20.73	48 x 76	101	8.42	21.59
66	91	7.58	23.45	53 x 83	109	9.08	24.35
72	98	8.17	26.37	58 x 91	118	9.83	27.45
78	105	8.75	29.39	63 x 98	126	10.50	30.50
84	112	9.33	32.57	68 x 106	135	11.25	33.91
90	119	9.92	35.90	72 x 113	143	11.92	36.99
96	126	10.50	39.37	77 x 121	152	12.67	40.69
102	133	11.08	42.99	82 x 128	160	13.33	44.45
108	140	11.67	46.75	87 x 136	168	14.00	47.79
114	147	12.25	50.66	92 x 143	176	14.67	51.70
120	154	12.83	54.72	97 x 151	185	15.42	56.01
126	161	13.42	58.92				
132	168	14.00	63.27	106 x 166	202	16.83	64.48
144	182	15.17	72.40	116 x 180	218	18.17	73.59

**Duckett Creek Sanitary District**  
PAYLINE WIDTHS OF TRENCH AND PAY-QUANTITIES OF CONCRETE  
Des. By: BSM App. By: KLA Detail No. 1  
Chk. By: MDOB Date: 12-21-99

