100 lbs. per 1000 sq. ft. (4,356 lbs. per ac.)

March 15 to September 15

RTILIZER RATES: Nitrogen Phosphate 30 lbs./ac.

Potassium 30 lbs./ac.


* ENM = effective neutralizing material as per State evaluation of guarried rock

PRINCIPALS & STANDARDS

- 1. All excavations, grading, or filling shall have a finished grade not to exceed a 3:1 slope (33%). Steeper grades may be approved by the designated official if the excavation is through rock or the excavation or the fill is adequately protected (a designed head wall or toe wall may be required). Retaining walls that exceed a height of four (4) feet shall require the construction of safety guards as identified in the appropriate section(s) of the adopted BOCA Codes and must be approved by the City Building Department. Permanent safety guards will be constructed in accordance with the appropriate section(s) of the adopted BOCA Codes.
- 2. Sediment and erosion control plans for sites that exceed 20,000 square feet of grading shall provide for sediment or debris basins, silt traps or filters, staked straw bales or other approved measures to remove sediment from run-off Temporary siltation control measures shall be maintained until vegetative cover is established at a sufficient density to provide erosion control on the site.
- 3. Where natural vegetation is removed during grading, vegetation shall be re-established in such a density as to prevent erosion. Permanent type grasses shall be established as soon as possible during the next seeding period after grading has been completed.
- 4. When grading operations are completed or suspended for more than 30 days permanent grass must be established at sufficient density to provide erosion control on the site. Between permanent grass seeding periods, temporary cover shall be

All finished grades (areas not to be disturbed by future improvement) in excess of 20% slopes (5:1) shall be mulched and tacked at the rate of 100 pounds per 1,000 square feet when seeded.

- 5. Provisions shall be made to accommodate the increased runoff caused by changed soils and surface conditions during and after grading. Unvegetated open channels shall be designed so that gradients result in velocities of 2 fps (feet per second) or less. Open channels with velocities more than 2 fps and less that 5 fps shall be established in permanent vegetation by use of commercial erosion control blankets or lined with rock riprap or concrete or other suitable materials. Detention basins, diversions or any other appropriate structures shall be constructed to prevent velocities above 5 fps.
- 6. The adjoining ground to development sites (lots) shall be provided with protection from accelerated and increased surface water, silt from erosion, and any other consequence of erosion. Run-off water from developed areas (parking lots, paved sites and buildings) above the area to be developed shall be directed to diversions, detention basins, concrete gutters and/or underground outlet systems. Sufficiently anchored straw bales may be temporarily substituted.
- 7. Development along natural watercourses shall have residential lot lines, commercial or industrial improvements, parking areas or driveways set back a minimum of 25 feet from the top of the existing stream bank. The watercourse shall be maintained and made the responsibility of the subdivision trustees or in the case of a site plan by the property owner. Permanent vegetation should be left intact. Variances will include designed streambank erosion control measures. FEMA and U.S. Army Corps of Engineers guidelines shall be followed where applicable regarding site development areas designated as flood plains and wetlands.
- 8. All lots shall be seeded and mulched or sodded before an occupancy permit shall be issued except that a temporary occupancy permit may be issued by the Building Department in cases of undue hardship because of unfavorable ground conditions.



A SET OF CONSTRUCTION PLANS FOR

PHEASANT POINT ELEMENTARY SCHOOL ADDITION

A TRACT OF LAND IN FRACTIONAL SECTION 16, U.S. SURVEY 1696 TOWNSHIP 46 NORTH, RANGE 3 EAST OF THE FIFTH PRINCIPAL MERIDIAN, ST. CHARLES COUNTY, MISSOURI

GRADING NOTES

- 1. A Geotechnical Engineer shall be employed by the owner and be on site during grading operations. All soils tests shall be verified by the Geotechnical Engineer concurrent with the grading and backfilling operations.
- 2. The grading contractor shall perform a complete grading and compaction operation as shown on the plans, stated in these notes, or reasonably implied there from, all in accordance with the plans and notes as interpreted by the Geotechnical Engineer.
- 3. The Contractor shall notify the Soils Engineer at least two days in advance of the start of the grading operation.
- 4. All areas shall be allowed to drain. All low points shall be provided with temporary ditches.
- 5. A sediment control plan that includes monitored and maintained sediment control basins and/or straw bales should be implemented as soon as possible. No graded area is to be allowed to remain bare without being seeded and mulched. Care should be exercised to prevent soil from damaging adjacent property and silting up existing downstream storm drainage system.
- 6. Debris and foundation material from any existing on-site building or structure which is scheduled to be razed for this development must be disposed of off-site.
- 7. All trash and debris on site, either existing or from construction, must be removed and properly disposed of off-site.
- 8. Soft soil in the bottom and banks of any existing or former pond sites or tributaries or on any sediment basins or traps should be removed, spread out and permitted to dry sufficiently to be used as fill. None of this material should be placed in proposed public right-of-way locations or on any storm sewer locations.
- 9. Site preparation includes the clearance of all stumps, trees, bushes, shrubs, and weeds; the grubbing and removal of roots and other surface obstructions from the site; and the demolition and removal of any man-made structures. The material shall be properly disposed of off-site. Topsoil and grass in the fill areas shall be thoroughly disced prior to the placement of any fill. The Soils Engineer shall approve the discing operation.
- 10. Compaction equipment shall consist of tamping rollers, pneumatic-tired rollers, vibratory roller, or high speed impact type drum rollers acceptable to the Soils Engineer. The roller shall be designed so as to avoid the creation of a layered fill without proper blending of successive fill
- 11. The Soils Engineer shall observe and test the placement of the fill to verify that specifications are met. A series of fill density tests will be determined on each lift of fill. Interim reports showing fill quality will be made to the Owner at regular intervals.
- 12. The Soils Engineer shall notify the Contractor of rejection of a lift of fill or portion thereof. The Contractor shall rework the rejected portion of fill and obtain notification from the Soils Engineer of its acceptance prior to the placement of additional fill.
- 13. All areas to receive fill shall be scarified to a depth of not less than 6 inches and then compacted in accordance with the specifications given below. Natural slopes steeper than 1 vertical to 5 horizontal to receive fill shall have horizontal benches, cut into the slopes before the placement of any fill. The width and height to be determined by the Soils Engineer. The fill shall be loosely placed in horizontal layers not exceeding 8 inches in thickness and compacted in accordance with the specifications given below. The Soils Engineer shall be responsible for determining the acceptability of soils placed. Any unacceptable soils placed shall be removed at the Contractor's expense.
- 14. The sequence of operation in the fill areas will be fill, compact, verify acceptable soil density, and repetition of the sequence. The acceptable moisture contents during the filling operation are those at which satisfactory dry densities can be obtained. The acceptable moisture contents during the filling operation in the remaining areas are from 2 to 8 percent above the optimum moisture control.
- 15. The surface of the fill shall be finished so that it will not impound water. If at the end of a days work it would appear that there may be rain prior to the next working day, the surface shall be finished smooth. If the surface has been finished smooth for any reason, it shall be scarified before proceeding with the placement of succeeding lifts. Fill shall not be placed on frozen ground, nor shall filling operations continue when the temperature is such as to permit the layer under placement to freeze.
- 16. Fill and backfill should be compacted to the criteria specified in the following table:

cined in the following table.	
CATEGORY	MINIMUM PERCENT COMPACT
in building areas below footings under slabs, walks, and pavement other than building areas tural subgrade	90% 90% 88% 88%
vement subgrade vement base course	90%

by modified Proctor Test (ASTM-D-1557). Moisture content must be within 2 percent below or 4 percent above optimum moisture content if fill is deeper than 10 feet.

Measured as a percent of the maximum dry density as determined

- 17. Detention shall be in place prior to completion of site improvements. (see plans for Pheasant Point Center)
- 18. Application for L.O.M.R. will be made to F.E.M.A. upon completion of grading. Corp of Engineers wetlands determination is not necessary at this time.

-) UNDERGROUND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE INFORMATION AND THEREFORE THEIR LOCATIONS SHALL BE CONSIDERED APPROXIMATE ONLY. THE VERIFICATION OF THE LOCATION OF ALL UNDERGROUND UTILITIES, EITHER SHOWN OR NOT SHOWN ON THESE PLANS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE LOCATED PRIOR TO ANY GRADING OR CONSTRUCTION OF THE IMPROVEMENTS.
- 2) ALL FILLED PLACES, INCLUDING TRENCH BACKFILLS, UNDER BUILDINGS, PROPOSED STORM AND SANITARY SEWER LINES AND/OR PAVED AREAS, SHALL BE COMPACTED TO 90% MAXIMUM DENSITY AS DETERMINED BY THE "MODIFIED AASHTO T-180 COMPACTION TEST," (A.S.T.M.-D-1557). ALL FILLED PLACES WITHIN PUBLIC ROADWAYS SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY AS DETERMINED BY THE "STANDARD PROCTOR TEST AASHTO T-99, METHOD C" (A.S.T.M.
- 3) ALL TRENCH BACKFILLS UNDER PAVED AREAS SHALL BE GRANULAR BACKFILL, AND SHALL BE COMPACTED TO 90% OF THE MAXIMUM DENSITY AS DETERMINED BY THE "MODIFIED AASHTO T-180 COMPACTION TEST," (A.S.T.M.-D-1557). ALL OTHER TRENCH BACKFILLS MAY BE EARTH MATERIAL (FREE OF LARGE CLODS OR STONES). ALL TRENCH BACKFILLS SHALL BE WATER JETTED.
- 4) NO AREA SHALL BE CLEARED WITHOUT THE PERMISSION OF THE PROJECT ENGINEER.
- 5) ALL GRADES SHALL BE WITHIN 0.2 FEET OF THOSE SHOWN ON THE GRADING PLAN.
- 6) NO SLOPE SHALL BE STEEPER THAN 3:1. ALL SLOPES SHALL BE SODDED OR SEEDED AND MULCHED.
- 7) ALL CONSTRUCTION AND MATERIALS USED SHALL CONFORM TO CURRENT CITY OF O'FALLON STANDARDS.
- 8) ALL MECHANICAL EQUIPMENT TO BE SCREENED FROM PUBLIC VIEW.
- 9) PROPOSED BUILDING WILL COMPLY WITH CURRENT AMERICAN DISABILITY ACT
- 10) SEE ARCHITECTURAL DRAWING FOR ALL BUILDING DIMENSIONS, SERVICE CONNECTIONS, DETAILS, ETC.
- 11) ALL UTILITIES SHOWN ARE EXISTING UNLESS OTHERWISE NOTED. ALL NEW UTILITIES SHALL BE LOCATED UNDERGROUND.
- 12) ALL DIMENSIONS ARE TO BACK OF CURB UNLESS OTHERWISE NOTED.
- 13) MINIMUM TREE REQUIREMENTS PER ZONING ORDINANCE:

TOTAL REQUIRED: 23 TREES


- 14) TOTAL TREES PROPOSED: 31 TREES (SEE TREE INVENTORY & LANDCAPE LEGEND)
- 15) THE DEVELOPER SHALL COMPLY WITH CURRENT TREE PRESERVATION ORDINANCE NUMBER 1689 AND PROVIDE LANDSCAPING AS SET FORTH IN ARTICLE 23 OF THE CITY OF O'FALLON ZONING ORDINANCES. (SEE TREE INVENTORY & LANDSCAPE LEGEND)
- 16) THE DEVELOPER SHALL COMPLY WITH CURRENT ARTICLE 13 PERFORMANCE STANDARDS.
- 17) DETENTION SHALL BE PROVIDED OFFSITE.
- 18) ALL FENCING REQUIRES A SEPARATE PERMIT FROM PLANNING & ZONING.

DEVELOPMENT NOTES

1.	Area of Tract:	13.028 Acres
2.	Existing Zoning:	R-1 (CITY OF O'FALLO
3.	Proposed Zoning:	R-1 (CITY OF O'FALLO
4.	Proposed Use:	ELEMENTARY SCHOOL
5.	Area of Building:	19,756 Sq. Ft.
6.	The required height and building se	tbacks are as follows:
	Minimum Front Yard:	25 feet

- 25 feet Minimum Rear Yard: Maximum Height of Building: 35 feet 7. Owner under contract: Ft. Zumwalt School District
- 110 Virgil O'Fallon, MO 63366 (314) 272-6620 8. Site is served by:
 - Duckett Creek Sanitary District Union Electric Company St. Charles Gas Company St. Charles County Public Water Supply District #2 GTE Telephone Company Fort Zumwalt School District O'Fallon Fire Protection District
- 9. Flood Plain exists on this tract per F.I.R.M. #29183 0430 E, dated Aug. 2, 1996.
- 10. Topographic information is per Topographic Survey By BAX Engineering.
- 11. Parking Required:
- Elementary school Two parking spaces per each classroom 33 existing classrooms x 2 parking spaces + 17 new classrooms x 2 parking spaces = 100 parking spaces required parking provided = 172 spaces with 6 handicap spaces
- 12. Parking Landscaping Required: 172 spaces \times 270 \times 6% = 2,787 sq.ft.
- 13. SITE COVERAGE CALCULATIONS: BUILDING = 85,456.73 SQ. FT. ~ 1.962 AC. PAVEMENT = 132,381.76 SQ. FT. ~ 3.039 AC. GREEN SPACE = 349,661.51 SQ. FT. ~ 8.027 AC.

landscaping provided = 18,527 sq.ft.



CONCRETE CURB DETAIL

3" TYPE "C" ASPHALTIC CONCRETE - WEARING SURFACE

DIRECTION OF FLOW

1. STRAW BALES, NOT HAY BALES

2. BUTT ENDS OF BALES TIGHTLY TOGETHER.

WEDGING LOOSE STRAW BETWEEN THEM.

3. INSTALL BALES WITH BINDING AROUND


SIDES, NOT TOP AND BOTTOM.

4. FILL ANY GAP BETWEEN BALES BY

SHALL BE USED

ASPHALT PAVEMENT DETAIL

8" ROLLED STONE BASE -



COMPACTED -


BACKFILL

DRAINAGE WAY

PLACEMENT AND CONSTRUCTION OF A STRAW BALE BARRIEF

STRAW BALES BARRIERS

FOR URBAN DEVELOPMENT SITES




ELEVATION


HIGHER THAN POINT "B'

POINTS "A" SHOULD BE

1. FILTER BARRIERS SHALL BE INSPECTED IMMEDIATLY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY 2. SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL BE NECESSARY, THE FABRIC SHALL BE REPLACED PROMILY.

3. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY HALF THE HEIGHT OF THE BARRIER. 4. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THIE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, PREPARED AND SEEDED.






TRENCH AND

COMPACT THE

EXCAVATED SOIL






-NEW STRAW BALE

- BALE BINDING





ENGINEERING

12-23-98 DATE 96-7218D St. Peters, MO. 63376 PROJECT NUMBER 1 OF 3

SHEET

Proj. No. Date: Plot: U-

AS NOTED

BUILDING CONST. INSP

CARIS LINNEMAN

ADDITION INT ELEME SCHOOL

ISSUED FOR: 80% OWNERS REVIEW JANUARY 11, 1999

REVISIONS: