


FINAL SURVEY DRAWING  
 SURVEY PLOTTED  
 NOTE BOOK NO. 1000  
 AREA CHECKED


DATE  
 BY  
 ORIGINAL SURVEY DRAWING  
 SURVEY PLOTTED  
 NOTE BOOK NO. 1000  
 AREA CHECKED



SCALE  
 HORIZ 1" = 50'  
 VERT 1" = 10'

**H.D.P.E. PIPE DETAIL**

- The use of High Density Polyethylene Compacted pipe A.D.S. N12 or Equal will be permitted as an acceptable alternative to reinforced concrete pipe. Pipe shall meet A.S.T.M. D-2321 and A.A.S.H.O. M-294-92. Concrete floors and sections and inlet structures shall be required. Pipe must have smooth interior wall and is not to be used inside the Public Right-of-Way.
- All concrete pipe or HDPE pipe shall be installed with o-ring rubber type gaskets per M.S.D. Standard Construction Specifications or Manufacturer.
- In typical conditions the minimum trench width is determined by the size of the pipe and the ability to get compaction equipment between the pipe and the trench walls. The minimum trench width should not be less than the outside diameter plus 16 inches or the pipe outside diameter times 1.25 plus 12 inches; whichever is greater. High speed trenchers may enable satisfactory installation of pipe in narrower trenches. Poor in-situ soil conditions such as peat, muck, running sands, or expansive clays will require substantially wider backfill as well as deeper foundation and bedding. Trench width and foundation depth should be based on a thorough site investigation.
- Backfill in the area up to the springline should be carefully placed and compacted to achieve a minimum E-value of 1,000 ps as detailed in ASTM D2321. A minimum of 12" of backfill should be placed and compacted above the crown of the pipe. It is typical for trenches to be backfilled entirely with Type I or Type II materials when under pavement.
- Flexible pipe should never be installed in a concrete cradle, as done for rigid pipe in a Class A installation. This type of installation could create concentrated forces at the ends of the cradle when the pipe has deformed.



NOTE:  
 IF CONTRACTOR/DEVELOPER USES ALTERNATIVE HDPE PIPE,  
 ALL SEWER CROSSINGS SHALL BE CONCRETE ENCASED.  
 ALL FLARED END SECTIONS AND INLET STRUCTURES WILL BE CONCRETE.