



NOTES:

1. STRAW BALES, NOT HAY BALES SHALL BE USED.
2. BUTT ENDS OF BALES TIGHTLY TOGETHER.
3. INSTALL BALES WITH BINDING AROUND SIDES, NOT TOP AND BOTTOM.
4. FILL ANY GAP BETWEEN BALES BY WEAVING LOOSE STRAW BETWEEN THEM.

SEDIMENT BARRIER
NO SCALE

GRADING QUANTITIES:

6,703 C.Y. CUT
17,400 C.Y. FILL (INCLUDES 15% SHRINKAGE)
10,400 C.Y. SHORTAGE

THE ABOVE GRADING QUANTITY IS APPROXIMATE ONLY, NOT FOR BIDDING PURPOSES. CONTRACTOR SHALL VERIFY QUANTITIES PRIOR TO CONSTRUCTION.

IT IS THE INTENTION OF THE ENGINEER FOR THE EARTHWORK TO RECEIVE 11,595 CU. YDS. EXCESS CUT FROM THE TRACT TO THE NORTH OF THIS SITE. ENGINEER SHALL BE NOTIFIED IF ANY DIFFICULTIES ARISE IN ACHIEVING THE REQUIRED EXCESS.