



 AREA TO BE DEMOLISHED
 STRIPING TO BE REMOVED

IF AIR ALCOVE CONTAINS EXISTING WATER HYDRANT, CORE DRILL AND CAP BELOW GRADE, PATCH CONCRETE, AND DISCONNECT PIPE FROM WATER SOURCE AT BUILDING.

VERIFY WITH FPM/QT REPRESENTATIVE PRIOR TO DEMOLITION THE EXTENT OF SLAB DEMOLITION DUE TO TRANSITIONS BETWEEN STANDARD PARKING AND ACCESSIBLE SPACES WITH LASER LEVEL.

VERIFY EXTENT OF ALL DEMOLITION WORK WITH QUIKTRIP REPRESENTATIVE.

REMOVE AND RELOCATE EXISTING AIR DISPENSER. REMOVE CONCRETE PAD AND REPLACE WITH SOD WITHIN 14 DAYS.

CONTACT DM TO DETERMINE IF PAY PHONE SHOULD BE REPLACED OR REMOVED.

EXISTING QT 662 35 X 115

REMOVE PARKING SIGNAGE.

REMOVE AND RELOCATE EXISTING LANDSCAPING (WITHIN 14 DAYS) FOR NEW SIDEWALK.

REMOVE EXISTING CURB, GUTTER AND SIDEWALK AS NEEDED FOR NEW CURB RAMP.

REMOVE EXISTING CURB RAMP.

REMOVE PARKING STRIPING AND PAINTED ACCESSIBLE PARKING SYMBOLS ALONG FRONT OF BUILDING.

AIMPD100

LINE OF GAS CANOPY ABOVE

HORIZ

PROPERTY LINE

PROPERTY LINE

REMOVE PARKING STRIPING.



LICENSE NUMBER: AR007257
 EXPIRES: 12/31/2014
 SIGNATURE DATE: JAN 06 2012



The McIntosh Group, LLC
 2850 South Boulder, Suite 300
 Tulsa, Oklahoma 74119
 Telephone 918.585.8555
 Telefax 918.583.7382

Quik Trip No. 662

955 Bryan Rd.
 O'Fallon, MO 63366



PROTOTYPE	P-01
DIVISION	6
VERSION	1
DATE	09/08/2011

REV	DATE	DESCRIPTION

SHEET TITLE:
Demo Site Plan

SHEET NUMBER:
AS 100

A1 DEMOLITION SITE PLAN
 1:20" = 1'-0"