


SCALE: 1" = 50'



SILTATION CONTROL DETAIL
 NO SCALE

NOTE: AS STORM SEWER IS INSTALLED IT WILL BE THE RESPONSIBILITY OF THE SEWER CONTRACTOR TO PROVIDE STRAW BALES FOR SILTATION CONTROL AT ALL INLETS.

NOTE: NO GRADING IN OFFSITE AREAS W/O EASEMENT.

B-1 - TEST HOLE (TYP)

C.L. MISSOURI STATE HIGHWAY "K"



MATCH LINE

STRAW BALES FOR SILTATION CONTROL
 PROPERTY W/E JAMES E. AND ARTHUR A. BRASSER AND JANET WEBB
 (NO RECORDS AVAILABLE)

- GENERAL NOTES**
- A Geotechnical Engineer shall be employed by the owner and be on site during grading operations.
 - The grading contractor shall perform a complete grading and compaction operation as shown on the plans, stated in these notes, or reasonably implied therefrom, all in accordance with the plans and notes as interpreted by the geotechnical engineer.
 - All areas will be allowed to drain. All low points should be provided with temporary ditches.
 - A sediment control plan that includes monitored and maintained sediment control basins and/or straw bales should be implemented as soon as possible. No graded area is to be allowed to remain bare over the winter without being seeded and mulched. Care should be exercised to prevent soil from causing adjacent property and killing up existing Christmas stump drilling systems.
 - Debris and foundation material from any existing concrete building structure which is scheduled to be razed for this development must be disposed of off-site, or buried on site.
 - Any existing trash and debris currently on this property must be removed and disposed of off-site, or buried on site.
 - Soft soils to the bottom and base of any existing or former pond site should be removed, spread out and permitted to dry sufficiently to be used as fill. None of this material should be placed in proposed public right-of-way locations, or on storm sewer locations.
 - Site preparation includes the clearance of all stumps, trees, bushes, shrubs, and weeds; the grubbing and removal of roots and other surface obstructions from the site; and the demolition and removal of any non-made structures. The unsuitable material shall be properly disposed of off-site. Topsoil and grass in the fill areas shall be thoroughly mixed prior to the placement of any fill. The Soils Engineer shall approve the mixing operation.
 - Compaction equipment shall consist of tamping rollers, pneumatic-tired rollers, vibratory rollers, or high speed impact sock drive rollers acceptable to the Soils Engineer. The roller shall be designed so as to ensure the creation of a layered fill without proper blending of successive fill layers.
 - The Soils Engineer shall observe and test the placement of the fill to verify that specifications are met. A series of fill density tests will be obtained on each lift of fill. Interim reports showing fill quality will be made to the Owner at regular intervals.
 - The Soils Engineer shall notify the Contractor of rejection of a lift of fill as portion thereof. The Contractor shall remark the rejected portion of fill and notify the Soils Engineer of its acceptance prior to the placement of additional fill.
 - All areas to receive fill shall be scarified to a depth of not less than 6 inches and then compacted to at least 85 percent of the maximum density as determined by the Modified ASTM D 1557 Compaction Test (ASTM-D-1557). Natural slopes steeper than 1 vertical to 3 horizontal to receive fill shall have horizontal benches, with minimum widths of 10 feet and maximum height of 8 feet, cut into the slopes before the placement of any fill. The fill shall be loosely placed in horizontal layers not exceeding 8 inches in thickness and compacted in accordance with the specifications given below. The Soils Engineer shall be responsible for determining the acceptability of soils placed. Any unacceptable soils placed shall be removed at the Contractor's expense.
 - The sequence of operation in the fill area will be fill, compact, verify acceptable soils density, and repetition of the sequence. The acceptable moisture content during the filling operation shall be those at which satisfactory dry densities can be obtained. The acceptable moisture contents during the filling operation in the remaining areas are from 2 to 8 percent above the optimum moisture content.
 - The surface of the fill shall be finished so that it will not pond water. If at the end of a day's work it would appear that there is a ponding area prior to the next working day, the surface shall be finished smooth. If the surface has been finished smooth for any reason, it shall be scarified before proceeding with the placement of succeeding lifts. Fill shall not be placed on frozen ground, nor shall filling operations continue when the temperature is such as to permit the frozen ground to freeze.
 - Fill and backfill should be compacted to the criteria specified in the following table:

CATEGORY	MINIMUM PERCENT COMPACTION
Fill in building areas below footings	90%
Fill under slabs, walls, and pavements	90%
Fill other than building areas	85%
Natural subgrade	85%
Pavement subgrade	90%
Pavement base course	90%

Measured as a percent of the maximum dry density as determined by modified Proctor Test (ASTM-D-1557).
 Moisture content must be within 2 percent below or 4 percent above optimum moisture content if fill is deeper than 10 feet.
 NOTE: Trash and debris shall be disposed of in the detention basin area and other designated areas. All debris shall be buried a minimum of 3 feet below finished grade.