

NOTES:

- 1. ALL DISTURBED AREAS SHALL BE REPAIRED WITH SOD THAT IS A FESCUE BLEND. ALL NETTING SHALL BE REMOVED BEFORE INSTALLATION.
- 2. CONTRACTOR SHALL WATER AND FERTILIZE FOR UP TO 60 DAYS MAXIMUM, OR UNTIL SOD IS ESTABLISHED AND ACCEPTED BY THE GRANTOR.
- 3. ALL IMPROVEMENTS, INCLUDING STORM SEWER, WALLS AND GRADING, WILL BE BY SEPARATE PERMIT BY THE CITY OF O'FALLON.
- 4. 2" FORCE MAIN SHALL BE INSTALLED WITH 6" SEPARATION BETWEEN EACH OF THE THREE LINES.
- DUCKETT CREEK SEWER DISTRICT NOTES:
- 1. EXISTING SANITARY SEWER SERVICE SHALL NOT BE INTERRUPTED.
- 2. CONNECTION TO DUCKETT CREEK SEWER DISTRICT (DCSD) SANITARY SEWERS REQUIRES DCSD INSPECTION. CONTACT THE DCSD INSPECTION DEPARTMENT AT (636) 441-1244 TO SCHEDULE INSPECTION. 48 HOUR ADVANCE NOTICE IS REQUIRED.
- 3. ALL LATERALS UNDER ANY FUTURE PAVEMENT WILL REQUIRE GRANULAR FILL TO TOP OF TRENCH AND/OR BOTTOM OF PAVEMENT SECTION.
- 4. FUTURE LOTS INCLUDING THE CAR WASH REQUIRE SEPARATE PLAN REVIEW AND APPROVAL.
- EACH BUILDING MUST HAVE ITS OWN CONNECTION TO THE PUBLIC WASTER WATER FACILITIES.
- 6. IT IS THE RESPONSIBILITY OF THE OWNER/DEVELOPER TO OBTAIN ALL PERMITS NECESSARY FOR THE PROJECT.

	3~2" FORCE MAIN (PR SCRUBBLES PRIVATE S EXCAVATION F	ANITARY LIFT STATION ERMIT EXC23-000382		BEGIN INSTALLATION OF (PRIVATE)	2 FORCE MAIN	
			CAP TWO OF THE 2" LINES 10 CAP TWO OF THE 2" LINES 10 INSIDE SCRUBBLES EXPRESS WASH HWY, K LLC PROPERTY WASH HWY, K LLC PROPERTY		-EXISTI GRADI	
				· · · · · · · · · · · · · · · · · · ·		
	EXISTING 3~2" SD HDPE DR-9 SANIT MAIN (PRIVATE)	R-21 PVC OR 2 ARY FORCE 0 UND UDD UDD UDD UDD UDD UDD UDD		-2" SDR-21 PVC OR HDPE DR-9 FORCE M (PRIVATE)	· ·	G TO TO FORCE MA
lo+00		11+00		12+00		

- NON-PUMPING DURING PROOFROLLING AND COMPACTION.
- EXISTING SEWERS.

- RECORD PLAT
- STANDARDS OF THE DUCKETT CREEK SANITARY DISTRICT.
- FOR COORDINATION OF INSPECTION.
- VERTICAL DISTANCE OF 21/2 FEET.
- NATURAL RESOURCES SPECIFICATION 10 CSR 20-8.120(6)(F) 1.
- BE USED UNDER PAVEMENT AREAS.

- 18. BRICK SHALL NOT BE USED ON SANITARY SEWER MANHOLES.

- MISSION-TYPE COUPLINGS WILL NOT BE ALLOWED.
- PROPERTIES OR ROADWAYS ARE THE RESPONSIBILITY OF THE DEVELOPER.
- REQUIRED.
- EQUIPMENT AS APPROVED BY THE DISTRICT. TESTING SHALL INCLUDE:
- BE CONDUCTED PRIOR TO 30 DAYS AFTER FINAL BACKFILL.
- PRESSURE DURING A TEST PERIOD OF 5 MINUTES.



CALL BEFORE YOU DIG!

