GENERAL NOTES
1. Do not scale drawing. Follow dimensions.
2. Concrete shall be air entrained with a minimum of 6% and a maximum of 8% entrained air.
3. Reinforcement shall be placed as shown on the plans.
4. Expansion joints shall be placed at 60 ft. intervals.
5. Contraction joints shall be placed at 15 ft. intervals.
6. Concrete shall be placed on a compacted subgrade.
7. Concrete shall be cured by an approved curing method.
8. Concrete shall have a minimum compressive strength of 3000 psi at 28 days.
9. Concrete shall be placed in accordance with Section 1019 of the Missouri Standard Specifications for Highway Construction.
10. Concrete shall be finished with a broom finish.
11. Concrete shall be placed in accordance with Section 1020 of the Missouri Standard Specifications for Highway Construction.
12. Concrete shall be placed in accordance with Section 1021 of the Missouri Standard Specifications for Highway Construction.
13. Concrete shall be placed in accordance with Section 1022 of the Missouri Standard Specifications for Highway Construction.