

GENERAL NOTES

1. Driveway locations shall not interfere with the sidewalk handicap ramps, or curb inlet sumps
2. Sidewalks, curb ramps, ramps and accessible parking spaces shall be constructed in accordance with the current approved "American with Disabilities Act Accessibility Guidelines" (ADAAG) along with the required grades, construction materials, specifications and signage. If any conflict occurs between the above information and the plans, the ADAAG guidelines shall take precedence and the contractor prior to any construction shall notify the Project Engineer.
- 2.1. Truncated domes for curb ramps located in public right of way shall meet PROWAG requirements and shall be constructed using red pre-cast truncated domes per pavement details.
3. Any proposed pavilions or playground areas will need a separate permit from the Building Division.
4. The Contractor is responsible to call Missouri One Call and The City of O'Fallon for the location of utilities. Contact the City of O'Fallon (636) 379-3814 for the location of City maintained cable for street lights and traffic signals, all other utilities call Missouri One Call 1-800-DIG-RITE. 1-800-344-7483
5. All proposed utilities and/or utility relocations shall be located underground.
6. All proposed fencing requires a separate permit through the Building Safety Division.
6. All construction operations and work zone traffic control within the right of way will follow MoDOT or M.U.T.C.D. standards whichever is more stringent.
8. (INTENTIONALLY OMITTED)
9. All subdivision identification or directional sign(s) must have the locations and sizes approved and permitted separately through the Planning and Development Division.
10. Materials such as trees, organic debris, rubble, foundations, and other deleterious material shall be removed from the site and disposed of in compliance with all applicable laws and regulations. If the material listed previously are reused, a letter from a soil Engineer must clarify amount, location, depth, etc. and be approved with the construction plans. Landfill tickets for such disposal shall be maintained on file by the developer. Burning on site shall be allowed only by permit from the local fire district. If a burn pit is proposed the location and mitigation shall be shown on the grading plan and documented by the soils engineer.
11. Twenty-four (24) hours prior to starting any of the work covered by the above plans and after approval thereof, the developer shall make arrangements with the Construction Inspection Office to provide for inspection of the work, sufficient in the opinion of the City Engineer, to assure compliance with the plans and specifications as approved.
12. The City Engineer or their duly authorized representative shall make all necessary inspections of City infrastructure, escrow items or infrastructure located on the approved plans.
13. All installations and construction shall conform to the approved engineering drawings. However, if the developer chooses to make minor modifications in design and/or specifications during construction, he/she shall make such changes at his/her own risk, without any assurance that the City Engineer will approve the completed installation or construction. It shall be the responsibility of the developer to notify the City Engineer of any changes from the approved drawings. The developer may be required to correct the installed improvements so as to conform to the approved engineering drawings. The developer may request a letter from the Construction Inspection Division regarding any field changes approved by the City inspectors.
14. City approval of the construction site plans does not mean that any building can be constructed on the lots without meeting the building setbacks as required by the zoning code.

Grading Notes

1. Developer must supply City Construction Inspectors with an Engineer's soil reports prior to and during site grading. The soil report will be required to contain the following information on soil test curves (Proctor reports) for projects within the City:
 - 1.1. Maximum dry density
 - 1.2. Optimum moisture content
 - 1.3. Maximum and minimum allowable moisture content
 - 1.4. Curve must be plotted to show density from a minimum of 90% Compaction and above as determined by the "Modified AASHTO T-180 Compaction Test" (A.S.T.M.-D-1157) or from a minimum of 95% as determined by the "Standard Proctor Test ASHTO T-99, Method C" (A.S.T.M.-D-698). Proctor type must be designated on document.
 - 1.5. Curve must have at least 5 density points with moisture content and sample locations listed on document
 - 1.6. Specific gravity
 - 1.7. Natural moisture content
 - 1.8. Liquid limit
 - 1.9. Plastic limit
- Be advised that if this information is not provided to the City's Construction Inspector the City will not allow grading or construction activities to proceed on any project site.
2. All fill placed in areas other than proposed storm sewers, sanitary sewers, proposed roads, and paved areas shall be compacted from the bottom of the fill up in 8" lifts and compacted to 90% maximum density as determined by Modified AASHTO T-180 compaction test or 95% of maximum density as determined by the Standard Proctor Test AASHTO T-99. Ensure the moisture content of the soil fill areas corresponds to the compactive effort as defined by the Standard or Modified Proctor Test. Optimum moisture content shall be determined using the same test that was used for compaction. Soil compaction curves shall be submitted to the City of O'Fallon prior to the placement of fill.
3. The surface of the fill shall be finished so it will not impound water. If at the end of a days work it would appear that there may be rain prior to the next working day, the surface shall be finished smooth. If the surface has been finished smooth for any reason, it shall be scuffed before proceeding with the placement of succeeding lifts. Fill shall not be placed on frozen ground, nor shall filling operations continue when the temperature is such as to permit the layer under placement to freeze.
4. All sediment and detention basins are to be constructed during the initial phase of the grading operation or in accordance with the approved SWPPP.
5. When grading operations are complete or suspended for more than 14 days, permanent grass must be established at sufficient density to provide erosion control on site. Between permanent grass seeding periods, temporary cover shall be provided according to Missouri Department of Natural Resources Protecting Water Quality - a field guide to erosion, sediment and stormwater best management practices for development sites in Missouri and Kansas.All finished grades (areas not to be disturbed by improvements) in excess of 20% slopes (5:1) shall be mulched and tacked at a rate of 100 pounds per 1000 square feet when seeded.
6. No slopes shall exceed 3 (horizontal): 1 (vertical) unless otherwise approved by the soils report and specifically located on the plans and approved by the City Engineer.
7. All low places whether on site or off shall be graded to provide drainage with temporary ditches.
8. Any existing wells and/or springs which may exist on the property must be sealed in a manner acceptable to the City of O'Fallon Construction Inspection Department and following Missouri Department of Natural Resources standards and specifications.
9. (INTENTIONALLY OMITTED)
10. All trench back fills under paved areas shall be granular back fill, and compacted mechanically. All other trench back fills may be earth material (free of large clods, or stones) and compacted using either mechanical tamping or water jetting. Granular material and earth material associated with new construction outside of pavements may be jetted, taking care to avoid damage to newly laid sewers. The jetting shall be performed with a probe roter on not greater than 7.5 foot centers with the jetting probe centered over and parallel with the direction of the pipe. Trench widths greater than 10 feet will require multiple probes every 7.5 foot centers.
- 10.1. Depth, Trench back fills less than 8 feet deep shall be probed to a depth extending half the depth of the trench back fill, but not less than 3 feet. Trench back fill greater than 8 feet in depth shall be probed to half the depth of the trench back fill but not greater than 8 feet.
- 10.2. Equipment. The jetting probe shall be a metal pipe with an interior diameter of 1.5 to 2 inches.
- 10.3. Method. Jetting shall be performed from the lowest surface topographic point and proceed toward the highest point, and from the bottom of the trench back fill toward the surface. The flooding of each jetting probe shall be started slowly allowing slow saturation of the soil. Water is not allowed to flow away from the trench without first saturating the trench.
- 10.4. Surface Bridging. The contractor shall identify the locations of the surface bridging (the tendency for the upper surface to crust and arch over the trench rather than collapse and consolidate during the jetting process). The contractor shall break down the bridged areas using an appropriate method such as wheels or bucket of a backhoe. When surface crust is collapsed, the void shall be back filled with the same material used as trench back fill and re-jetted. Compaction of the materials within the sunken/jetted area shall be compacted such that no further surface subsidence occurs.
11. Site grading.
 - 11.1. Within City right-of-way. Material is to be placed in eight (8) inch to twelve (12) inch loose lifts and compacted per the approved compaction requirements. One (1) compaction test will be performed every two hundred fifty (250) feet along the centerline for each lift.
 - 11.2. Outside of City right-of-way. Material is to be placed in eight (8) inch to twelve (12) inch loose lifts and compacted per the approved compaction requirements. One (1) compaction test will be performed at two (2) foot vertical intervals and approximately every one thousand (1,000) cubic yards.
12. Access to the site from any other location other than the proposed construction entrance is strictly prohibited!

Erosion Control Notes

1. The Permittee shall assume complete responsibility for controlling all siltation and erosion of the project area. The Permittee shall use whatever means necessary to control erosion and siltation including, but not limited to, staked straw bales and/or siltation fabric fences (possible methods of control are detailed in the plan). Control shall commence with the clearing operations and be maintained throughout the project until acceptance of the work by City of O'Fallon and as needed by MoDOT. The Permittee's responsibilities include all design and implementation as required to prevent erosion and the depositing of silt. The City of O'Fallon and as required by MoDOT may at their option direct the Permittee in his methods as deemed fit to protect property and improvements. Any depositing of silt or mud on new or existing pavement shall be removed immediately. Any depositing of silts or mud in new or existing storm sewers and/or swales shall be removed after each rain and affected areas cleaned to the satisfaction of the City of O'Fallon and as required by MoDOT."
2. All erosion control systems are to be inspected and corrected weekly, especially within 48 hours of any rain storm resulting in one-quarter inch of rain or more. Any silt or debris leaving the site and affecting public right of way or storm water drainage facilities shall be cleaned up within 24 hours after the end of the storm.
3. Erosion control devices (silt fence, sediment basin, etc.) shall be in accordance with Missouri Department of Natural Resources Protecting Water Quality - a field guide to erosion, sediment and stormwater best management practices for development sites in Missouri and Kansas.
4. This development is required to provide long term post construction BMP's such as; low impact design, source control and treatment controls that protects water quality and controls run off to maximum extent practical in compliance with Phase II Illicit Storm Water Discharge Guidelines. (Ord. 5082, section 405.245)
5. Graded areas shall be seeded and mulched (stowed) within 14 days of stopping land disturbance activities. Unless it can be shown to the City Engineer that weather conditions are not favorable, vegetative growth is to be established within 6 weeks of stopping grading work on the project. The vegetative growth established shall be sufficient to prevent erosion and the standard shall be as required by EPA and DNR. (70% coverage per square foot) Ord. 6496, Section 405.095

Sanitary Sewer Notes

1. All sanitary sewer installation is to be in accordance with M.S.D. standards and specifications except as modified by the City of O'Fallon Ordinances.
2. Brick shall not be used in the construction of sanitary sewer structures. Pre cast concrete structures are to be used unless otherwise approved by the City of O'Fallon.
3. Connections at all sanitary structures are to be made with A-Lock joint or equal
4. All sanitary laterals shall be a minimum of 4" residential, 6" commercial diameter pipe.
5. All sanitary mains shall be a minimum of 8" diameter pipe.
6. All sanitary sewer line with a slope greater than 20% will require concrete cradle or concrete collar at each pipe joint. Sanitary line with a slope greater than 50% will require a special approved design as shown on detail sheet.
7. All manholes built within the 100 year flood plain must have lock type watertight manhole covers.
8. All sanitary sewer mains must have a minimum of 42" cover.
9. When sanitary mains cross over storm line the sanitary main must be ductile iron pipe for 10 feet on each side of the crossing.
10. Encase with concrete both sanitary and storm sewer at crossing when storm sewer is within 18 inches above sanitary sewer. Add concrete cradle to only RCP storm sewer and encase flexible storm sewer when it is more than 18 inches above sanitary line. Show on profile sheet.
11. The sanitary sewers should run diagonally through the side yards to minimize any additional utility easements required.
12. All sanitary sewer structures shall be waterproofed on the exterior in accordance to Missouri DNR specifications 10CSR-8.120 (7)(E).
13. All sanitary sewer pipe shall be SDR35 or equal. All sanitary sewer laterals shall be Schedule 40.
14. All sanitary sewer manholes and pipes will be tested to the following specifications. ASTM C1244, Standard testing method for Concrete Sewer Manhole by Negative Air Pressure (Vacuum), Latest revision ASTM F1417, Standard testing method for Installation Acceptance of Plastic Gravity Sewer Lines Using Low Pressure Air, Latest revision.
15. Add 1" minus rock back fill to all sanitary sewer and all other utilities that lie within the 1:1 shear plane of the road.

Storm Sewer Notes

1. All Storm Sewer installation is to be in accordance with M.S.D. standards and specifications except as modified by the City of O'Fallon ordinances.
2. Brick shall not be used in the construction of storm sewer structures. Pre cast concrete structures are to be used unless otherwise approved by the City of O'Fallon.
3. A 5/8" trash bar shall be installed horizontally in the center of the opening(s) in all curb inlets and area inlets.
4. (INTENTIONALLY OMITTED)
5. Encase with concrete both sanitary and storm sewer at crossing when storm sewer is within 18 inches above sanitary sewer. Add concrete cradle to only RCP storm sewer and encase flexible storm sewer when it is more than 18 inches above sanitary line. Show on profile sheet.
6. The storm sewers should run diagonally through the side yards to minimize any additional utility easements required.
7. All concrete pipes will be installed with O-ring rubber type gaskets.
8. Connections at all storm structures are to be made with A-lock joint or equal.
9. Pre cast concrete inlet covers are not to be used.
10. The swale in the detention basins shall have a minimum 2% longitudinal slope and be lined with a permanent erosion control blanket that will allow infiltration of storm water.
11. All structures and fired end sections must be concrete. H.D.P.E. pipe will not be allowed for detention basin outflows, final pipe run to detention basins, creek discharge or other approved means.
12. (INTENTIONALLY OMITTED)
13. Rip rap shown at flared end sections will be evaluated in the field by the Engineer, Contractor, and City Inspectors after installation for effectiveness and field modified, if necessary to reduce erosion on and off site.
14. Add 1" minus rock back fill to all storm sewer that lie within the 1:1 shear plane of the road.
15. (INTENTIONALLY OMITTED)

Flood plain Information

1. Refer to Section 415 for Floodplain Development Information

Water Notes

1. Fire hydrants shall be a maximum of 600' apart. Local fire district approval is required.
2. Coordinate with the water company on the location of water meters. For meters in the City's district, meters shall be in the right-of-way, otherwise an access easement from the right-of-way shall be provided.
3. All water main must have a minimum of 42" of cover. (City water mains)
4. Provide water valves to isolate the system.
5. All water mains shall be class 200 SDR 21 or equal with locator/tracer wires
6. If the excavations are made in the improved portion of the right-of-way, twelve inches of granular backfill will be placed over exposed facilities and controlled low strength material (CLSM) aka flowable fill will fill the hole with eight inches of the finished surface for concrete pavement. There will be a plastic membrane placed between the rock base and the CLSM to prevent the material from bleeding into the rock base. The remaining eight inches will be restored by placing a 28 day, 4,000 psd concrete mix.
7. DISINFECTING: Disinfecting shall be accomplished by placing sufficient hypo chlorite granule (HTH) in each section of pipe to achieve a chlorine residual in the pipeline, upon initial filling, of 50 mg/L (PPM). HT. tablets will not be allowed. Following completion of the pipeline, it shall be slowly filled with water and a sample will be taken immediately and the chlorine residual must be 50 mg/L or greater. The solution shall be allowed to stand for 24 hours and a sample shall then be taken. The chlorine residual after 24 hours shall be 30 mg/L or greater. If the piping shows insufficient chlorine residuals in either test, the piping shall be re-chlorinated by the injection of hypo chlorite solution until satisfactory results are achieved. All disinfecting shall be done by the contractor. Only the testing to determine the chlorine residual will be done by the City.
8. PRESSURE TESTING: Immediately following disinfection, the piping shall be pumped to a pressure (at the HIGHEST point in the project) of 150 psi or higher where the working pressure is higher than 150 PSI as determined by the City. In such cases, the pressure shall be as specified by the City and two pressure tests shall be conducted. The first test shall be with the fire hydrant auxiliary valve open and be to 50 PSI. The second test shall be with the fire hydrant auxiliary valve closed and be to the higher pressure as directed by the City. All pumping equipment and pressure gauges shall be provided by the contractor. After achieving the test pressure, the piping shall be left closed for a period of two (2) hours. At the end of this time the pressure drops shall not exceed 2 psi. In addition, if the pressure appears, in judgment of the City's representative, to be continuing to drop, the test shall be continued for another two (2) hours and if any further drops occur, the test shall be considered a failure. If the pressure test fails, the contractor will be required to find and correct the source of the leakage. If this requires draining of the pipeline, when the leakage is corrected, the pipeline must be re-disinfected and the pressure tested again until satisfactory result are achieved. Any MDRN required dechlorination will be performed by the contractor.
9. All tops for valves, meters, and manholes are to be constructed to within 1 inch (0.08") of finish grade. Grading around structure tops on slopes need to be accounted for.
10. BACTERIOLOGICAL TESTING: After satisfactory disinfection and pressure testing, a sample shall be taken by the contractor in the presence of a City representative and submitted to a laboratory approved by the Missouri Department of Natural Resources and the City for bacteriological analysis. After 24 hours, a second sample shall be taken in a like manner and submitted for analysis. The two samples taken on consecutive days, a minimum of 24 hours apart, must be found to be "safe" by the testing laboratory, and copies of the test results must be supplied to the City. If the samples are not found to be "safe" further flushing and/or disinfection as directed by the City shall be conducted by the contractor until "safe" samples on two consecutive test days are achieved. Following successful bacteriological testing and a determination by the City that the samples are "safe", the mains may be placed into service.

Roadway Notes


1. All paving (public and private) to be in accordance with St. Louis County Standards and Specifications except as modified by the City of O'Fallon ordinances.
2. If the intersecting road does not have a curb, then the curb on the new entrance shall begin 10' from the edge of the existing road.
3. Provide 6" of concrete over 5" of aggregate base rock or asphalt equivalent for minor residential streets per City Code 405.370.
 - 3.1. Rock to meet the all the requirements of MoDOT type 5 rock with a tighter restriction on the fines being that no more than ten percent (10%) fines shall pass a no. 200 sieve. (City Code 405.210.B.1) The gradation of this rock needs to be submitted to the City for approval. Any deliveries made without the proper delivery ticket, including signatures, will not be accepted. The delivery ticket must list the project name or jobsite location. A separate certification sheet may be provided attached to the delivery ticket with a signature of the company's quality control manager. The quality control certification must be current and dated within 4 weeks of the delivery. (City Code 405.210.A.2.k)
4. Multi-use trail (when required) Shall have a minimum of 3" Type "C" Asphalt over 4" aggregate base per City requirements.
5. Type C (BP-1) Compaction requirements shall be 98% minimum density according to St. Louis Co. Standard Specifications.
6. Provide pavement striping at any point where the multi-use trail crosses existing or proposed pavement
7. All street stub-outs over 250' in length will require a temporary turnaround.
8. All sub grade in cut or fill will need to conform to the City of O'Fallon Compaction requirements
9. Material Testing And Frequency. Materials for construction shall be tested and inspected per the appropriate ASTM code or at the City Engineer's discretion. The developer's engineer shall perform quality control guidelines, in accordance with St. Louis County requirements 501.3.1.
10. Approval Of Sub grade And Base (Sub base). The City Engineer or representative shall approve the sub grade before any base is placed thereon and shall approve the base before concrete or surface course is placed. The sub grade and base shall be so constructed that it will be uniform in density throughout.
11. In all fill areas in the roadways, soil tests shall be submitted and approved by the City Engineer for each foot of fill and at least one (1) test and an average of one (1) test within every two hundred fifty (250) feet.
12. No traffic will be allowed on new concrete pavement until it has cured for seven (7) days and it reaches three thousand five hundred (3,500) psi within 28 days.
 - 12.1. Concrete pavements shall not be approved unless it reaches a strength of four thousand (4,000) psi. Cylinders/compressive strength. One (1) set of four (5) cylinders within the first fifty (50) cubic yards and one (1) set per one hundred (100) cubic yards thereafter. One (1) cylinder must be tested at seven (7) days, three (3) at twenty-eight (28) days, and one (1) held in reserve.
13. Prior to placement of aggregate base material on sub grade and prior to placement of pavement on base material, the sub grade and base must be proof-rolled with a fully loaded (ten (10) ton load) tandem truck or equivalent tire vehicle with one (1) pass down each driving lane no faster than three (3) miles per hour. If soft spots are detected, or pumping, rutting or heaving occurs greater than one (1) inch at the sub grade, the roadbed shall be considered unsatisfactory and the soil in these areas shall be remediated to the depth indicated by the contractor's testing firm and approved by a representative of the City Engineer.
14. Sub grade and base beneath pavements shall be compacted to St. Louis County Highway Department specifications. The moisture range shall be determined by the Standard or Modified Proctor Density Method AASHTO T-99 and within -2/+4 percentage points of the optimum moisture content.
15. The entire width and length will conform to line, grade and cross section shown on the plans or as established by the engineer. If any settling or washing occurs, or where hauling results in ruts or other objectionable irregularities, the contractor shall improve the sub grade or base to the satisfaction of the City before the pavement is placed. Additional rolling or methods to verify compaction shall be at the discretion of the City Engineer. Tolerance allowed on all lines, grades and cross sections shall be plus or minus four-hundredths (+0.04) feet.
16. Utility Work Prior To Base Construction. No base course work may proceed on any street until all utility excavations (storm and sanitary sewers, water, gas, electric, etc.) have been properly back filled with granular material, crushed stone or gravel mechanically tamped in ten (10) inch lifts. Utilities installed after sub grade preparation shall be bored. Compaction requirements shall follow St. Louis Goly standards.
17. Equipment calibration. The developer's contractors and subcontractors must have their equipment calibrated by the following minimum standards.
 - 17.1. Air meter---weekly.
 - 17.2. Cylinder compression---annually by independent calibration service.
 - 17.3. Batch scales---monthly.
 - 17.4. Nuclear testing devices---every six (6) months.
 - 17.5. Proctor equipment---every six (6) months.
 - 17.6. Slump cone---monthly.
18. All permanent traffic control will be per M.U.T.C.D. or MoDot standards. S1-1 from the M.U.T.C.D. manual will be used at all crosswalk locations accompanied with ether w16-9p or w16-7p signs.
19. All traffic signals, street signs, sign post, backs and bracket arms shall be painted black using Carboline Rust Bond Penetrating Sealer SG and Carboline 133 HB paint (or equivalent as approved by City of O'Fallon and MoDOT)
20. If the excavations are made in the improved portion of the right-of-way, twelve inches of granular backfill will be placed over exposed facilities and controlled low strength material (CLSM) aka flowable fill will fill the hole with eight inches of the finished surface for concrete pavement. There will be a plastic membrane placed between the rock base and the CLSM to prevent the material from bleeding into the rock base. The remaining eight inches will be restored by placing a 28 day, 4,000 psi concrete mix.

PROJECT TITLE:


GRADING PLANS FOR
Steiniger W Terra Lane
W Terra Lane
O'Fallon, MO 63366

ENGINEERING
PLANNING
SURVEYING

221 Point View Blvd.
St. Charles, MO 63301
636-928-5562
FAX 928-1718



DISCLAIMER OF RESPONSIBILITY
I hereby specify that the documents intended to be authorized by my seal are limited to this sheet, and I hereby disclaim any responsibility for all other Drawings, Specifications, Estimates, Reports or other documents or instruments relating to or intended to be used for any part or parts of the architectural or engineering project or survey.



Larry D. Walker
CIVIL ENGINEER
2007020343
Copyright 2025
Bax Engineering Company, Inc.
Authority No. 000655
All Rights Reserved

REVISIONS

10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS

Developer / Owner:
Mark Steiniger
854 Long Star Drive
O'Fallon, MO 63366
(636) 978-3478

P+Z No. 25-008321
Approved: 09-04-2025



City No.
GR25-000007

Page No.

2 of 11

CONSTRUCTION NOTES

Bax Project # 22-86008 Issue Date: 10/21/2025



UNDERGROUND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE INFORMATION AND THEREFORE THEIR LOCATIONS SHALL BE CONSIDERED APPROXIMATE ONLY. THE VERIFICATION OF THE LOCATION OF ALL UNDERGROUND UTILITIES, EITHER SHOWN OR NOT SHOWN ON THESE PLANS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE LOCATED PRIOR TO ANY GRADING OR CONSTRUCTION OF THE IMPROVEMENTS.

PROJECT TITLE:
GRADING PLANS FOR
Steiniger W Terra Lane
W Terra Lane
O'Fallon, MO 63366

**ENGINEERING
PLANNING
SURVEYING**
221 Point View Blvd.
St. Charles, MO 63301
636-928-5562
FAX 928-1718

DISCLAIMER OF RESPONSIBILITY
I hereby specify that the documents intended to be
utilized by my seal are limited to this sheet,
and I hereby disclaim any responsibility for all other
drawings, specifications, estimates, reports or other
documents or instruments relating to or intended to
be used for any part or parts of the architectural or
engineering project or survey.

Larry D. Walker
CIVIL ENGINEER
2007020343
Copyright 2025
Box Engineering Company, Inc.
Authority No. 000655
All Rights Reserved

REVISIONS	
10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS


Developer / Owner:
Mark Steiniger
854 Long Star Drive
O'Fallon, MO 63366
(636) 978-3478

P+Z No. 25-008321
Approved: 09-04-2025

City No.
GR25-000007

Page No.
3 of 11

FLOOD EXHIBIT




* Tree Preservation calculations: 20% of existing trees or 15 trees per acre (whichever is greater) shall be preserved

4.115 Acres Existing Trees x 0.20 = 0.82 Acres Required Trees Preserved

Total Trees Preserved = 0.93 Acres Trees

- NOTES:
1. ALL 5:1 SLOPES TO 3:1 SLOPES SHALL BE COVERED WITH NORTH AMERICAN GREEN S75 EROSION CONTROL BLANKET (OR EQUIVALENT).
 2. CONTRACTOR TO KEEP ROADWAYS CLEAN AND FREE OF DEBRIS AT ALL TIMES.
 3. CONTRACTOR TO REPAIR GREENSPACE IN RIGHT OF WAY WITH SOD.
 4. CLEARING LIMITS SHALL BE VISIBLY MARKED IN THE FIELD PRIOR TO THE REMOVAL OF TREES.
 5. TREE CLEARING MAY TAKE PLACE BETWEEN OCTOBER 16TH AND MARCH 31ST. ANY CLEARING OUTSIDE OF THIS TIMEFRAME MUST BE CLEARED BY U.S. FISH AND WILDLIFE.



UNDERGROUND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE INFORMATION AND THEREFORE THEIR LOCATIONS SHALL BE CONSIDERED APPROXIMATE ONLY. THE VERIFICATION OF THE LOCATION OF ALL UNDERGROUND UTILITIES, EITHER SHOWN OR NOT SHOWN ON THESE PLANS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE LOCATED PRIOR TO ANY GRADING OR CONSTRUCTION OF THE IMPROVEMENTS.

PROJECT TITLE:

GRADING PLANS FOR

Steiniger W Terra Lane

W Terra Lane

O'Fallon, MO 63366

ENGINEERING

PLANNING

SURVEYING

221 Point View Blvd.


St. Charles, MO 63301

636-928-5562

FAX 928-1718

DISCLAIMER OF RESPONSIBILITY

I hereby specify that the documents intended to be authorized by my seal are limited to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be used for any part or parts of the architectural or engineering project or survey.



Larry D. Walker

CIVIL ENGINEER

2007020343

Copyright © 2025

Box Engineering Company, Inc.

Authority No. 000655

All Rights Reserved

REVISIONS

10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS

Developer / Owner:

Mark Steiniger

854 Long Star Drive

O'Fallon, MO 63366

(636) 978-3478

P+Z No. 25-008321

Approved: 09-04-2025

City No.


GR25-000007

Page No.


4 of 11

DEMOLITION PLAN

Box Project # 22-186008 Issue Date: 10/21/2025



- NOTES:
1. ALL 5:1 SLOPES TO 3:1 SLOPES SHALL BE COVERED WITH NORTH AMERICAN GREEN S75 EROSION CONTROL BLANKET (OR EQUIVALENT).
 2. CONTRACTOR TO KEEP ROADWAYS CLEAN AND FREE OF DEBRIS AT ALL TIMES.
 3. CONTRACTOR TO REPAIR GREENSPACE IN RIGHT OF WAY WITH SOD.
 4. CLEARING LIMITS SHALL BE VISIBLY MARKED IN THE FIELD PRIOR TO THE REMOVAL OF TREES.



UNDERGROUND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE INFORMATION AND THEREFORE THEIR LOCATIONS SHALL BE CONSIDERED APPROXIMATE ONLY. THE VERIFICATION OF THE LOCATION OF ALL UNDERGROUND UTILITIES, EITHER SHOWN OR NOT SHOWN ON THESE PLANS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE LOCATED PRIOR TO ANY GRADING OR CONSTRUCTION OF THE IMPROVEMENTS.


PROJECT TITLE:
GRADING PLANS FOR
Steinieger W Terra Lane
W Terra Lane
O'Fallon, MO 63366

**ENGINEERING
PLANNING
SURVEYING**

■ 221 Point West Blvd.
St. Charles, MO 63301
636-928-5552
FAX 928-1718



DISCLAIMER OF RESPONSIBILITY
I hereby specify that the documents intended to be authenticated by my seal are limited to this sheet, and I hereby disclaim any responsibility for all other Drawings, Specifications, Estimates, Reports or other documents or instruments relating to or intended to be used for any part or parts of the architectural or engineering project or survey.



Larry D. Walker
CIVIL ENGINEER
2007020343
Copyright 2025
Bax Engineering Company, Inc.
Authority No. 000655
All Rights Reserved

REVISIONS

10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS

Developer / Owner:
Mark Steiniger
854 Long Star Drive
O'Fallon, MO 63366
(636) 978-3478

P+Z No. 25-008321
Approved: 09-04-2025



City No. GR25-000007

Page No.


5 of 11

GRADING PLAN


Bax Project # 22-18600B Issue Date: 10/21/2025




Basin Section A-A
HORIZONTAL SCALE: 1" = 20'
VERTICAL SCALE: 1" = 10'



Basin Section B-B
HORIZONTAL SCALE: 1" = 20'
VERTICAL SCALE: 1" = 10'




Basin Section C-C
HORIZONTAL SCALE: 1" = 20'
VERTICAL SCALE: 1" = 10'



OVERFLOW STRUCTURE DETAIL
NOT TO SCALE


18"W x 18" H DEBRIS CAGE
#3 BARS BOLTED IN EIGHT PLACES TO
OUTFALL STRUCTURE WALL.
3" MAXIMUM SPACING OF REBAR, CAGE TO
EXTEND A MINIMUM OF 6" FROM FACE OF
STRUCTURE.

ORIFICE DEBRIS CAGE
N.T.S.



12" W x 12" H
UPPER FLOW ORIFICE
F.L. = 496.00

6" W x 18" H
UPPER FLOW ORIFICE
F.L. = 494.50




TEMPORARY SEDIMENT BASIN DETAIL
NOT TO SCALE

NOTE: PAINT MARK @ ELEV. 496.50
FOR CLEANOUT OF SEDIMENT BASIN.
DETENTION BASIN SHALL BE USED FOR TEMPORARY SEDIMENT BASIN.


UNDERGROUND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE INFORMATION AND THEREFORE THEIR LOCATIONS SHALL BE CONSIDERED APPROXIMATE ONLY. THE VERIFICATION OF THE LOCATION OF ALL UNDERGROUND UTILITIES, EITHER SHOWN OR NOT SHOWN ON THESE PLANS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE LOCATED PRIOR TO ANY GRADING OR CONSTRUCTION OF THE IMPROVEMENTS.

PROJECT TITLE:
GRADING PLANS FOR
Steiniger W Terra Lane
W Terra Lane
O'Fallon, MO 63366

**ENGINEERING
PLANNING
SURVEYING**
221 Point View Blvd.
St. Charles, MO 63301
636-928-5562
FAX 928-1718



DISCLAIMER OF RESPONSIBILITY
I hereby specify that the documents intended to be authorized by my seal are limited to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be used for any part or parts of the architectural or engineering project or survey.



Larry D. Walker
CIVIL ENGINEER
2007020343
Copyright 2025
Box Engineering Company, Inc.
Authority No. 000655
All Rights Reserved

REVISIONS

10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS

Developer / Owner:
Mark Steiniger
854 Long Star Drive
O'Fallon, MO 63366
(636) 978-3478

P+Z No. 25-008321
Approved: 09-04-2025



City No.
GR25-000007

Page No.


6 of 11

BASIN AND STORM DETAILS


Box Project # 22-186008 Issue Date: 10/21/2025




STORM PROFILE
HORIZONTAL SCALE: 1"=40'
VERTICAL SCALE: 1"=10'



STORM PROFILE
HORIZONTAL SCALE: 1"=40'
VERTICAL SCALE: 1"=10'



SNOUT DETAIL AI 202 PLAN VIEW
NOT TO SCALE




SNOUT DETAIL AI 202 PROFILE VIEW: A-A
NOT TO SCALE


UNDERGROUND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE INFORMATION AND THEREFORE THEIR LOCATIONS SHALL BE CONSIDERED APPROXIMATE ONLY. THE VERIFICATION OF THE LOCATION OF ALL UNDERGROUND UTILITIES, EITHER SHOWN OR NOT SHOWN ON THESE PLANS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE LOCATED PRIOR TO ANY GRADING OR CONSTRUCTION OF THE IMPROVEMENTS.

PROJECT TITLE:
GRADING PLANS FOR
Steiniger W Terra Lane
W Terra Lane
O'Fallon, MO 63366

ENGINEERING
PLANNING
SURVEYING
22 Point View Blvd.
St. Charles, MO 63301
636-928-5562
FAX 928-1718



DISCLAIMER OF RESPONSIBILITY
I hereby specify that the documents intended to be authorized by my seal are limited to this sheet, and I hereby disclaim any responsibility for all other Drawings, Specifications, Estimates, Reports or other documents or instruments resting to or intended to be used for any part or parts of the architectural or engineering project or survey.



Larry D. Walker
CIVIL ENGINEER
2007020343
Copyright 2025
Box Engineering Company, Inc.
Authority No. 000655
All Rights Reserved

REVISIONS

10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS

Developer / Owner:
Mark Steiniger
854 Long Star Drive
O'Fallon, MO 63366
(636) 978-3478

P+Z No. 25-008321
Approved: 09-04-2025

City No.
GR25-000007

Page No.

7 of 11

STORMWATER PROFILES

FILTREXX™
Silt/Sediment Control Technology

SWPPP Cut Sheet
Last Updated: 7-1-07

Section 1: Erosion and Sediment Control – Construction Activities

1.1 Filtrrexx SiltSoxx™
Sediment & Perimeter Control Technology


PURPOSE & DESCRIPTION
Filtrrexx SiltSoxx™ are a three-dimensional tubular sediment control and storm water runoff filtration device typically used for **perimeter control** of sediment and other soluble pollutants (such as phosphorus and petroleum hydrocarbons), on and around construction activities.

- APPLICATION**
Filtrrexx SiltSoxx™ are to be installed down slope of any disturbed area requiring erosion and sediment control, and filtration of soluble pollutants from runoff. SiltSoxx™ are effective when installed perpendicular to sheet or low concentrated flow. Acceptable applications include:
- Site perimeters
 - Above and below disturbed areas subject to sheet runoff, interrill and rill erosion
 - Above and below exposed and erodible slopes
 - Around area drains or inlets located in a "rump"
 - On compacted soils where trenching of silt fence is difficult or impossible
 - Around sensitive trees where trenching of silt fence is not beneficial for tree survival or may unnecessarily disturb established vegetation.
 - On frozen ground where trenching of silt fence is impossible.
 - On paved surfaces where trenching of silt fence is impossible.

- INSTALLATION**
1. SiltSoxx™ used for perimeter control of sediment and soluble pollutants in storm runoff shall meet Filtrrexx SiltSoxx™ Material Specifications and use Certified Filtrrexx FiltrMedia™.
 2. Contractor is required to be Filtrrexx Certified™ as determined by Filtrrexx International, LLC (440-926-2607) or visit website at www.filtrrexx.com. Certification shall be considered current if appropriate identification is shown during time of bid or at time of application (current listing can be found at www.filtrrexx.com). Look for the Filtrrexx Certified™ Seal.
 3. SiltSoxx™ will be placed at locations indicated on plans as directed by the Engineer.
 4. SiltSoxx™ should be installed parallel to the base of the slope or other disturbed area. In extreme conditions (i.e., 2:1 slopes), a second SiltSoxx™ shall be constructed at the top of the slope.
 5. Staples shall be installed through the middle of the SiltSoxx™ on 10 ft (3m) centers, using 2 in (50mm) by 2 in (50mm) by 3 ft (1m) wooden stakes. In the event staking is not possible, i.e., when SiltSoxx™ are used on pavement, heavy concrete blocks shall be used behind the SiltSoxx™ to help stabilize during rainfall/runoff events.
 6. Staking depth for sand and silt loam soils shall be 12 in (300mm), and 8 in (200mm) for clay soils.
 7. Loose compost may be backfilled along the up-slope side of the SiltSoxx™, filling the seam between the soil surface and the device, improving filtration and sediment retention.
 8. If the SiltSoxx™ is to be left as a permanent filter or part of the natural landscape, it may be seeded at time of installation for establishment of permanent vegetation. The Engineer will specify seed requirements.
 9. Filtrrexx SiltSoxx™ are not to be used in perennial, ephemeral, or intermittent streams.
- See design drawing schematic for correct Filtrrexx SiltSoxx™ installation (Figure 1.1).

- INSPECTION AND MAINTENANCE**
Routine inspection should be conducted within 24 hrs of a runoff event or as designated by the regulating authority. SiltSoxx™ should be regularly inspected to make sure they maintain their shape and are producing adequate hydraulic flow-through. If ponding becomes excessive, additional SiltSoxx™ may be required to reduce effective slope length and sediment removal may be necessary. SiltSoxx™ shall be inspected until area above has been permanently stabilized and construction activity has ceased.
1. The Contractor shall maintain the SiltSoxx™ in a functional condition at all times and it shall be routinely inspected.
 2. If the SiltSoxx™ has been damaged, it shall be repaired, or replaced if beyond repair.
 3. The Contractor shall remove sediment at the base of the up-slope side of the SiltSoxx™ when accumulation has reached 1/2 of the effective height of the SiltSoxx™, or as directed by the Engineer. Alternatively, a new SiltSoxx™ can be placed on top of and slightly behind the original one creating more sediment storage capacity without soil disturbance.
 4. SiltSoxx™ shall be maintained until disturbed area above the device has been permanently stabilized and construction activity has ceased.
 5. The FiltrMedia™ will be dispersed on site once disturbed area has been permanently stabilized, construction activity has ceased, or as determined by the Engineer.
 6. For long-term sediment and pollutant control applications, SiltSoxx™ can be needed at the time of installation to create a vegetative filtering system for prolonged and increased filtration of sediment and soluble pollutants (contained vegetative filter strip). The appropriate seed mix shall be determined by the Engineer.


Filtrrexx® SiltSoxx™ Details




- Notes:**
1. All material to meet Filtrrexx specifications.
 2. SiltSoxx™ composite/pollockseed fill to meet application requirements.
 3. SiltSoxx™ depicted is for minimum slopes. Greater slopes may require larger rocks per the Engineer.
 4. Compost material to be dispersed on site, as determined by Engineer.

Slope Percent	Maximum Slope Length Above SiltSoxx™ in Feet (meters)*				
	8 in (200 mm) SiltSoxx™	12 in (300 mm) SiltSoxx™	18 in (450 mm) SiltSoxx™	24 in (600mm) SiltSoxx™	32 in (800mm) SiltSoxx™
2 (or less)	600 (180)	750 (225)	1000 (300)	1300 (400)	1650 (500)
5	400 (120)	500 (150)	550 (165)	650 (200)	750 (225)
10	200 (60)	250 (75)	300 (90)	400 (120)	500 (150)
15	140 (40)	170 (50)	200 (60)	325 (100)	450 (140)
20	100 (30)	125 (38)	140 (42)	260 (80)	400 (120)
25	80 (24)	100 (30)	110 (33)	200 (60)	275 (85)
30	60 (18)	75 (23)	90 (27)	130 (40)	200 (60)
35	60 (18)	75 (23)	80 (24)	115 (35)	150 (45)
40	60 (18)	75 (23)	80 (24)	100 (30)	125 (38)
45	40 (12)	50 (15)	60 (18)	80 (24)	100 (30)
50	40 (12)	50 (15)	55 (17)	65 (20)	75 (23)

*Based on a failure point of 36 in (0.9 m) super silt fence (wire reinforced) at 1000 ft (303 m) of slope, watershed width equivalent to receiving length of sediment control device, 1 in/ 24 in (25 mm/24 mm) rain event. **Effective height of Silt Soxx™ after installation and with constant head from runoff as determined by Ohio State University.



- Notes:**
1. ALL MATERIAL TO MEET SPECIFICATIONS.
 2. FILTER MEDIA TO MEET APPLICATION REQUIREMENTS.
 3. FILTER MEDIA TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.



SiltSoxx™ for Sediment Control on Pavement

Storm Water Pollution Prevention Plan


- A. PURPOSE:
- The purpose of the Storm Water Pollution Prevention Plan (SWPPP) is to inform the Developer/Contractor of the following objectives they are required to meet:
- Prevent erosion where construction activities shall occur.
 - Prevent pollutants from mixing with storm water.
 - Prevent pollutants from being discharged by trapping them on-site, before they can affect the receiving waters.
 - All regulations of Missouri Department of Natural Resources are met.
 - All regulations of the Environmental Protection Agency are met.
 - All regulations of the local municipality are met.

- B. PROJECT DESCRIPTION:
- The project is located in the Peru Creek watershed in St. Charles County, Missouri. This project disturbs approximately 3.88 acres.
- The project activities consist of the construction of a new building, parking lot and entrance. The site will be protected by the various erosion protection measures listed below:
1. Siltation Control: The entire perimeter of the project that allows storm water to exit will have silt siltation control installed. Details of these devices are depicted on the detail plans prepared by Box Engineering Company, Inc.
 2. Revegetation: The site will consist of varying ground slopes, upon completion of the grading activities the slope prone to erosion will be seeded and strawed to stabilize the slope and prevent erosion.

Table 60-5 Soil Stabilization Schedule

Soil Disturbance Activity or Condition	Required Stabilization Time
Soil disturbance has ceased in areas greater than 2,000 square feet.	14 days
After construction of dikes, swales, diversions, and other concentrated flow areas.	5 days
When slopes are greater than 3% and longer than 150 feet.	7 days
When slopes are greater than 3% and longer than 150 feet.	14 days
Perimeter controls around soil stockpiles.	End of workday
Stabilization or covering of inactive stockpiles.	30 days
When land disturbance is completed, permanent soil stabilization must be installed.	30 days

STABILIZED CONSTRUCTION ENTRANCE



CONSTRUCTION SPECIFICATIONS

1. Stone Size – Use 2" stone, or reclaimed or recycled concrete equivalent.
2. Length – As required, but not less than 50 feet (except on a single residence lot where a 30 foot minimum length would apply).
3. Thickness – Not less than six (6) inches.
4. Width – Twenty (20) foot minimum, but not less than the full width at points where ingress or egress occurs.
5. Filter Cloth – Will be placed over the entire area prior to placing of stone. Filter will not be required on a single family residence lot.
6. Surface Water All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted.
7. Maintenance – The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanup of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately.
8. Washing – Wheels shall be cleaned to remove sediment prior to entrance onto public rights-of-way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
9. Periodic inspection and needed maintenance shall be provided after each rain.

CHANNEL INSTALLATION DETAIL

1. Prepare soil before installing rolled erosion control products (RECPs), including any necessary application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the RECPs in a 6" (15cm) deep X 6" (15cm) wide trench with approximately 12" (30cm) of RECPs extended beyond the up-slope portion of the trench. Use ShoreMax mat at the channel/culvert outlet as supplemental scour protection as needed. Anchor the RECPs with a row of staples/stakes approximately 12" (30cm) apart in the bottom of the trench. Backfill and compact the trench after stapling. Apply seed to the compacted soil and fold the remaining 12" (30cm) portion of RECPs back over the seed and compacted soil. Secure RECPs over compacted soil with a row of staples/stakes spaced approximately 12" apart across the width of the RECPs.
3. Roll center RECPs in direction of water flow in bottom of channel. RECPs will unroll with appropriate side against the soil surface. All RECPs must be securely fastened to soil surface by placing staples/stakes in appropriate locations as shown in the staple pattern guide.
4. Place consecutive RECPs end-over-end (Shingle style) with a 4"-6" overlap. Use a double row of staples staggered 4" apart and 4" on center to secure RECPs.
5. Full length edge of RECPs at top of side slopes must be anchored with a row of staples/stakes approximately 12" (30cm) apart in a 6" (15cm) deep X 6" (15cm) wide trench. Backfill and compact the trench after stapling.
6. Adjacent RECPs must be overlapped (depending on RECPs type) and stapled.
7. In high flow channel applications a staple check slot is recommended at 30 to 40 foot (9 -12m) intervals. Use a double row of staples staggered 4" (10cm) apart and 4" (10cm) on center over entire width of the channel.
8. The terminal end of the RECPs must be anchored with a row of staples/stakes approximately 12" (30cm) apart in a 6" (15cm) deep X 6" (15cm) wide trench. Backfill and compact the trench after stapling.

VEGETATION ESTABLISHMENT For Urban Development Sites APPENDIX A	
SEEDING RATES:	
PERMANENT:	
Tall Fescue – 30 lbs./ac. Smooth	
Brome – 20 lbs./ac.	
Combined – Fescue @ 15 lbs./ac. AND Brome @ 10 lbs./ac.	
TEMPORARY:	
Wheat or Rye – 150 lbs./ac. (3.5 lbs. per 1,000 s.f.)	
Oats – 120 lbs./ac. (2.75 lbs. per 1,000 s.f.)	
SEEDING PERIODS:	
Fescue or Brome – March 1 to June 1	August 1 to October 1
Wheat or Rye – March 15 to November 1	October 1 to September 15
MULCH RATES:	
100 lbs. per 1,000 sq. ft. (4,356 lbs. per ac.)	
FERTILIZER RATES:	
Nitrogen – 30 lbs./ac.	
Phosphate – 30 lbs./ac.	
Potassium – 30 lbs./ac.	
Lime – 600 lbs./ac. ENM*	
* ENM = effective neutralizing material as per state evaluation of quarried rock.	

ROLLMAX™
ROLLED EROSION CONTROL

Specification Sheet – EroNet® P300® Permanent Erosion Control Blanket

DESCRIPTION
The permanent erosion control blanket shall be a machine-produced mat of 100% UV-stable polypropylene fiber. The matting shall be of consistent thickness with the synthetic fibers evenly distributed over the entire area of the mat. The matting shall be covered on the top side with black heavy-weight UV-stabilized polypropylene netting having ultraviolet additives to delay breakdown and an approximate 0.50 x 0.50 inch (1.27 x 1.27 cm) mesh. The bottom net shall also be UV-stabilized polypropylene with a 0.63 x 0.63 inch (1.57 x 1.57 cm) mesh size. The blanket shall be sewn together on 15 inch (3.81 cm) centers with non-degradable thread. All mats shall be manufactured with a colored thread ditched along both outer edges as an overlap guide for adjacent mats. The P300 shall meet Type 5A, 5B, specification requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) FP-03 Section 713.18

Index Property	Test Method	Typical
Thickness	ASTM D6525	0.47 in (9.34 mm)
Resiliency	ASTM D6524	31.5%
Density	ASTM D792	0.96 g/cm³
Mass/Unit Area	ASTM K566	13.03 oz/yd² (44.93 g/m²)
UV Stability	ASTM D4385/1000 hr	99%
Permeability	ECTC Guidelines	≥ 55.9%
Stiffness	ASTM D1398	0.94 in-lb (0.01529 m-g-cm)
Light Penetration	ASTM D6587	17.9%
Tensile Strength – MD	ASTM D6198	426 lb/ft (6.43 kN/m)
Elongation – MD	ASTM D6198	28.1%
Tensile Strength – TD	ASTM D6198	291.9 lb/ft (4.32 kN/m)
Elongation – TD	ASTM D6198	36.7%
Biomass Improvement	ASTM D7332	49.7%

Standard Roll Sizes	Long Densities
Width	6.5 ft (2.0 m)
Length	10.0 ft (3.0 m)
Weight ± 10%	51 lbs (22.6 kg)
Area	80 sq yd (66.0 m²)

Slope Design Data: C Factors	Slope Gradients (S)
Slope Length (L)	≤ 3:1
≤ 20 ft (6 m)	0.001
20-50 ft	0.006
≥ 50 ft (15.2 m)	0.070

Tensar International Corporation
2550 Northridge Parkway
Suite 500
Atlanta, GA 30309
800-TENSAR-1
tensarcorp.com

ERONET® P300®
Erosion Control Blanket

Tensar NORTH AMERICAN GREEN

Tensar International Corporation
5401 St. Wendel-Cynthiana Road
Poseyville, Indiana 47635
Tel. 800-772-2040
Fax 812-867-0247
www.namgreen.com

Material and Performance Specification S75 Erosion Control Blanket

Description	Index Property	Test Method	Typical
The short-term single net erosion control blanket shall be a machine-produced mat of 100% agricultural straw with a mechanical longevity of up to 12 months. (NOTE: functional longevity may vary depending upon climatic conditions, soil, geographical location, and elevation). The blanket shall be of consistent thickness with the straw evenly distributed over the entire area of the mat. The blanket shall be covered on the top side with a lightweight photodegradable polypropylene netting having an approximate 0.50 x 0.50 (1.27 x 1.27 cm) mesh. The blanket shall be sewn together on 1.50 inch (3.81 cm) centers with degradable thread. The blanket shall be manufactured with a colored thread ditched along both outer edges (approximately 2-5 inches (5-12.5 cm) from the edge) as an overlap guide for adjacent mats.	Thickness	ASTM D6525	0.37 in (9.4 mm)
	Resiliency	ECTC Guidelines	78.9%
	Water Absorbency	ASTM D1117	426%
	Mass/Unit Area	ASTM 6475	11.97 oz/yd² (407 g/m²)
	Smell	ECTC Guidelines	15%
	Smolder Resistance	ECTC Guidelines	Yes
	Stiffness	ASTM D1398	6.31 oz-in
	Light Penetration	ECTC Guidelines	7.3%
	Tensile Strength – MD	ASTM D6818	130.8 lb/ft (1.94 kN/m)
	Elongation – MD	ASTM D6818	24.4%
The S75 shall meet Type 2,C specification requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) FP-03 Section 713.17	Tensile Strength – TD	ASTM D6818	85.2 lb/ft (1.26 kN/m)
	Elongation – TD	ASTM D6818	26.8%

Material Content	Maximum Permissible Shear Stress
Matrix: 100% Straw Fiber	Unvegetated Shear Stress 1.55 lbs/ft² (74 Pa)
Netting: Top side only, lightweight photodegradable	Unvegetated Velocity 5.00 fty (1.52 m/s)
Thread: degradable	

Standard Roll Sizes	Long Densities
Width	6.6 ft (2.03 m)
Length	10.0 ft (3.0 m)
Weight ± 10%	40 lbs (18.14 kg)
Area	80 yd² (66.9 m²)

Slope Design Data: C Factors	Slope Gradients (S)
Slope Length (L)	≤ 3:1
≤ 20 ft (6 m)	0.029
20-50 ft	0.11
≥ 50 ft (15.2 m)	0.19

Test Method	Bench Scale Testing (NTPRP)	Results
ECTC-2 Rainfall	50 mm (2 in)/hr-30 min incubation	SLR** = 6.80
ECTC-3 Shear Res.	150 mm (6 in)/hr-30 min incubation	SLR** = 8.16
ECTC-4 Top Soil, Fescue, 21 day Germination	Shear at 0.50 inch soil loss	SLR** = 7.81
	Top Soil, Fescue, 21 day Germination	1.80 lbs/ft²
	228% improvement of Storms	

Proud Participant of:

Tensar International Corporation warrants that the time of delivery the product furnished hereunder shall conform to the specification stated herein. Any other warranty made by the manufacturer is hereby disclaimed. If the product does not conform to the specification stated herein, Tensar will replace the product at no cost to the customer. This is a design specification and does not constitute a warranty. Tensar is not responsible for the product described above and is not liable to any party for the product described above.

4401 St. Wendel - Cynthiana Rd. Poseyville, IN 47633

PH: 800-772-2040
www.namgreen.com

Tensar NORTH AMERICAN GREEN

Channel Installation Detail

CRITICAL POINTS

- A. Overlaps and Seams
- B. Projected Water Line
- C. Channel Bottom/Side Slope Vertices

NOTES:

- **In loose soil conditions, the use of staple or stake lengths greater than 6" (15cm) may be necessary to properly secure the RECPs.

Disclaimer:
The information presented herein is general design information only. For specific applications, consult an independent professional for further design guidance.

Drawing Not To Scale

Drawing on: 3-16-11

VEGETATION ESTABLISHMENT For Urban Development Sites APPENDIX A	
SEEDING RATES:	
PERMANENT:	
Tall Fescue – 30 lbs./ac. Smooth	
Brome – 20 lbs./ac.	
Combined – Fescue @ 15 lbs./ac. AND Brome @ 10 lbs./ac.	
TEMPORARY:	
Wheat or Rye – 150 lbs./ac. (3.5 lbs. per 1,000 s.f.)	
Oats – 120 lbs./ac. (2.75 lbs. per 1,000 s.f.)	
SEEDING PERIODS:	
Fescue or Brome – March 1 to June 1	August 1 to October 1
Wheat or Rye – March 15 to November 1	October 1 to September 15
MULCH RATES:	
100 lbs. per 1,000 sq. ft. (4,356 lbs. per ac.)	
FERTILIZER RATES:	
Nitrogen – 30 lbs./ac.	
Phosphate – 30 lbs./ac.	
Potassium – 30 lbs./ac.	
Lime – 600 lbs./ac. ENM*	
* ENM = effective neutralizing material as per state evaluation of quarried rock.	


ENGINEER SEAL DOES NOT APPLY TO FILTREXX AND TENSAR DETAILS

PROJECT TITLE:

GRADING PLANS FOR
Steiniger W Terra Lane
W Terra Lane
O'Fallon, MO 63366

ENGINEERING PLANNING SURVEYING

221 Point View Blvd.
St. Charles, MO 63301
636-928-5562
FAX 928-1718



DISCLAIMER OF RESPONSIBILITY
I hereby specify that the documents intended to be authorized by my seal are limited to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be used for any part of the architectural or engineering project or survey.



Larry D. Walker
Civil Engineer
2007020343
Copyright © 2025
Box Engineering Company, Inc.
Authority No. 000655
All Rights Reserved

REVISIONS	
10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS



Developer / Owner:
Mark Steiniger
854 Long Star Drive
O'Fallon, MO 63366
(636) 978-3478

SEDIMENT AND EROSION CONTROL DETAILS

P+Z No. 25-008321
Approved: 09-04-2025

City No.
GR25-000007

Page No.
9 of 11



UNDERGROUND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE INFORMATION AND THEREFORE THEIR LOCATIONS SHALL BE CONSIDERED APPROXIMATE ONLY. THE VERIFICATION OF THE LOCATION OF ALL UNDERGROUND UTILITIES, EITHER SHOWN OR NOT SHOWN ON THESE PLANS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE LOCATED PRIOR TO ANY GRADING OR CONSTRUCTION OF THE IMPROVEMENTS.

PROJECT TITLE:
GRADING PLANS FOR
Steiniger W Terra Lane
W Terra Lane
O'Fallon, MO 63366

ENGINEERING
PLANNING
SURVEYING
221 Point View Blvd.
St. Charles, MO 63301
636-928-5562
FAX 928-1713

DISCLAIMER OF RESPONSIBILITY
I hereby specify that the documents intended to be authorized by my seal are limited to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments resting or intended to be used for any part or parts of the architectural or engineering project or survey.

Larry D. Walker
CIVIL ENGINEER
2007020343
Copyright 2025
Box Engineering Company, Inc.
Authority No. 000655
All Rights Reserved

REVISIONS	
10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS


Developer / Owner:
Mark Steiniger
854 Long Star Drive
O'Fallon, MO 63366
(636) 978-3478

P+Z No. 25-008321
Approved: 09-04-2025

City No.
GR25-000007

Page No.
10 of 11


GRADING PLAN



PROJECT TITLE:

**ENGINEERING
PLANNING
SURVEYING**

■ 221 Point West Blvd.
St. Charles, MO 63301
636-928-5552
FAX 928-1718



STATE OF MISSOURI
 LARRY DAVID WALKER
 NUMBER
 PE-2007-020343
 PROFESSIONAL ENGINEER
 11/05/25

REVISIONS	
10-21-25	CITY COMMENTS
11-05-25	CITY COMMENTS

Developer / Owner:

Mark Steiniger
854 Long Star Drive
O'Fallon, MO 63366
(636) 978-3478

GRADING PLAN

P+Z No. 25-008321
Approved: 09-04-2025

City No. GR25-000007

Page No.

11 of 11