John Shively PE

Name	F <sub>hor</sub>	App.Pt.	F <sub>vert</sub>	App.Pt.	Design
	[lbf/ft]	z [ft]	[lbf/ft]	x [ft]	coefficient
Active pressure	692.2	-2.01	530.3	3.05	1.000

#### Verification of block No. 1

### Check for overturning stability

Resisting moment  $M_{res} = 4786.1$  lbfft/ft Overturning moment  $M_{ovr} = 1387.2$  lbfft/ft

Safety factor = 3.45 > 1.50

Joint for overturning stability is SATISFACTORY

#### Check for slip

Resisting horizontal force  $H_{res} = 1456.59$  lbf/ft Active horizontal force  $H_{act} = 684.43$  lbf/ft

Safety factor = 2.13 > 1.50

Joint for verification is SATISFACTORY

# Bearing capacity of foundation soil (Stage of construction 1)

Design load acting at the center of footing bottom

	No.	Moment	Norm. force	Shear Force	Eccentricity	Stress
	NO.	[lbfft/ft]	[lbf/ft]	[lbf/ft]	[-]	[psf]
	1	752.5	3396.37	767.97	0.052	892.2

Service load acting at the center of footing bottom

No.	Moment	Norm. force	Shear Force	
NO.	[lbfft/ft]	[lbf/ft]	[lbf/ft]	
1	752.5	3396.37	767.97	

# Verification of foundation soil

Stress in the footing bottom: rectangle

### **Eccentricity verification**

Max. eccentricity of normal force e = 0.052Maximum allowable eccentricity  $e_{alw} = 0.333$ 

# **Eccentricity of the normal force is SATISFACTORY**

#### Verification of bearing capacity

Max. stress at footing bottom  $\sigma = 892.2 \text{ psf}$ Bearing capacity of foundation soil  $R_d = 6000.0 \text{ psf}$ 

Safety factor = 6.73 > 2.00

Bearing capacity of foundation soil is SATISFACTORY

Overall verification - bearing capacity of found. soil is SATISFACTORY