

CLUSTER BOX UNIT (CBU) -ANCHORING METHODS-

CBU's must be level and mounted firmly in concrete, using one of the following

- 1. The J-bolt method is the preferred method of installation of CBU's on concrete pads; however, the J-bolt pattern must be accurate with the CBU pedestal plate. When using J-bolts, in order to prevent any damage or accidents that could result from the exposed bolts, consideration should be given as to the time lapse between pouring the concrete and the actual installation. Expansion anchors must be installed in accordance with the manufacturer's instructions.
- 2. The use of anchor bolts for the installation of CBU's on concrete pads is also acceptable as long as the methods described below are followed.
- a. Hilti Kwik bolt II, 1/2" diameter X 5-1/2" overall length Catalog Number: 000-453-696, KB II 12-512 Stainless Steel Catalog Number: 000-454-744 Minimum embedment in concrete must be no less than 3-1/2"
- b. ITW Ramset Redhead Trublot, galvanized, 1/2" diameter X 7" overall length
- c. Rawl Stud, 1/2" diameter X 5 1/2" overall length, galvanized. Catalog Number: 7324 Minimum embedment in concrete must be no less than 4"

CLUSTER BOX UNIT (CBU) -CONCRETE PAD REQUIREMENTS-


- ALL FREE STANDING PADS MUST BE 8" THICK -

4' X 4' SINGLE PAD 4' X 7' 2 UNITS DOUBLE PAD 4' X 10' 3 UNITS TRIPLE PAD 4' X 13' QUAD PAD 4 UNITS

WHEN PLACING A PARCEL LOCKER AT ANY CBU LOCATION, INCREASE THE PAD SIZE BY AN ADDITIONAL 4' X 4'***

POSTAL SERVICE DETAILS
FOR MULTI-UNIT CBU PLACEMENT

ENGINEERS SEAL DOES NOT APPLY TO USPS DETAILS ON THIS SHEET.





CONSTRUCTION SPECIFICATIONS

- 1. Stone Size Use 2" stone, or reclaimed or recycled concrete equivalent.
- 2. Length As required, but not less than 50 feet (except on a single residence lot where a 30 foot minimum length would apply).
- 3. Thickness Not less than six (6) inches.
- 4. Width Twenty (20) foot minimum, but not less than the full width at points where ingress or egress
- 5. Filter Cloth Will be placed over the entire area prior to placing of stone. Filter will not be required on a single family residence lot.
- 6. Surface Water All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted.
- 7. Maintenance The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights—of—way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights—of—way must be removed immediately.
- 8. Washing Wheels shall be cleaned to remove sediment prior to entrance onto public rights—of—way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
- 9. Periodic inspection and needed maintenance shall be provided after each rain.

STABILIZED CONSTRUCTION ENTRANCE/WASHDOWN AREA

NOT TO SCALE





 The use of High Density Polyethylene Corrugated pipe A.D.S. N12 or Equal will be permitted
as an acceptable alternative to reinforced concrete pipe. Pipe shall meet A.S.T.M. D-2321 and
AASHTO M-294-921. Concrete flared end sections and inlet structures shall be required. Pipe
must have smooth interior wall and is not to be used inside the Public Right-of-Way. All concrete pipe or HDPE pipe shall be installed with o—ring rubber type gaskets per M.S.D. Standard Construction Specifications or Manufacturer. 2. In typical conditions the minimum trench width is determined by the size of the pipe and the ability to get compaction equipment between the pipe and the trench walls. The minimum trench width should not be less than the outside diameter plus 16 inches or the pipe outside diameter times 1.25 plus 12 inches; whichever is greater. High speed trenchers may enable satisfactory installation of pipe in narrower trenches. Poor insitu soil conditions such as peat, muck, running sands, or expansive clays will require substantially wider backfill as well as deeper foundation and bedding. Trench width and foundation depth should be based on a thorough site investigation.

SODDED SWALE

TYPICAL SWALE

EXCAVATED TRENCH WIDTH


3:1 SLOPE

3:1 SLOPE

-FINAL BACKFILL


3. Backfill in the area up to the springline should be carefully placed and compacted to achieve a minimum E value of 1,000 psi as detailed in ASTM D2321. A minimum of 12" of backfill should be placed and compacted above the crown of the pipe. It is typical for trenches to be backfilled entirely with Type I or Type II materials when under pavement. 4. Flexible pipe should never be installed in a concrete cradle, as done for rigid pipe in a Class A installation. This type of installation could create concentrated forces at the ends of the cradle when the pipe has deformed.

H.D.P.E. PIPE DETAIL



MODULAR BLOCK CONCRETE RETAINING WALL (RETAINING WALL DESIGN BY OTHERS) NOT TO SCALE


* WALL DESIGN TO TAKE INTO ACCOUNT ANY LOADING OR IMPACT THE PROPOSED FENCE WILL HAVE ON SAID WALL.




" THICK ASPHALT TYPE "C" SURFACE MIX 4" COMPACTED TYPE 1 AGGREGATE BASE-

ASPHALT TRAIL DETAIL

NOT TO SCALE NOTE: THE ASPHALT SURFACE SHALL BE COMPACTED TO 98% MAXIMUM DENSITY.



ALL NON-REINFORCED CONCRETE SHALL BE 4,000 P.S.I. AT 28 DAYS.



ON THE X AND Y AXIS

PLAN VIEW OF A DETECTABLE WARNING SURFACE SHOWING DOMES ALIGNED IN ROWS, NOT SKEWED DIAGONALLY.

> TYPICAL DETAIL OF DETECTABLE WARNING SURFACE NOT TO SCALE

> > EXPANSION JOINT - WIDTH VARIES (20'-0" MAX. o.c.)

CONSTRUCTION JOINT - WIDTH BETWEEN JOINTS

SEE PLANS FOR WIDTH

* ALL GRANULAR ROLLED STONE BASE UNDER PROPOSED CONCRETE MUST BE COMPACTED TO 100% OF THE MAXIMUM DENSITY AS DETERMINED BY THE STANDARD PROCTOR TEST AASHTO T-99.

CONCRETE SIDEWALK DETAIL

7" NON-REINFORCED P.C. CONCRETE PAVEMENT

4" AGGREGATE BASE

CONCRETE PAVEMENT DETAIL

IN RIGHT-OF-WAY OF

KEATON CORPORATE PKWY

NOT TO SCALE

NOT TO SCALE

2" ROLLED STONE BASE

4" P.C. CONCRETE -

EQUALS SIDEWALK WIDTH

___ 4" P.C. CONCRETE

PREPARED SUBGRADE

PLAN AND SECTION VIEWS OF DETECTABLE WARNING DOMES AND THEIR RELATIVE SPACING

NO O

ISCLAIMER OF RESPONSIBILITY hereby specify that the documents intended to be authenticated by my seal are limited to this sheet, and I hereby disclaim any responsibility for all other Drawings, Specifications, Estimates, Reports or other documents or instruments relating to or intended to be used for any part or parts of the architectural or ngineering project or surv



Bax Engineering Company, Inc. Engineering Authority No. 000655 Surveying Authority No. 000144

All Rights Reserved		
REVISIONS		
02,	/20/17	CITY COMMENTS
03,	/17/17	CITY COMMENTS
09,	/20/18	CITY COMMENTS
11/	/ 06/18	CITY COMMENTS
12,	/14/18	CITY COMMENTS
12,	/28/18	CITY COMMENTS
06,	/11/21	CLIENT COMMENTS
03,	/01/22	CITY COMMENTS

S

ONSTRUC

Ó

P+Z No.₁₈₋₀₀₃₉₈₆ June 7, 2018

City No._{#18-009384} Permit #RSP18-000006

Page No.

31A of