SUMMARY OF QUANTITIES

JSP	ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
	2013000	CLEARING AND GRUBBING	LS	1
	2022010	REMOVAL OF IMPROVEMENTS	LS	1
	2035000	UNCLASSIFIED EXCAVATION	CUYD	10464
	2035500	EMBANKMENT IN PLACE	CUYD	1863
	2036000	COMPACTING EMBANKMENT	CUYD	7848
	2037075	COMPACTING IN CUT	STA	7.8
X	2039901{1}	UTILITY POTHOLING JSP	LS	1
	2063100	CLASS 3 EXCAVATION IN ROCK	CUYD	533
X	3049905{1}	MODIFIED TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	SQYD	2348
X	3049905{2}	MODIFIED TYPE 5 AGGREGATE FOR BASE (5 IN. THICK)	SQYD	10484
	4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	TONS	34.8
	5021308	CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS)	SQYD	9104.1
X	5029905{1}	8 IN. CONCRETE TRUCK APRON (STAMPED AND COLORED)	SQYD	303.3
X	6039922{1}	RECONSTRUCT MANHOLE AND ADJUST TO GRADE	EA	5
X	6039923{1}	REMOVE AND REPLACE 8 IN. DUCTILE IRON PIPE W/ENCASEMENT	LF	60
X	6049902{1}	CONVERT AREA INLET TO MANHOLE AND ADJUST TO GRADE	EA	1
	6061060	MGS GUARDRAIL	LF	400
	6061080	MGS END ANCHOR	EA	1
	6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	EA	1
	6071060	PEDESTRIAN FENCE (STRUCTURES)	LF	186
X	6079902{1}	REMOVE AND RELOCATE PROPERTY FENCE	LF	389
	6081012	TRUNCATED DOMES	SQFT	120
X	6083006	6 IN. CONCRETE MEDIAN STRIP	SQYD	311.5
	6085008	PAVED APPROACH, 8 IN.	SQYD	589.2
	6086004	CONCRETE SIDEWALK, 4 IN.	SQYD	1995.1
	6086008	CONCRETE SIDEWALK, 8 IN.	SQYD	52.9
X	6089902{1}	ADA CURB RAMP	EA	16
	6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	LF	20

SUMMARY OF QUANTITIES

JSP	PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY
	6092011	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	LF	3387
	6092021	INTEGRAL CURB (OVER 6 IN. HEIGHT) TYPE A	LF	182
X	6099903{1}	MODIFIED INTEGRAL CURB (3 IN. HEIGHT) TYPE M	LF	264
	6113020	FURNISHING TYPE 2 ROCK BLANKET	CUYD	1191
	6113040	PLACING TYPE 2 ROCK BLANKET	CUYD	1191
	6161005	CONSTRUCTION SIGNS	SQFT	284
	6161030	TYPE III MOVEABLE BARRICADE	EA	20
	6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	EA	4
	6173103	CONCRETE TRAFFIC BARRIER, TYPE D (MOMENT SLAB)	LF	60
	6181000	MOBILIZATION	LS	1
	6200012	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE	LF	74
	6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	EA	6
	6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	EA	25
	6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	EA	36
	6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	LF	898
	6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	LF	5532
	6206125A	24 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	LF	47
	6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	SQYD	91
	6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	SQYD	1785
	6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	LS	1
X	7209904{1}	LARGE BLOCK RETAINING WALL	SQFT	2033
X	7261015	15 IN. RCP	LF	1729
X	7319902{1}	PRECAST CONCRETE SINGLE CURB INLET	EA	11
X	7319902{2}	PRECAST CONCRETE DOUBLE CURB INLET	EA	5
X	7319902{3}	PRECAST CONCRETE MANHOLE - 42 IN.	EA	1
X	7319902{4}	PRECAST CONCRETE SINGLE DROP INLET W/SIDE INTAKE	EA	1
X	7319902{5}	REMOVE AND REPLACE SINGLE CURB INLET W/DOUBLE CURB INLET	EA	2
X	7320615A	15 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	EA	2

STATE OF MISSOURI
BENTLEY M. GEDRIS
NUMBER PE-2010017818
PROFESSIONAL ENGINEER

DATE PREPARED
8/14/2024

DISTRICT	STATE
SL	MO

SHEET NO.
3

ROUTE
WELDON SPRING

OA JOB NO.
221150

EW GATEWAY ID.
7209-22

PROJECT NO.
CMAQ-7302(691)

BRIDGE NO.
N/A

DESCRIPTION	DATE

OATES
ST. LOUIS
720 Olive - Suite 700
St. Louis, MO 63101
tel 314-588-8331

MISSOURI DESIGN FIRM
LICENSE NO. 001166

MISSOURI LAND SURVEY CORP
LICENSE NO. 2006270

CITY OF O'FALLON
ENGINEERING DEPARTMENT
100 NORTH MAIN STREET
O'FALLON, MO 63366
tel 636.379.5596

SUMMARY OF QUANTITIES
SHEET 1 OF 7

REV.

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.