



NOTES:
 DAM TO BE COMPACTED TO 87% MODIFIED PROCTOR.
 LS ENGINEER TO TAKE SOIL TESTS TO VERIFY COMPACTION.
 DAM TO BE FINISH GRADED, FERTILIZED, AND SEEDED
 WITH RED FESCUE AFTER COMPLETION OF ROUGH GRADING.

