




TYPICAL PAVEMENT DETAIL
 NOT TO SCALE




HANDICAPPED RAMP DETAIL
 NOT TO SCALE




TYPICAL LOT RESUBDIVISION
 NOT TO SCALE




INTEGRAL VERTICAL CURB
INTEGRAL ROLLED CURB
INTEGRAL CURB PAVEMENT TYPICAL SECTIONS AND DETAILS




CONCRETE SIDEWALK DETAIL
 NOT TO SCALE




ASPHALT TRAIL
 NOT TO SCALE




PLAN OF JOINT LOCATION
 N.T.S.



CUL-DE-SAC OPEN CENTER
 N.T.S.
CUL-DE-SAC FULLY PAVED
 N.T.S.




RIP RAP UNDERLAIN WITH WOVEN GEOTEXTILE FABRIC
 N.T.S.




H.D.P.E. PIPE DETAIL


- The use of High Density Polyethylene Corrugated pipe A.D.S. N12 or Equal will be permitted as an acceptable alternative to reinforced concrete pipe. Pipe shall meet A.S.T.M. D-2321 and AASHTO M-294-921. Concrete flared end sections and inlet structures shall be required. Pipe must have smooth interior wall and is not to be used inside the Public Right-of-Way.
- In typical conditions the minimum trench width is determined by the size of the pipe and the ability to get compaction equipment between the pipe and the trench walls. The minimum trench width should not be less than the outside diameter plus 18 inches or the pipe outside diameter times 1.25 plus 12 inches, whichever is greater. High speed trenchers may enable satisfactory installation of pipe in narrower trenches. Poor insitu soil conditions such as peat, muck, running sands, or expansive clays will require substantially wider backfill as well as deeper foundation and bedding. Trench width and foundation depth should be based on a thorough site investigation.
- Backfill in the area up to the springline should be carefully placed and compacted to achieve a minimum E value of 1,000 psi as detailed in ASTM D2321. A minimum of 12\"/>




TYPE "A" EXPANSION JOINT




TYPE "A" ALTERNATE EXPANSION JOINT




TYPE "B" LONGITUDINAL CONSTRUCTION JOINT




TYPE "C" SAWED OR PREMOLDED STRIP LONGITUDINAL OR TRANSVERSE




TYPE "D" TRANSVERSE CONSTRUCTION JOINT




TYPE "E" TIED TRANSVERSE CONSTRUCTION JOINT



MANHOLE BOXING
 N.T.S.



INTEGRAL CURB DETAIL "B" AT DRIVEWAYS
 N.T.S.



INLET JOINT
 N.T.S.
SECTION A-A
 N.T.S.

- NOTES**
- ALL CATCH BASINS SHALL BE SEPARATED FROM THE PAVEMENT AND CURB BY EXPANSION JOINT MATERIAL EXTENDING COMPLETELY THROUGH CURB AND SLAB. MANHOLE CASTINGS WITHIN THE PAVEMENT LIMITS SHALL BE BOXED IN AS SHOWN.
 - WHEN A JOINT FALLS WITHIN 5 FEET OF OR CONTACTS BASIN, MANHOLES OR OTHER STRUCTURES, SHORTEN ONE OR MORE PANELS EITHER SIDE OF OPENING TO PERMIT JOINT TO FALL ON ROUND STRUCTURES AND AT OR BETWEEN CORNERS OF RECTANGULAR STRUCTURES.
 - T = 6\"/>