



WATER MAIN INSTALLATION NOTES

1. All fire hydrants shall be 5 feet behind back of curb.
2. Proposed water main shall be installed and then connected to existing water main by wet tap so as not to disrupt the water service to the Copperfield Subdivision. Existing water main to be abandoned shall then be removed during grading and excavating operations. All hydrants and valve boxes shall be removed and saved for future City of O'Fallon use.
3. For typical installation details, see sheet 20 of 20.

