Mercedes-Benz Dealership at Weldon Point S\@ave Automotive

A TRACT OF LAND IN U.S. SURVEY 1796, TOWNSHIP 46 NORTH, RANGE 3 EAST OF THE 5TH PRINCIPAL MERIDIAN LOCATED IN CITIES OF O'FALLON AND WELDON SPRING, ST. CHARLES COUNTY, MISSOURI

SITE IMPROVEMENT PLANS

LEGEND


EXISTING CONTOURS	450
PROPOSED CONTOURS	450
EXISTING SEWER	=======================================
PROP. STORM SEWER	
PROP. SANITARY SEWER	
WATER MAIN	—— w ——— w ——
GAS MAIN	——— G ————— G ————————————————————————
ELECTRIC	—— E ——— E ——
OVERHEAD WIRES	—— ОН ——— ОН ———
CENTERLINE	
EASEMENT	
RAILROAD	
CONCRETE PAVEMENT	
EXISTING TREES	(12 ¹¹)
EXISTING SPOT ELEVATION	* ************************************
PROPOSED SPOT ELEVATION	+_120.10
SWALE	
TO BE ABANDONED	T.B.A.
TO BE REMOVED	T.B.R.
TO BE REMOVED & REPLACED	T.B.R. & R.
TO BE USED IN PLACE	U.I.P.
BACK OF CURB	B.C.
FACE OF CURB	F.C.
ADJUST TO GRADE	A.T.G.
FIRE HYDRANT	***
POWER POLE	Q
TRAFFIC FLOW	-
SOIL BORINGS	⊕ B−1
EXPLORER PIPELINE GAS MAIN	———— GAS ———

RECEIVED OCT 2 1 2005 BUILDING DEPT.

PREPARED FOR:

Seave Automotive

3400 EAST LAFAYETTE DETROIT, MICHIGAN 48207 Phone 313.567.5759 Fax: 313.567.5763



LOCATION MAP

PERTINENT DATA

MDNR PERMIT NO: MO-R107683

EXISTING ZONING: PC - PLANNED COMMERCIAL OTC - OLD TOWN COMMERCIAL OVERLAY DISTRICT

FIRE DISTRICT

SITE ACREAGE:

6.37 ACRES ±

951 TECHNOLOGY DRIVE SITE ADDRESS:

UTILITIES:

WATER SERVICE MISSOURI AMERICAN WATER CO. 535 NORTH NEW BALLAS ROAD ST. LOUIS, MO 63141 PH. 314-996-2286 CONTACT: BENJAMIN P. FREESE, P.E. COTTLEVILLE OFFICE P.O. BOX 355 COTTLEVILLE, MO 63338 PH. 636-922-9164

CONTACT: TOM ARREN/PEGGY SPELLZZA SEWER DISTRICT DUCKETT CREEK SEWER DISTRICT 3550 HIGHWAY K O'FALLON, MO 63368-8616 PH. 636-441-1244 FAX 636-498-8150

CONTACT: MIKE O'BRIEN PHONE SERVICE SOUTHWESTERN BELL TELE. 402 N. 3rd. STREET ST. CHARLES, MO 63301 PH. 1-949-1320 CONTACT: DEBBIE ESTES

MoDOT REVIEW OFFICE 6780 OLD HIGHWAY "N" 402 N. 3rd. STREET ST. CHARLES, MO 63304 CONTACT: MR. SCOTTY D. WARD

P.O. BOX 385 1385 MOTHERHEAD ROAD COTTLEVILLE, MO 63338 CONTACT: MARK BOEHLE ELECTRIC SERVICE AMERENUE - WENTZVILLE DISTRICT 200 CALLAHAN ROAD WENTZVILLE, MO 63385 PH. 636-639-8307 CONTACT: SUREN MEHTA

COTTLEVILLE FIRE PROTECTION DIST.

GAS SERVICE LACLEDE GAS 1999 TRADE CENTER EAST ST. PETERS, MO 63376 PH. 636-978-2663 x103 CONTACT: MIKE LANGAN

EXPLORER PIPELINE PO BOX 2650 TULSA OK 74101-2650 PH. 918-493-5172 CONTACT: PATRICK NWAKOBY 1355 ROBBINS ROAD HARTFORD IL 62048 PH. 618-251-0262

CONTACT: RICK THOMPSON

as noted

SERVICES PROVIDED BY OTHERS TO IMPLEMENT THE

IMPROVEMENTS SHOWN ON THIS PLAN AND ALL OTHER

DRAWINGS WHERE THE UNDERSIGNED ENGINEER'S SEAL

APPEARS. THE CONSTRUCTION MEANS AND METHODS AF

STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. H

NO RESPONSIBILITY TO VERIFY FINAL IMPROVEMENTS AS

AUTHORIZED TO DO SO BY THE OWNER OR CONTRACTOR,

DESCRIPTION: BOTH THE STATION AND THE AZIMUTH MARK ARE STANDARD MO DNR ALUMINUM GRS DISK. THE STATION IS STAMPED "SC-18, 1999". THE AZIMUTH IS STAMPED "SC-12, 1990". BOTH DISKS ARE SET IN 12 INCH DIAMETER BY 30 INCH DEEP CONCRETE MONUMENTS FLUSH WITH THE GROUND

STATION, AZIMUTH MARKS AND REFERENCE TIES: THE STATION IS LOCATED AT THE AUGUST A. BUSCH WILDLIFE AREA, IT IS IN THE GRASSY AREA WEST OF THE PAVED PARKING LOT FOR THE MAIN BUILDING OF THE BUSCH WILDLIFE AREA. THE STATION IS 24 FT. SOUTH OF THE CENTER OF THE ENTRANCE ROAD; 18 FT. WEST OF THE SERVICE DRIVE TO THE BACK OF THE BUILDING:

THE AZIMUTH MARK IS ABOUT 0.25 MILES WEST OF THE STATION AND NEAR THE SOUTHEAST CORNER OF THE PARKING LOT FOR THE AHDEN KNIGHT HAMPTON MEMORIAL LAKE. IT IS 89.0 FT. SOUTHWEST OF THE NORTHWEST CORNER POST OF A RAIL FENCE AROUND THE PARKING LOT: 46.2 FEET NORTHWEST OF A RAIL FENCE POST.

TITLE SHEET

INDEX

C1.0 SPECIFICATIONS SHEET C3.0 EXISTING CONDITIONS PLAN C4.0,C4.1 SITE AND GRADING PLANS C5.0, C5.1 SITE GEOMETRICS/PAVEMENT DETAILS C6.0,C6.1,C6.2 STORM SEWER PROFILES/DETAILS

C7.0,C7.1,C7.2 SANITARY SEWER PROFILES / DETAILS EROSION CONTROL PLAN C8.0 DRAINAGE AREA PLAN

CONTRACTOR NOTE:

THE CONTRACTOR SHALL ASSUME COMPLETE RESPONSIBILITY FOR CONTROLLING ALL SILTATION AND EROSION OF THE PROJECT AREA. THE CONTRACTOR SHALL USE WHATEVER MEANS NECESSARY TO CONTROL EROSION AND SILTATION INCLUDING, BUT NOT LIMITED TO. STAKED STRAW BALES AND/OR SILTATION FABRIC FENCES (POSSIBLE METHODS OF CONTROL ARE DETAILED IN THE PLAN). CONTROL SHALL COMMENCE WITH GRADING AND BE MAINTAINED THROUGHOUT THE PROJECT UNTIL ACCEPTANCE OF THE WORK BY THE OWNER AND/OR THE CITY OF WELDON SPRING AND/OR MODOT. THE CONTRACTOR'S RESPONSIBILITIES INCLUDE ALL DEIGN AND IMPLEMENTATION AS REQUIRED TO PREVENT EROSION AND THE DEPOSITING OF SILT. THE OWNER AND/OR THE CITY OF WELDON SPRING AND/OR MODOT MAY AT THEIR OPTION DIRECT THE CONTRACTOR IN HIS METHODS AS DEEMED FIT TO PROTECT PROPERTY AND IMPROVEMENTS. ANY DEPOSITING OF SILT OR MUD ON NEW OR EXISTING PAVEMENT SHALL BE REMOVED IMMEDIATELY. ANY DEPOSITING OF SILT OR MUD IN NEW OR EXISTING STORM SEWERS OR SWALES SHALL BE REMOVED AFTER EACH RAIN AND AFFECTED AREAS CLEANED TO THE SATISFACTION OF THE OWNER AND/OR THE CITY OF WELDON SPRING AND/OR MODOT.

OWNER NOTE:

ONCE THE CONTRACTOR DELIVERS THE PROPERTY TO THE OWNER, THE OWNER SHALL BE RESPONSIBLE TO MAINTAIN ANY CONTROL MEASURE THAT IS TO REMAIN AS A PERMANENT STRUCTURE TO CONTROL SILTATION AND EROSION.


UTILITY NOTE:

UNDERGROUND FACILITIES, STRUCTURES AND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS, RECORDS AND INFORMATION, AND, THEREFORE DO NOT NECESSARILY REFLECT THE ACTUAL EXISTENCE, NON-EXISTENCE, SIZE, TYPE, NUMBER, OR LOCATION OF THESE FACILITIES. STRUCTURES AND UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE ACTUAL LOCATION OF ALL UNDERGROUND FACILITIES, STRUCTURES, AND UTILITIES, EITHER SHOWN OR NOT SHOWN ON THESE PLANS. THE UNDERGROUND FACILITIES, STRUCTURES, AND UTILITIES SHALL BE LOCATED IN THE FIELD PRIOR TO ANY GRADING, EXCAVATION OR CONSTRUCTION OF IMPROVEMENTS. THESE PROVISIONS SHALL IN NO WAY ABSOLVE ANY PARTY FROM COMPLYING WITH THE UNDERGROUND FACILITY SAFETY AND DAMAGE PREVENTION ACT, CHAPTER 319 RSMo.

10/20/05 - REVISED PER REVIEW COMMENTS 10/07/05 - REVISED PER REVIEW/CLIENT COMMENTS 1 9/27/05 - REVISED PER MODOT COMMENTS

SOAVE AUTOMOTIVE @ WELDON POINT

TITLE SHEET



UTILITY LOCATES

MISSOURI ONE-CALL

CITY OF O'FALLON

MODOT

1 800 344-7483

(314) 340-4100

(636) 281-2858

257 Chesterfield Business Parkway PH. (636) 530-9100 FAX (636) 530-9130 e-mail: general@stockassoc.com Web: www.stockassoc.com

10/20/05 DRAWN BY: T.P.S. 08/22/05 G.M.S.

File

EROSION AND SEDIMENT CONTROL NOTES

- Installation of perimeter sediment control shall be implemented as the first step of grading and within seven (7) days of grubbing
- Inspection of siltation control devices shall take place once every seven days and within 24 hours of any 0.5"/24 hour rain event. Any siltation control in need of repair shall occur
- 3. Any disturbed areas which will remain unworked for 14 days or more shall be stabilized with seeding and mulching per specifications within 7 days. If seasonal conditions prohibit seeding, mulching or matting shall be used.
- 4. All slopes or drainage channels, once constructed to final grade, shall be seeded and mulched per specifications within
- 5. Silt fences shall be installed immediately around each storm sewer structure once final construction of each individual structure is complete.
- 6. All siltation control devices shall remain in place until upslope areas have been permanently stabilized.
- 7. The Contractor shall assume complete responsibility for controlling all siltation and erosion of the project area. The Contractor shall use whatever means necessary to control erosion and siltation including, but not limited to, staked straw bales and/or siltation fabric fences (possible methods of control are detailed in the plan). Control shall commence with grading and be maintained throughout the project until acceptance of the work by the Owner and/or the City of Weldon Spring and/or MoDOT. The Contractor's responsibilities include all design and implementation as required to prevent erosion and the depositing of silt. The Owner and/or the City of Weldon Spring and/or MoDOT may at their option direct the Contractor in his methods as deemed fit to protect property and improvements. Any depositing of silts or mud on new or existing pavement or in new or existing storm sewers or swales shall be removed after each rain and affected areas cleaned to the satisfaction of the Owner and/or the City of Weldon Spring and/or MoDOT." Owner shall be responsible for structure to remain as permanent after construction is complete.
- Erosion control shall not be limited to what is shown on the plan. Whatever means necessary shall be taken to prevent siltation and erosion from entering natural streams and adjacent roadways, properties, and ditches.
- When deemed necessary, positive steps should be exercised to prevent this soil from damaging adjacent property and silting up all storm drainage systems whether on or off site.

Siltation Control Schedule Implementation Perimeter siltation control and construction entrances to be

- 2. Begin placing aggregate base in parking areas once area has reached final grade to prevent erosion
- 3. Place silt fence around each storm sewer structure as it is completed.
- 4. Immediately seed areas upon reaching final grade that are to
- be permanently seeded. Temporary Access Roads and Parking Areas Specifications
- Temporary roads shall follow the contour of the natural terrain to the extent possible. Slopes should not exceed 10
- 2. Grades should be sufficient to provide drainage, but should not exceed 10 percent.
- Roadbeds shall be at least 24 feet wide.
- 4. All cuts and fills shall be 3:1 or flatter to the extent
- Drainage ditches shall be provided as needed.
- 6. The roadbed or parking surface shall be cleared of all vegetation, roots and other objectionable material.
- A 10—inch course of 2" MINUS aggregate shall be applied immediately after grading or the completion of utility installation within the right-of-way. Filter fabric may be applied to the roadbed for additional stability in accordance with fabric manufacturer's specifications.

Vegetation

All roadside ditches, cuts, fills and disturbed areas adjacent to parking areas and roads shall be stabilized with appropriate temporary or permanent vegetation according to the applicable standards and specifications.

Maintenance

Both temporary and permanent roads and parking areas may require periodic top dressing with new gravel. Seeded areas adjacent to the roads and parking areas should be checked periodically to ensure that a vigorous stand of vegetation is maintained. Roadside ditches and other drainage structures should be checked regularly to ensure that they do not become clogged with silt or other

All erosion control systems shall be inspected and necessary corrections made within 24 hours of any rainstorm resulting in 1/2 inch of rain

Straw Bale Siltation Control Specifications

- Sheet Flow Applications 1. Bales shall be placed in a single row, lengthwise on the
- 2. All bales shall be either wire—bound or string—tied. Straw bales shall be installed so that buildings are oriented around the sides rather than along the tops and bottoms of the bales (in order to prevent deterioration of the bindings). See

contour, with both ends of adjacent bales tightly abutting one

- 3. The barrier shall be entrenched and backfilled. A trench shall be excavated the width of a bale and the length of the proposed barrier to a minimum depth of 4 inches. After the bales are staked and chinked, the excavated soil shall be backfilled against the barrier. Backfill soil shall conform to the ground level on the downhill and shall be built up to 4 inches against the uphill side of the barrier (See detail this sheet).
- 4. Each bale shall be securely anchored by at least two stakes or rebars driven through the bale. The first stake in each bale shall be driven toward the previously laid bale to force the bales together. Stakes or rebars shall be driven deep enough into the ground to securely anchor the bales.
- 5. The gaps between bales shall be chinked (filled by wedging) with straw to prevent water from escapina between the bales. (Loose straw scattered over the area immediately uphill from

a straw bale barrier tends to increase barrier efficiency).

- 6. Inspection shall be frequent and repair or replacement shall be made promptly as needed.
- Straw bale barriers shall be removed when they have served their usefulness, but not before the upslope areas have been permanently stabilized.

Channel Flow Applications

- 1. Bales shall be placed in a single row, lengthwise, oriented perpendicular to the contour, with ends of adjacent bales tightiv abutting one another.
- 2. The remaining steps for installing a straw bale barrier for sheet flow applications apply here, with the following
- 3. The barrier shall be extended to such a length that the bottoms of the end bales are higher in elevation than the top of the lowest middle bale (see detail) to assure that sedimentladen runoff will flow either through or over the barrier but not around it.

Maintenance

- 1. Straw bale barriers shall be inspected immediately after each rainfall and at least daily during prolonged rainfall.
- 2. Close attention shall be paid to the repair of damaged fence, end runs and undercutting beneath fence.
- 3. Necessary repairs to barriers or replacement of silt fence shall be accomplished promptly.
- 4. Sediment deposits should be removed after each rainfall. They must be removed when the level of deposition reaches approximately one—half the height of the barrier.
- 5. Any sediment deposits remaining in place after the straw bale barrier is no longer required shall be dressed to conform to the existing grade, prepared and seeded.
- Silt Fence Specifications 1. Silt Fence to be woven geotextile fabric Mirafi 100X or equal.
- 2. Fabric to be supported by metal tee post with spade base spaced on 5' centers with 6 x 6/10 x 10 gage welded wire fence. See detail this sheet.
- 3. Fabric shall be entrenched and backfilled. A trench shall be excavated a minimum of 6 inches deep for the length of the fence. The excavated soil shall be backfilled against the fence. See detail this sheet.
- 4. Fence height shall be a minimum of 4 feet in height, with the fabric installed on the fence on the upstream side.
- 5. Silt fences shall be used only on sheet flow conditions.
- 6. Silt fences shall be installed around all storm sewer structures.

Maintenance

- 1. Silt fence barriers shall be inspected immediately after each rainfall and at least daily during prolonged rainfall.
- 2. Close attention shall be paid to the repair of damaged bales, end runs and undercutting beneath bales.
- 3. Necessary repairs to barriers or replacement of bales shall be accomplished promptly.
- 4. Sediment deposits should be removed after each rainfall. They must be removed when the level of deposition reaches approximately one—half the height of the barrier.
- 5. Any sediment deposits remaining in place after the silt fence barrier is no longer required shall be dressed to conform to the existing grade, prepared and seeded.

GENERAL NOTES

- 1. BOUNDARY AND TOPOGRAPHIC SURVEY BY STOCK & ASSOCIATES
- 2. ALL UTILITIES SHOWN HAVE BEEN LOCATED BY SURVEY AND RECORD INFORMATION. THEIR LOCATION SHOULD BE CONSIDERED APPROXIMATE. THE CONTRACTOR HAS THE RESPONSIBILITY TO NOTIFY ALL UTILITY COMPANIES, PRIOR TO CONSTRUCTION, TO HAVE EXISTING UTILITIES FIELD LOCATED.
- 3. NO SLOPE SHALL BE STEEPER THAN 3:1.
- 4. SUBJECT PROPERTY LIES WITHIN FLOOD ZONE "X" (AREAS DETERMINED TO BE OUTSIDE THE 500-YEAR FLOODPLAIN) PER THE NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP FOR S' CHARLES COUNTY, MISSOURI AND INCORPORATED AREAS. THE MAP IS IDENTIFIED AS MAP NO. 29183C0430 E, WITH A MAP REVISION DATE OF
- 5. ALL SLOPES TO BE STABILIZED IMMEDIATELY AFTER GRADING.
- 6. ALL UTILITIES SERVING SITE ARE UNDERGROUND.
- 7. ALL OUTSIDE TRASH CONTAINERS, HVAC UNITS, ELECTRIC, TELEPHONE AND GAS METERS, SATELLITE DISHES, AND ROOFTOP MECHANICAL APPARATUS SHALL BE THOROUGHLY SCREENED WITH MATERIALS AND/OR LANDSCAPING TO CONCEAL THE VISIBILITY OF SUCH ITEMS FROM THE VIEW OF RIGHTS-OF-WAY AND/OR ADJACENT PROPERTIES AS APPROVED BY THE PLANNING AND ZONING COMMISSION.
- 8. ALL CONSTRUCTION AND MATERIALS USED SHALL CONFORM TO CURRENT CITY OF WELDON SPRING STANDARDS.
- 9. SEE ARCHITECTURAL DRAWINGS FOR ALL BUILDING DIMENSIONS AND DETAILS.
- 10. HANDICAP STALL LOCATIONS ARE TO BE DETERMINED AND COORDINATED WITH THE CITY OF WELDON SPRING.
- 11. ROOF TOP MECHANICAL EQUIPMENT WILL BE PROHIBITED. THE GROUND MOUNTED MECHANICAL EQUIPMENT MUST BE FULLY SCREENED WITH LANDSCAPING OR SOLID MATERIALS.
- 12. ALL FILL PLACED UNDER PROPOSED STORM AND SANITARY SEWER, PROPOSED ROADS. AND/OR PAVED AREAS SHALLI BE COMPACTED TO 90% OF MAXIMUM DENSITY AS DETERMINED BY THE MODIFIED AASHTO T-180 COMPACTION TEST OR 95% OF MAXIMUM DENSITY AS DETERMINED BY THE STANDARD PROTOR TEST AASHTO T-99. ALL FILL PLACED IN PROPOSED ROADS SHALL BE COMPACTED FROM THE BOTTOM OF THE FILL UP, ALL TESTS SHALL BE VERIFIED BY A SOILS ENGINEER CONCURRENT WITH GRADING AND BACKFILLING OPERATIONS. "NOTE THAT THE MOISTURE CONTENT OF THE SOIL IN FILL AREAS IS TO CORRESPOND TO THE COMPACTIVE EFFORT AS DEFINED BY THE STANDARD OR MODIFIED PROCTOR TEST. OPTIMUM MOISTURE CONTENT SHALL BE DETERMINED USING THE SAME TEST THAT WAS USED FOR COMPACTION. SOIL COMPACTION CURVES SHALL BE SUBMITTED TO THE CITY OF WELDON SPRING PRIOR TO THE PLACEMENT OF FILL, PROOF ROLLING MAY BE REQUIRED TO VERIFY SOIL STABILITY AT THE DISCRETION OF THE CITY OF WELDON SPRING.
- 13. DEVELOPER MUST SUPPLY CITY CONSTRUCTION INSPECTORS WITH SOIL REPORTS PRIOR TO OR DURING SITE SOIL TESTING.
- 14. ENSURE SIDEWALKS, CURB RAMPS, RAMP AND ACCESSIBLE PARKING SPACES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CURRENT APPROVED AMERICAN WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES (ADAAG) ALONG WITH THE REQUIRED GRADES, CONSTRUCTION MATERIALS, SPECIFICATIONS AND SIGNAGE. IF ANY CONFLICT OCCURS BETWEEN THE ABOVE INFORMATION AND THE PLANS, THE ADAAG GUIDELINES SHALL TAKE PRECEDENCE AND THE CONTRACTOR PRIOR TO ANY CONSTRUCTION SHALL NOTIFY THE PROJECT ENGINEER. (ENSURE AT LEAST ONE 8' WIDE HANDICAP AISLE IS PROVIDED AND CURB RAMPS DO NOT PROJECT INTO THE HANDICAP ACCESS AISLE). ALL HANDICAP RAMPS ARE TO BE CONCRETE.
- 15. LIGHTING VALUES WILL BE REVIEWED ON SITE PRIOR TO THE FINAL OCCUPANCY INSPECTION. CORRECTIONS WILL NEED TO BE MADE IF NOT IN COMPLIANCE WITH
- 16. ALL PAVED ROADWAYS GOING ON AND OFFSITE WILL BE KEPT FREE OF DIRT, ROCKS, GRAVEL OR OTHER MATERIALS DURING CONSTRUCTION.
- 17. RIP RAP SHOWN AT FLARED ENDS WILL BE EVALUATED IN THE FIELD AFTER INSTALLATION FOR EFFECTIVENESS AND FIELD MODIFIED IF NECESSARY TO REDUCE EROSION ON AND
- 18. CONTRACTOR TO FOLLOW GEOTECHNICAL ENGINEER RECOMMENDATIONS. CONTRACTOR SHOULD FAMILIARIZE THEMSELVES WITH ALL THE GEOTECHNICAL REPORTS. CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF ANY ROCK ENCOUNTERED.
- 19. A SEPARATE SIGN PERMIT WILL BE REQUIRED FOR SIGNS.

VEGETATION ESTABLISHMENT

TILLAGE PERPARATIONS *TILL TOP 4" OF SOIL

FERTILIZER * PER SOIL TEST OR FOLLOWING TABLE:

		LBS./1	,000 S.F	-
	N	Р	K	LIME
TEMPORARY SEEDING PERMANENT	0.7	0.7 1.4	0.7 1.4	14 ENM+ 14 ENM+

+ SOIL TEST RESULTS TAKE PRECEDENCE, DUE TO HIGHLY VARIBALE SOIL ph.

150 LBS. / ACRE

SEEDING RATES TEMPORARY WHEAT OR RYE

PERMANENT FESCUES KENTUCKY BLUEGRASS/ PERENNIAL RYEGRASS FINE FESCUE SEEDING PERIODS

150 LBS. / ACRE 6 LBS / 1000 S.F. 8 LBS / 1000 S.F. MARCH 1 - JUNE 1 LISTED LEGUMES/GRASSES AUGUST 1 - OCTOBER 1 WHEAT/RYE MARCH 15 - NOVEMBER 1

SECTION B-B

Tee Post w/spade base

Existing ground

SILTATION CONTROL SILTFENCE DETAIL (n.t.s.)

Cut 6"x6" trench '

and place fabric

in ditch and backfill

GENERAL NOTES:

SHEET FLOW

(GEOTEXTILE

(WOVEN)


TYP.

1. Do not scale drawing. Follow Dimensions

SECTION A-A

- 2. Siltation Control Devices to remain in place until adequate vegetative growth insures no further erosion of the soil.
- 3. Siltation Fences shall be inspected periodically for damage and for the amount of sedimentation which has accumulated. Removal of sediment will be required when it reaches 1/2 of th height of the silitation fence.
- 4. Straw Bales shall be inspected periodically for deterioration. Bales which mave rolled or failed shall be replaced.
- 5. Attachment of Geotextile Fabric to be in accordance with the manufacturer's recommendation.

BALES OF STRAW STAKED DOWN PLAN VIEW EXISTING GROUND したオンレーイン



SECTION B-B

SILTATION CONTROL HAY BALE DETAIL (n.t.s.)

Developer must supple City construction inspectors with soil reports prior to or during site soil testing." The soil report will be required to contain the following information on soil test curves (Proctor reports) for projects within the City:

1.Maximum dry density, 2.Optimum moisture content. Maximum and minimum allowable moisture content. 4. Curve must be plotted to show density from a minimum of 90% Compaction and above as determined by the "Modified AASHTO-T 18 Compaction Test" (A.S.T.M.-D-1157) or from a

Minimum of 95% as determined by the "Standard Proctor Test ASSHTO T-99, Method C" (A.S.T.M.-D-698). Proctor type must be designated on document, 5 Curve must have at least 5 density points with moisture content and sample location listed on document. 6. Specific gravity. 7. Natural moisture

Content. 8. Liquid limit. 9. Plastic Limit. Be advised that if this information is not provided to the City's Construction Inspector the City will not allow grading or construction activities to proceed on any project

STORM SEWER NOTES

1.) ALL CONCRETE SHALL BE REINFORCED, AND CONFORM TO A.S.T.M. DESIGNATION C76-80 CLASS III UNLESS NOTED.

MATERIAL'S STANDARD PROCTOR MAXIMUM DRY DENSITY.

- 2.) ALL STORM SEWER STRUCTURES WITHIN PROJECT SITE SHALL BE DESIGNED PER METROPOLITAN ST. LOUIS SEWER DISTRICT'S "STANDARD CONSTRUCTION SPECIFICATIONS FOR SEWERS AND DRAINAGE FACILITIES".
- TYPE "C" BEDDING IS REQUIRED FOR PIPES IN ROCK.
- 4.) ALL TRENCH BACKFILLS UNDER PAVEMENT SHALL BE GRANULAR BACKFILLED. 5.) JETTING IS NOT A PERMITTED METHOD OF COMPACTION ON SEWER TRENCHES BACKFILL MUST BE SUITABLE SOILS & COMPACTED TO 95 % OF THE
- 6.) ALL CURB INLETS AND AREA INLETS TO HAVE 5/8" TRASH BAR ACROSS INLET OPENINGS.

(APPLIES TO TRENCHES THAT DO NOT REQUIRE GRANULAR BACKFILL)

7.) "O" RING PIPE TO BE USED ON ALL STORM SEWERS.

10.) PROVIDE 36" MINIMUM COVER FOR STORM SEWERS.

THE STRUCTURE OF ALL DROP STRUCTURES.

- 8.) GRANULAR BACKFILL TO BE PLACED WITH A MINIMUM OF 1'H:1'V SLOPE FROM EDGE OF PAVEMENT.
- 9.) BRICK SHALL NOT BE USED IN THE CONSTRUCTION OF STORM SEWER STRUCTURES.
- 11.) PROVIDE CONCRETE CRADLES FOR RCP AND CONCRETE ENCASEMENTS FOR HDPE
- AT CROSSING WITH SANITARY SEWER. 12.) COMPACTED ROCK BACKFILL IS REQUIRED IN THE DISTURBED GROUND AROUND
- 13.) ALL STORM SEWERS ARE TO BE CONSIDERED PRIVATE, UNLESS OTHERWISE NOTED.

14.) CONTRACTORS TO PROVIDED ALTERNATE BID FOR ADS N-12 ULTRA WT OR EQUAL

(SMOOTH INTERIOR) AASHTO TYPE "S" (N-12 ULTRA WT). 15.) JOINTS SHALL BE GASKETED O-RING TYPE PER CITY OF O'FALLON.

ALT. STORM SEWER NOTES

SPECIFICATIONS AND TECHNICAL DATA:

- Applicable specifications and installation guidelines:
- ASTM F 405, Standard Specification for Corrugated Polyethylene Pipe and Fittings.
- ASTM F 667, Standard Specification for Large Diameter corrugated Polyethylene Pipe and Fittings.
- AASHTO M252, Standard Specification for Polyethylene Corrugated Drainage Pipe.
- AASHTO M 294, Standard Specification for corrugated Polyethylene Pipe, 12" to 36" diameter.
- ASTM D 2321, Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity Flow Applications.

ADS Corrugated polyethylene pipe is a flexible conduit. When properly installed, ADS pipe has excellent compressive load bearing strength. It is suitable for use under H20 and E80 live loads, or with fill heights in excess of 50 feet. To ensure maximum performance, ADS pipe should be installed in accordance with the following recommendations:

Installation Recommendations:

- Crushed stone, gravel or compacted soil backfill material should be used as the bedding and envelope material.
- The corrugated pipe should be laid on grade, on a layer of bedding material. If native soil is used as the bedding and backfill material, it should be well compacted in six inch layers under the haunches, around the sides and above the pipe to the recommended minimum height of cover.
- Either flexible (asphalt) or rigid (concrete) pavements may be laid as part of the minimum cover requirements.
- Site conditions and availability of bedding materials often dictate the type of installation method used.
- The load bearing capability of flexible conduits is dependent on the type of backfill material used and the degree of compaction achieved. Crushed stone and gravel backfill materials typically reach a compaction level of 90-95% AASHTO standard density without compaction. When native soils are used as backfill material, a minimum compaction level of 85% is required. This is the same minimum compaction that is recommended by all drainage pipe manufacturers and can be achieved by various compaction methods.
- ADS recommends that N-12 pipe be installed in accordance with ASTM D 2321, Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity Flow Applications.

H.D.P.E. STORM SEWER NOTES:

12 INCHES AS OUTLINED HEREIN:

48" (1200mm)

- 1.) STORM SEWER PIPE DESIGNATED AS HIGH DENSITY POLYETHYLENE (H.D.P.E.) SHALL HAVE WATER TIGHT GASKETED JOINTS WITH RUBBER O-RING GASKETS MEETING ASTM F477. O-RING GASKET SHALL BE INSTALLED ON THE SPIGOT END OF PIPE
- 2.) 12" TO 36" PIPE SHALL CONFORM TO THE AASHTD M294 CLASSIFICATION "TYPE S" AND 42" TO 48" SHALL CONFORM TO AASHTO MP6-95 CLASSIFICATION "TYPE D."
- 3.) ALL PIPE JOINTS SHALL CONSIST OF BELL AND SPIGOT JOINING SYSTEM WITH THE BELL COVERING TWO PIPE CORRUGATIONS AS RECOMMENDED IN AASHTO M294. 4.) PIPE MANUFACTURED FOR THIS SPECIFICATION SHALL COMPLY WITH THE REQUIREMENTS FOR TEST METHODS, DIMENSIONS AND MARKINGS FOUND IN AASHTO DESIGNATIONS M252

AND M294. PIPE AND FITTINGS SHALL BE MADE FROM VIRGIN PE COMPOUNDS WHICH

- CONFORM WITH THE REQUIREMENTS OF CELL CLASS 335420C AS DEFINED AND DESCRIBED 5.) FITTINGS MAY BE EITHER MOLDED OR FABRICATED AND SHALL CONFORM TO THE REQUIREMENTS AASHTO M252 AND M294. THE FITTINGS SHALL NOT REDUCE OR IMPAIR THE OVERALL INTEGRITY OR FUNCTION OF THE PIPE LINE. ONLY FITTINGS SUPPLIED OR RECOMMENDED BY
- THE PIPE MANUFACTURER SHALL BE USED. 6.) INSTALLATION OF THE PIPE SPECIFIED ABOVE SHALL BE IN ACCORDANCE WITH THE ASTM RECOMMENDED PRACTICE D2321.
- 7.) BOTH BELL AND SPIGOT (WITH O-RING GASKET) ENDS OF THE PIPE SHALL BE LUBRICATED AS RECOMMENDED BY MANUFACTURER AND INSERTED TO THE HOMING MARK ON THE SPIGOT

8.) MINIMUM RECOMMENDED TRENCH WIDTH SHALL BE NOT LESS THAN THE GREATER OF EITHER

PIPE OUTSIDE DIAMETER PLUS 16 INCHES OR THE PIPE OUTSIDE DIAMETER TIMES 1.25, PLUS

NOMINAL PIPE	E DIAMETER	MINIMUM	TRENCH	HTOW
12" (300	mm)		31"	
15" (375	mm)		34"	
18" (450	mm)		39"	
24" (600	mm)		42"	
30" (750	nm)		58"	
36" (900	mm)		66"	
42" (105	0mm)		71"	

DUCKETT CREEK SANITARY DISTRICT CONSTRUCTION NOTES

- 1. Underground utilities have been plotted from available information and therefore location shall be considered approximate only. The verification of the location of all underground utilities, either shown or not shown on these plans, shall be the responsibility of the contractor and shall be located prior to any grading or construction of improvements.
- 2. Gas, water and other underground utilities shall not conflict with the depth or horizontal location of existing or proposed sanitary and storm sewers, including house laterals.
- 3. All existing site improvements disturbed, damaged or destroyed shall be repaired or replaced to closely match preconstruction conditions.
- 4. All fill including places under proposed storm and sanitary sewer lines and paved areas including trench backfills within and off the road right—of—way shall be compacted to 90 percent of maximum density as determined by the "Modified AASHTO T-180" Compaction Test (ASTM D1557)". All tests shall be verified by a Soils Engineer concurrent with grading and backfilling operations. The compacted fill shall be free of rutting and shall be non-yielding and non-pumping during procfrolling and compaction.
- 5. The contractor shall prevent all storm, surface water, mud and construction debris from entering the existing sanitary sewer system
- 6. All sanitary sewer flowlines and tops built without elevations furnished by the engineer will be the responsibility
- of the sewer contractor. 7. Easements shall be provided for all sanitary sewers, storm sewers and all utilities on the record plat.
- 8. All construction and materials shall conform to the current construction standards of the Duckett Creek Sanitary District. 9. The Duckett Creek Sanitary District shall be notified at

least 48 hours prior to construction for coordination of

10. All sanitary sewer building connections shall be designed so that the minimum vertical distance from the low point of the basement to the flowline of a sanitary sewer at the corresponding building connection shall not be less than the diameter of the

specification 10 CSR-8.120(7)(E).

inspection.

- pipe plus the vertical distance of 2-1/2 feet. 11. All sanitary sewer manholes shall be waterproofed on the exterior in accordance with Missouri Dept. of Natural Resources
- 12. All PVC sanitary sewer pipe shall conform to the requirements of ASTM D-3034 Standard Specification for PSM Polyvinyl Chloride Sewer Pipe, SDR-35 or equal, with "clean" 1/2 inch to 1 inch granular stone bedding uniformly graded. This bedding shall extend from 4 inches below the pipe to springline of pipe. Immediate backfill over pipe shall consist of same size "clean" or "minus" stone from springline of pipe to 6 inches above the
- 13. All sanitary and storm sewer trench backfills shall be water jetted. Granular backfill will be used under pavement areas.
- 14. All pipes shall have positive drainage through manholes. No flat invert structures are allowed.
- 15. All creek crossings shall be grouted rip—rap as directed by District inspectors. (All grout shall be high slump ready-mix concrete).
- 16. Brick shall not be used on sanitary sewer manholes.

Existing sanitary sewer service shall not be interrupted.

- 18. Maintain access to existing residential driveways and streets. 19. Pre-manufactured adapters shall be used at all PVC to DIP
- connections. Rubber boot / Mission—type couplings will not be allowed. 20. Any permits, licenses, easements, or approvals required to

work on public or private properties or roadways are the

responsibility of the developer. 21. 'Type N' Lock-Type Cover and Locking Device (Lock-Lug) shall

be used where lock-type covers are required.

COTTLEVILLE FIRE PROTECTION DISTRICT NOTES

- 1. The fire department connection will be located within 150-ft. of a fire hydrant.
- See Fire Sprinkler Site Plan by others.

Standard Threads.

- 2. See site plan for watermain sizes. 3. The minimum fire flow from a single fire hydrant shall be two thousand
- (2000) gallons per minute at twenty (20) psi residual pressure. 4. Each fire hydrant shall have not less than two 2 1/2 inch outlets and one 4 1/2 inch outlet, a 5 1/4 inch valve, a 6 inch barrel and shall be of the breakaway
- 5. Each fire hydrant shall be provided with a control valve in the hydrant connection such that the hydrant can be removed from service without

shutting off water supply to other fire hydrants.

STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. AND

SERVICES PROVIDED BY OTHERS TO IMPLEMENT THE

IMPROVEMENTS SHOWN ON THIS PLAN AND ALL OTHER

DRAWINGS WHERE THE UNDERSIGNED ENGINEER'S SEAL

APPEARS. THE CONSTRUCTION MEANS AND METHODS ARE

THE SOLE RESPONSIBILITY OF THE OWNER AND CONTRACTO

STOCK AND ASSOCIATES CONSULTING ENGINEERS, "AC. HA

NO RESPONSIBILITY TO VERIFY FINAL IMPROJEMENTS AS SHOWN ON THIS PLAN UNLESS SPECIFICALL: ENGAGED AND

design, frost free with chain, left hand open design and have National

- 6. The fire hydrants will be set to the final grade, not less than 18—in. from center of a hose nozzle outlet to finish grade.
- 7. There shall be no obstruction, i.e., plantings, bushes, trees, signs, light standards, mailboxes, etc. within six (6) feet of any fire hydrant, and or fire department connection to an automatic sprinkler system.


THE UNDERSIGNED ENGINEER HAVE NO RESPONSIBILITY FOR /2 10/07/05 — REVISED PER REVIEW/CLIENT COMMENTS

8. The hydrants on the system side of the detector check/meter vault will be private and painted red.

DETECTOR CHECK VAULT FOR 4",6",8" FIRE SERVICES

1 9/27/05 - REVISED PER MODOT COMMENTS SOAVE AUTOMOTIVE @ WELDON POINT

SPECIFICATION SHEET



Consulting Engineers, Inc.

3 10/20/05 - REVISED PER REVIEW COMMENTS

St. Lauis. MD 63005 PH. (636) 530-9100 FAX (636) 530-9130 e-mail: gereral@stockessoc.com Web: www.stockassoc.com

257 Chesterfield Business Parkway

box. For services smaller than 4" in size, flexible Type "K" copper is required through the stop box. After the stop box, flexible or rigid Type "K" or "I" copper is required to four feet beyond the meter box. For larger services, ductile iron pipe should run from the main to a point at least six feet beyond the meter box. From the building foundation, copper or ductile iron pipe must extend a minimum of ten feet outside the building wall. Once a fire line is past a detector check meter it is considered to be metered and any materials can be used that comply with the local plumbing codes (C-900 PVC is the minimum). A "Master Service"

4. The joints on copper service lines (excluding joints on pre-purchased "meter setters" shall be either flared, compression, or silver soldered. 5. Existing services will have to be destroyed at the main unless they are being reused.

Permission to reuse a service (either permanently or temporarily) must come from

the District Supervisor. 6. Missouri American Water does not own, operate, or maintain service lines. As a general rule St. Louis Co. Water does not run a water main extension on a

project which can be served by a service line.

M.A.W.C. WATER LINE NOTES

1. The service connection will require the plumber to purchase a top at least

The only fee is the actual cost of the tap itself. The tapping fee is

year's actual costs.

would not metered.

substantial building construction.

two weeks prior to when he needs it. As a general rule Missouri American Water Co. makes the taps in the order in which they are received, and cannot

the plumber has to schedule it with the District Supervisor. The plumber has

to have all required information, plus Missouri American Water requires two sets of a site plans showing the proposed layout and valving. Along with this Missouri

different for every combination of pipe size and tap size and is based on previous

2. The footing of the building must be in before Missouri American Water Co. will make

3. A minimum Class 52 ductile iron pipe, conforming to applicable AWWA standards, is required on any service line that is 4" or greater in size before a meter.


Copper piping is required for smaller services from the main through the meter

a tap. Missouri American Water does not make taps for vacant lots or previous to


American Water Co. can insure that they are able to provide the required flow.


guarantee two weeks during a busy time of the year. Once the tap is purchased


7. Missouri American Water Co. requires a detector check valve on all fire protection lines for sprinkler systems. They also require a detector check valve on fire hydrants, with the possible exception of hydrants that are immediately adjacent to and visible from public street Missouri American Water also requires valves on both fire and domestic lines after they split from a combined service. Thus a typical split service would have valves on both fire and damestic lines after a tee. Of course this would also require a valve on a line going to a fire hydrant that come off of a "Master Water Service".





METER BOX FOR 1 1/2 "-2" & 2 1/2 " SERVICES





















Area Area(A) No.* (Acres)*		P.I. Factor 100 yr, 20 min.	Flow (Q=PlxA) (cfs)	Onsite Q to Pond & Overflow (cfs)
1	0.6	2.29	1.37	1.37
2	0.23	4.77	1.10	1.10
2 3	0.45	4.77	2.15	2.15
4	0.31	4.77	1.48	1.48
	0.12	2.29	0.27	0.27
5	0.59	6.00	3.54	3.54
5 6	0.07	4.77	0.33	0.33
	0.03	2.29	0.07	0.07
7	0.36	4.77	1.72	1.72
7	0.09	2.29	0.21	0.21
9	0.1	2.29	0.23	to offsite detention
10	0.4	4.77	1.91	to offsite detention
11	0.32	4.77	1.53	1.53
	0.11	2.29	0.25	0.25
12	0.24	4.77	1.14	to offsite detention
13	0.09	4.77	0.43	to offsite detention
14	0.44	4.77	2.10	2.10
15	0.09	4.77	0.43	0.43
16	0.26	6.00	1.56	1.56
17	0.3	4.77	1.43	1.43
18	0.35	4.77	1.67	1.67

* From Drainage Area Map

roject na	me:	Soave Au	tomotive		Calculat	ted By:	SJK		15yr 20min																
oject ni	ımber:	204-3319			Checked	By:	GMS			- w	Bend Coefficien	's:													
oject L	ocation:	Weldon S	pring, MO		Date:		Aug 19/2	005	$5^0 = 0.06$	$20^0 = 0.24$	$35^0 = 0.4$	$50^0 = 0.50$	$65^0 = 0.57$	$80^0 = 0.65$											
	LIN	Œ	FLOW	LINE					$10^0 = 0.11$	$25^0 = 0.30$	$40^0 = 0.43$	$55^0 = 0.52$	$70^0 = 0.60$	$85^0 = 0.67$		HEAD I	LOSS		Hyd	raulic Elev	ations				
			ELEVA	ATIONS					$15^0 = 0.18$	$30^0 = 0.35$	$45^0 = 0.47$	$60^0 = 0.55$	$75^0 = 0.62$	$90^0 = 0.70$								Structure	ТОР	Free	
tructure	Upper	Lower	Upper	Lower	Length	Flowline	Pipe Siz	Full Flow	Fotal (Q)	Mean Full Flov	Bend	Velocity	QV_h	Pipe Coef.	$\mathbf{H}_{\mathbf{f}}$	Junction	Bend	Total	Upper F.I	Lower H.E	Lower H.F	-	Structure	2.000	Struc
Number		structure	structure	Structure	(ft)	Grade ft/ft	(in.)	Cap. (cfs)	(cfs)	Vel.(V) (ft/s)	Coef.	Head (Vh) (ft)	(ft^4/s)	(n)	(ft)	(ft)	(ft)	H _{mt}	+ Dia.	$+H_{\rm f}$		H.E. + H _m			Nun
			-																			AIII			
7	7	6	578.68	577.33	135.00	0.0100	12	3.57	0.32	0.41	0.00	0.00	0.00	0.013	0.01	0.00	0.00	0.00	579.68	578.34	578.33	578.69	583.00	4.31	7
6	6	5	577.33	573.53	190.00	0.0200	12	5.05	1.17	1.49	0.18	0.03	0.04	0.013	0.20	0.00	0.01	0.01	578.33	574.84	574.63	577.54	582.75	5.21	6
5	5	4	573.53	572.93	30.00	0.0200	12	5.05	2.59	3.30	0.60	0.17	0.44	0.013	0.16	0.00	0.10	0.10	574.53	574.12	573.96	574.63	582.00	7.37	5
4	4	3	572.93	570.29	132.00	0.0200	12	5.05	2.76	3.51 2.25	0.18	0.19	0.53	0.013	0.79	0.00	0.03	0.03	573.93	572.34	571.55	573.96	581.15	7.19	4
2	2	EX30	570.29 567.79	567.79 565.79	125.00 100.00	0.0200	15 15	9.16	2.76	2.25	0.70	0.08	0.22	0.013	0.23	0.00	0.01	0.01	571.54 569.04	570.37 570.08	570.14 569.90	571.55 570.14	578.00	6.45 4.86	2
											D UTILITY PLAN			0.013	0.10		ULIC GR			370.06	309.90	569.90	575.00	4.80	
LASO	171XLIV 1	ROMBI		71050011	1120(301	110.200 2	100.2, 1	ROGREDOI	OHVI ROZI	D, SEWER, AR	CILITIE		. 1 20 02			min	OLIO ON	ANDE EX	1112			307.50			
25	25	24	575.00	574.40	60.00	0.0100	12	3.57	0.15	0.19	0.18	0.00	0.00	0.013	0.00	0.00	0.00	0.00	576.00	575.42	575.42	575.43	579.65	4.22	25
24	24	23	574.40	573.66	74.00	0.0100	12	3.57	1.42	1.81	0.35	0.05	0.07	0.013	0.12	0.00	0.02	0.02	575.40	574.93	574.82	575.42	579.50	4.08	24
23	23	22	573.66	560.61	261.00	0.0500	12	7.99	4.20	5.35	0.35	0.44	1.87	0.013	3.62	0.00	0.16	0.16	574.66	567.63	564.01	574.82	579.25	4.43	23
22	22	21	560.61	558.49	50.00	0.0424	15	13.34	5.50	4.48	0.18	0.31	1.72	0.013	0.36	0.00	0.06	0.06	561.86	563.95	563.59	564.01	566.50	2.49	22
21	21	20	558.49	557.00	35.00	0.0426	15	13.36	7.09	5.78	0.00	0.52	3.67	0.013	0.42	0.00	0.00	0.00	559.74	563.59	563.17	563.59	566.10	2.51	21
20													HYDRAUL	IC GRADE I	IINE = (15 YR. PC	OND ELE	V.)				563.17			
17	17	16	575.00	574.70	30.00	0.0100	12	3.57	0.19	0.24	0.00	0.00	0.00	0.013	0.00	0.00	0.00	0.00	576.00	576 15	57615	F7C 15	570.15	2.00	1.7
17 16	16	15	574.70	573.65	105.00	0.0100	12	3.57	1.32	1.68	0.18	0.04	0.06	0.013	0.00	0.00	0.00	0.00	575.70	576.15 576.14	576.15 576.00	576.15 576.15	579.15 580.50	3.00 4.35	17 16
15	15	14	573.65	573.16	49.00	0.0100	12	3.57	3.20	4.07	0.60	0.26	0.82	0.013	0.39	0.00	0.15	0.01	574.65	575.84	575.45	576.00	579.15	3.15	15
14	14	13	573.16	571.76	140.00	0.0100	12	3.57	4.26	5.42	0.43	0.46	1.95	0.013	2.00	0.00	0.20	0.20	574.16	575.25	573.26	575.45	580.50	5.05	14
13	13	12	571.76	568.26		0.0200	15	9.16	6.59	5.37	0.55	0.45	2.95	0.013	1.82	0.00	0.25	0.25	573.01	571.33	569.51	573.26	577.20		13
12	12	11	559.50	557.00	50.00	0.0500	15	14.48	7.40	6.03	0.00	0.56	4.18	0.013	0.66	0.00	0.00	0.00	560.75	563.83	563.17	569.26	573.00		12
11													HYDRAUL	IC GRADE I	LINE = (15 YR. PC	OND ELE	V.)				563.17			
																			1						
10	10	9	556.00	555.85	30.00	0.0050	24	16.04	21.20	6.75	0.47	0.71	14.99	0.013	0.26	0.00	0.33	0.33	558.00	558.11	557.85	558.45	564.25		10
9	9	8	555.85	550.00	83.00	0.0705	24	60.22	21.20	6.75	0.00	0.71	14.99	0.013	0.73	0.00	0.00	0.00	557.85	552.73	552.00	557.85	563.00	5.15	9
8										-			HIDRAUL	LIC GRADE I	INE = (TOP OF F	TPE)					552.00			
18	18	14	574.09	573.16	93.00	0.0100	12	3.57	1.06	1.35	0.50	0.03	0.03	0.013	0.08	0.00	0.01	0.01	575.09	574.24	574.16	575.10	579.00	3.90	18
14	10	1.1	571.09	5/5,10	22100	0.0100		3.31	1.00	1.00	0.00			IC GRADE I		0.00	0.01	0.01	272.09	J/7.47	2/7,10	556.00	3/3.00	2.70	10
4 1																			700			220.00			
19	19	15	574.70	573.65	21.00	0.0500	12	7.99	1.56	1.99	0.65	0.06	0.10	0.013	0.04	0.00	0.04	0.04	575.70	574.69	574.65	575.74	579.10	3.36	19
15													HYDRAUL	IC GRADE I	INE =		-					556.00			
7																									
																						512.69			
ORMUL			W VELOC								n (Q _{in} V _{in})]x1.33/[Note:							CH BEND I				



VELOCITY HEAD:

GEORGE MICHAEL STOCK NUMBER E 25116 STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. AND THE UNDERSIGNED ENGINEER HAVE NO RESPONSIBILITY FOR SERVICES PROVIDED BY OTHERS TO IMPLEMENT THE IMPROVEMENTS SHOWN ON THIS PLAN AND ALL OTHER DRAWINGS WHERE THE UNDERSIGNED ENGINEER'S SEAL APPEARS. THE CONSTRUCTION MEANS AND METHODS ARE THE SOLE RESPONSIBILITY OF THE OWNER AND CONTRACTO STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. HA NO RESPONSIBILITY TO VERIFY FINAL IMPROVEMENTS AS SHOWN ON THIS PLAN UNLESS SPECIFICALLY ENGAGED AN AUTHORIZED TO DO SO BY THE OWNER OR CONTRACTOR.

10/07/05 - REVISED PER REVIEW/CLIENT COMMENTS 1 9/27/05 - REVISED PER MODOT COMMENTS

SOAVE AUTOMOTIVE @ WELDON POINT

STORM SEWER DETAILS/HYDRAULICS

10/20/05 - REVISED PER REVIEW COMMENTS


3. IF $QV_{h(in)} > QV_{h(out)}$, NO JUNCTION LOSES TO BE CALCULATED.


257 Chesterfield Business Parkway St. Louis, MO 63005 • PH. (636) 530-9100 FAX (636) 530-9130 e-mail: general@stockassoc.com Web: www.stockassoc.com


C6.2


Consulting Engineers, Inc. Nucl 10/20/05 DRAWN BY: GEORGE M. STOCK E-2511


204-3319















10/20/05 - REVISED PER REVIEW COMMENTS 10/07/05 - REVISED PER REVIEW/CLIENT COMMENTS 1 9/27/05 - REVISED PER MODOT COMMENTS

SOAVE AUTOMOTIVE @ WELDON POINT


SANITARY SEWER PROFILES/DETAILS


STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. AND THE UNDERSIGNED ENGINEER HAVE NO RESPONSIBILITY FOR SERVICES PROVIDED BY OTHERS TO IMPLEMENT THE IMPROVEMENTS SHOWN ON THIS PLAN AND ALL OTHER DRAWINGS WHERE THE UNDERSIGNED ENGINEER'S SEAL APPEARS. THE CONSTRUCTION MEANS AND METHODS ARE THE SOLE RESPONSIBILITY OF THE OWNER AND CONTRACTOR NO RESPONSIBILITY TO VERIFY FINAL IMPROVEMENTS AS SHOWN ON THIS PLAN UNLESS SPECIFICALLY ENGAGED AN AUTHORIZED TO DO SO BY THE OWNER OR CONTRACTOR.





257 Chesterfield Business Parkway St. Lauis, MO 63005 PH. (636) 530-9100 FAX (636) 530-9130 e-mail: general@stockassoc.com Web: www.stockassoc.com


Consulting Engineers, Inc. T.P.S. 08/22/05 G.M.S.



























SOAVE AUTOMOTIVE @ WELDON POINT


SANITARY SEWER DETAILS


STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. AND THE UNDERSIGNED ENGINEER HAVE NO RESPONSIBILITY FOR SERVICES PROVIDED BY OTHERS TO IMPLEMENT THE IMPROVEMENTS SHOWN ON THIS PLAN AND ALL OTHER DRAWINGS WHERE THE UNDERSIGNED ENGINEER'S SEAL APPEARS. THE CONSTRUCTION MEANS AND METHODS ARE THE SOLE RESPONSIBILITY OF THE OWNER AND CONTRACTO STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. H. NO RESPONSIBILITY TO VERIFY FINAL IMPROVEMENTS AS


AUTHORIZED TO DO SO BY THE OWNER OR CONTRACTOR.




257 Chesterfield Business Parkway St. Lauis, MO 63005 PH. (636) 530-9100 FAX (636) 530-9130 Consulting Engineers, Inc. e-mail: general@stockassoc.com Web: www.stockassoc.com












PLASTIC MAIN






SOAVE AUTOMOTIVE @ WELDON POINT

SANITARY SEWER DETAILS







257 Chesterfield Business Parkway St. Louis, MO 63005 PH. (636) 530-9100 FAX (636) 530-9130

Consulting Engineers, Inc. e-mail: general@stockassoc.com Web: www.stockassoc.com

